



Industrie Service

Choose certainty.
Add value.

Verification Report

Danish Energy Agency

First Periodic Verification of the JI Track 1 Project
“Energy efficiency improvement of the
district heating system in Drobeta Turnu-Severin”

Monitoring period: 01-01-2008 to 31-12-2008

Report No. 600500382-2

03 June 2010

TÜV SÜD Industrie Service GmbH
Carbon Management Service
Westendstrasse 199 - 80686 Munich - GERMANY

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Page 1 of 18

Report No.	Date of first issue	Version No.:	Revision date	No. of pages
600500382-2	16-04-2010	03	03-06-2010	18
Subject:			First Periodic Verification	
Executing Operational Unit:				
TÜV SÜD Industrie Service GmbH, Carbon Management Service Westendstrasse 199 - 80686 Munich, Federal Republic of Germany				
Project Participant (client):				
<ol style="list-style-type: none"> 1. Ministry of Climate and Energy Danish Energy Agency Amaliegade 44 DK-1256; Copenhagen K; Denmark 2. ROMAG TPP 				
Registration number / Project Title			Project: “Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin”	
Monitoring period:			01-01-2008 to 31-12-2008	
First Monitoring Report (version/date)			Version 01 / 18-09-2009	
Final Monitoring Report (version/date)			Version 03 / 07-01-2010	
Summary:				
<p>TÜV SÜD Industrie Service GmbH has performed the first periodic verification of the JI project: “Energy efficiency improvement of the district heating system in Drobeta Turnu Severin”. The project consists of 38 heat conversion substations connected to the secondary network of the Drobeta Turnu-Severin district heating system operated by ROMAG Thermo PP. The total length of the secondary networks pipework is approximately 175 km including heating and hot portable water distribution. Heat to the network is provided by the ROMAG Thermo PP CHP plant that is equipped with 6 boiler units and 6 turbines.</p> <p>The management of ROMAG Thermo PP is responsible for the preparation of the GHG emissions data and the reported GHG emission reductions.</p> <p>A document review, followed by a site visit was conducted to verify the information submitted by the project participant regarding the present verification period. Based on the assessment carried out, the verifier confirms the following:</p> <ul style="list-style-type: none"> • that the project has been implemented and operated in accordance with the description given in the PDD (version 08, 07 11 2009). http://ji.unfccc.int/JIITLProject/DB/09PG38GL1EVUCD8D8JUNQEI4RPHUVJ/details • that the project is completely implemented as described in the PDD. • that the monitoring plan complies with the project specific methodology (described in the PDD) and the monitoring has been carried out in accordance with the monitoring plan. Installed equipment essential for generating emission reductions run reliably and the meters are calibrated appropriately. The project is generating emission reductions as a JI project. <p>The verifier can confirm that the GHG emission reductions are calculated without material misstatements. Our opinion refers to the project’s GHG emissions and resulting GHG emission reductions reported, both determined using the valid project’s baseline, its monitoring plan and its associated documents.</p> <p>Based on the information we have seen and evaluated, we confirm that the implementation of the project resulted in 110.054 t CO_{2e} of emission reductions (ERUs) during the verification period 01-01-2008 to 31-12-2008.</p> <p>A possibility of double counting of ERs is also excluded as clearly stated in §8 of the LoA from the Romanian DFP.</p>				

	TÜV SÜD Industrie Service GmbH Carbon Management Service	
	Westendstraße 199 80686 München	Tel.: 089 5791-2246 Fax: 089 5791-2756

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta
Turnu-Severin (2008)”



Industrie Service

Page 2 of 18

<p>Assessment Team Leader: Thomas Kleiser</p> <p>Assessment Team Members: Auditor Steffen Klein Expert Constantin Zaharia</p> <p>Project Manager: Georgios Agrafiotis</p>	<p>Veto Person:</p> <p>Certification Body responsible: Rachel Zhang Deputy Head of Certification Body</p>
--	---



Abbreviations

ACM	Approved Consolidated Methodology
CAR	Corrective Action Request
CDM	Clean Development Mechanism
CDM-EB	CDM Executive Board
CER	Certified Emission Reduction
CMP	Conference of the Parties serving as the Meeting of the Parties to the Kyoto Protocol
CO_{2e}	Carbon dioxide equivalent
CR / CL	Clarification Request
DNA	Designated National Authority
DOE	Designated Operational Entity
EF	Emission Factor
EIA / EA	Environmental Impact Assessment / Environmental Assessment
ER	Emission Reduction
FAR	Forward Action Request
FSR	Feasibility Study Report
GHG	Greenhouse Gas(es)
GWP	Global Warming Potential
IPCC	Intergovernmental Panel on Climate Change
IRL	Information Reference List
KP	Kyoto Protocol
MP	Monitoring Plan
MR	Monitoring Report
NGO	Non-Governmental Organisation
PDD	Project Design Document
PP	Project Participant
TÜV SÜD	TÜV SÜD Industrie Service GmbH
UNFCCC	United Nations Framework Convention on Climate Change
VVM	Validation and Verification Manual
VP	Verification Protocol

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta
Turnu-Severin (2008)”



Industrie Service

Page 4 of 18

Main Documents (referred to in this report)

Methodology (name / version)	N/A	
Scope	3 (Energy demand)	
Technical Area	3.1 (Heat and Steam efficiency)	
PDD:	Version 08. 07 11 2009	
Revised Monitoring Plan:	N/A	
	Version	Date
Published Monitoring Report	01	18-09-2009
Revised Monitoring Report	03	07-01-2010
Project documentation link:		

Table of Contents**Page**

1	Introduction	5
1.1	Objective	5
1.2	Scope	5
1.3	GHG Project Description.....	5
2	Methodology.....	7
2.1	Verification Process	7
2.2	Verification Team	7
2.3	Review of Documents	8
2.4	On-site Assessment and follow-up Interviews	8
2.5	Quality of Evidence to Determine Emission Reductions	8
2.6	Resolution of Clarification and Corrective and Forward Action Requests	9
2.7	Internal Quality Control	9
3	Verification Results	10
3.1	FARs from Determination / Previous Verification.....	10
3.2	Project Implementation in accordance with the registered Project Design Document.	10
3.3	Compliance of the Monitoring with the Monitoring Plan.....	10
3.4	Assessment of Data and Calculation of Greenhouse Gas Emission Reductions	14
4	Summary of Findings	15
5	Verification Statement.....	18

Annex 1: Verification Protocol

Annex 2: Information Reference List

PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin” (2008)



Industrie Service

1 INTRODUCTION

1.1 Objective

Danish Energy Agency has commissioned an independent verification by TÜV SÜD Industrie Service GmbH (TÜV SÜD) of its registered JI track 1 project: “Energy efficiency improvement of the district heating system in Drobeta Turnu Severin”.

The objective of the verification work is to comply with the requirements of paragraph 62 of the CDM Modalities and Procedures and with the Decision 9 (JI Guidelines) issued in COP/MOP 1 Montreal 2005. The JI DVM was also used as guidance for the verification since it came into force in the mean time. Finally national requirements of Romania as they are described in the Romanian National JI Track I Procedure have been taken under consideration.

According to this assessment TÜV SÜD shall:

- ensure that the project activity has been implemented and operated as per the PDD “Energy efficiency improvement of the district heating system in Drobeta Turnu Severin” Version 08, 07-11-2009, and that all physical features (technology, project equipment, monitoring and metering equipment) of the project are in place as described in the PDD.
<http://ji.unfccc.int/JIITLProject/DB/09PG38GL1EVUCD8D8JUNQEI4RPHUVJ/details>
- ensure that the published MR and other supporting documents provided are complete, verifiable and in accordance with applicable JI requirements,
- ensure that the actual monitoring systems and procedures comply with the monitoring systems and procedures described in the monitoring plan and the registered PDD.

1.2 Scope

The verification scope encompasses an independent and objective review and ex-post determination of the monitored reductions in GHG emissions by the Accredited Independent Entity. The verification is based on the submitted monitoring report, the determined project design documents including its monitoring plan and determined report, the applied monitoring methodology, relevant decisions, clarifications and guidance from the CMP and the JISC and any other information, references and national regulations relevant to the project activity’s resulting emission reductions. These documents are reviewed against the requirements of the Kyoto Protocol, the JI Modalities and Procedures and related rules and guidance.

Based on the requirements in the JI DVM, TÜV SÜD has applied a rule-based approach for the verification of the project. The principles of accuracy, completeness, relevance, reliability and credibility were combined with a conservative approach to establish a traceable and transparent verification opinion.

The verification considers both quantitative and qualitative information on emission reductions.

The verification is not meant to provide any consultancy towards the client. However, stated requests for clarifications, corrective and/or forward actions may provide input for improvement of the monitoring activities.

1.3 GHG Project Description

Project activity: “Energy efficiency improvement of the district heating system in Drobeta Turnu Severin”

UNFCCC registration number: RO1000133

UNFCCC link: http://ji.unfccc.int/JI_Parties/DB/5T6DPV4N47Z6OW3HI1GX0QKFOUI6YL/viewDFP

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Page 6 of 18

Project Participants: ROMAG TPP, Regia Autonoma pentru Activitati Nucleare – RAAN – project owner represented by the Director GABRIEL BALACI

Danish Energy Agency, Danish Ministry of Climate and Energy represented by Inge Gerhardt Pedersen, Chief Programme Coordinator for Romania

Location of the project: Latitude 44°40 min 25.5 N, Longitude 22°41 min 18 E

Date of registration as Track 1: 02-04-2010

<http://ji.unfccc.int/JIITLProject/DB/09PG38GL1EVUCD8D8JUNQEI4RPHUVJ/details>

Starting date of the JI crediting period: 01-01-2008

After ROMAG TPP took over the district heating system from the municipality in 2003, the power plant initiated a number of activities in order to improve the overall efficiency of heat and hot portable water supply to consumers.

The JI Track 1 project activity focuses on the heat conversion part of the heat conversion substations and the secondary district heating network for supply of heat and hot portable water. In this context the project includes the a redesign of the secondary district heating network and a subsequent replacement in total of approximately 190 km of heat and hot portable water pipes by new pre-insulated district heating pipes. Moreover the project comprises the installation of 114 new heat exchangers in 38 heat conversion substations located within the secondary district heating network. In connection with the rehabilitation work, heat metering devices have been installed at the heat conversion substation to meter the heat and hot portable water consumption side.

The district heating network rehabilitation project reduces heat and water losses within the secondary district heating network and the heat conversion substations connected to primary network. Bottom up this leads to the fuel consumption reduction at the ROMAG – TERMO CHP power plant and effects a reduction of the annual greenhouse gas emissions of the coal fiered plant.

Besides greenhouse gas emission reductions, there is expected to be a decrease of local dust and particle pollution from lignite transportation and combustion in association with the proposed project activity.

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Page 7 of 18

2 METHODOLOGY

2.1 Verification Process

The verification process is based on the approach depicted in the Determination and Verification Manual.

Standard auditing techniques have been adopted for the verification process. The verification team performs first a desk review, followed by an on-site visit, which results in the formation of a protocol that includes all the findings. The next step involves the evaluation of the findings through direct communication with the PPs and then finally the preparation of the verification report. This verification report and other supporting documents then undergo an internal quality control by the CB “climate and energy” before submission to the client, the Danish Energy Agency (DEA).

2.2 Verification Team

The appointment of the verification team takes into account the technical area(s), sectoral scope(s) and relevant host country experience required amongst team members for verifying the ER achieved by the project activity in the relevant monitoring period for this verification.

The verification team consisted of the following members:

Name	Qualification	Coverage of scope	Coverage of technical area	Host country experience
Thomas Kleiser	ATL	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Steffen Klein	GHG-A	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Constantin Zaharia	T	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Georgios Agrafiotis	GHG-T	<input checked="" type="checkbox"/>		

Thomas Kleiser is a lead auditor for CDM and JI projects at TÜV SÜD Industrie Service GmbH and head of CDM/JI division within TÜV SÜD. In this position he is responsible for the implementation of validation and certification processes for GHG mitigation projects. He has participated in more than 100 CDM and JI project assessments.

Steffen Klein is an appointed auditor for CDM and JI projects of the CB “climate and energy” of TÜV SÜD Industrie Service GmbH. The experience in CDM and JI projects he has gained (determination and verification) by participation in projects in Russia, Poland, Czech Republic, Pakistan and Colombia. As a graduated engineer he is an expert in the field of energy systems performing energy consultancy and certification services. Working for TÜV SÜD over 12 years he is a lead auditor in EU-ETS since 2004.

Constantin Zaharia is an environmental expert and expert for projects in South – East Europe working as associate for “TÜV SÜD Carbon Management Service”. Being a trainee for qualifying as GHG-auditor he has already been involved in several CDM/JI activities, including the host country for this JI project. In this moment he is accredited for 5 scopes (1, 4, 5, 10, 13).

Georgios Agrafiotis is environmental engineer. He has work experience in the field of industrial environmental technology and protection and also in technical environmental projects. As GHG trainee he has been appointed scopes 1, 5 and 13 as per UNFCCC definition.

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Page 8 of 18

2.3 Review of Documents

The Monitoring Report version 01 submitted by the PP on 18/09/2009 and was assessed based on all the relevant documents as listed above. The aim of the assessment in the desk review was to:

- verify the completeness of the data and the information presented in the MR,
- check the compliance of the MR with respect to the monitoring plan depicted in the registered PDD. Particular attention to the frequency of measurements, the quality of the metering equipment including calibration requirements, and the quality assurance and quality control procedures was paid,
- evaluate the data management and the quality assurance and quality control system in the context of their influence on the generation and reporting of emission reductions.

A complete list of all documents reviewed is available in annex 2 of this report.

2.4 On-site Assessment and follow-up Interviews

During 14-10-2009 to 15-10-2009, TÜV SÜD performed a physical site inspection and on-site interviews with project stakeholders to:

- confirm the implementation and operation of the project,
- review the data flow for generating, aggregating and reporting the monitoring parameters,
- confirm the correct implementation of procedures for operations and data collection,
- cross-check the information provided in the MR documentation with other sources,
- check the monitoring equipment against the requirements of the PDD including calibrations, maintenance etc.
- review the calculations and assumptions used to obtain the GHG data and ER,
- identify if the quality control and quality assurance procedures are in place to prevent or correct errors or omissions in the reported parameters.

A list of the persons interviewed during this verification activity is included in annex 2.

2.5 Quality of Evidence to Determine Emission Reductions

Among several evidence items submitted, the following relevant and reliable evidence material have been used by the audit team during the verification process:

1. Monitoring report for 2008
2. Monitoring Plan, Guidelines and Procedures
3. JI Process Data Log Sheets 2008, Monthly reports
4. Calibration protocols
5. Determination of fuel parameters
6. Training evidences
7. Process control equipment (data collection)
8. Quality assurance procedures of all relevant processes

Sufficient evidence covering the full verification period in the required frequency is available to validate the figures stated in the final MR. The source of the evidence will be discussed in chapter 3 of this report. Specific cross-checks have been done in cases that further sources were available. The monitoring report's figures were checked by the audit team against the raw data. The data

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Page 9 of 18

collection system meets the requirements of the monitoring plan as per the project specific methodology.

2.6 Resolution of Clarification and Corrective and Forward Action Requests

The objective of this phase of the verification process is to resolve any outstanding issues which require clarification for TÜV SÜD's positive conclusion of the achieved GHG emission reduction. The findings raised as Forward Action Requests (FARs) (if any) indicated in previous reports (determination/verification) were discussed during communications between the PP and TÜV SÜD.

To guarantee the transparency of the verification process, the concerns raised in the desk review, the on-site audit assessments and the follow up interviews together with the responses that have been provided by the PP are documented in Annex 1 (verification protocol).

A Corrective Action Request is raised where TÜV SÜD identifies:

- non-conformities in monitoring and/or reporting with the monitoring plan and/or PDD;
- that the evidence provided is not sufficient to prove conformity;
- mistakes in assumptions, data or calculations that impair the ER;
- FARs stated during determination that are not solved until the on-site visit.

A Clarification Request is raised where TÜV SÜD does not have enough information or the information is not clear in order to confirm a statement or data.

A Forward Action Request is raised where TÜV SÜD identifies that monitoring and/or reporting require special attention or adjustments for the next verification period.

Information or clarifications provided as a response to a CAR, CL or FAR could also lead to a new CAR.

2.7 Internal Quality Control

As a final step of verification, the final documentation including the verification report and annexes have to undergo an internal quality control by the Certification Body (CB) “climate and energy”, i.e. each report has to be finally approved either by the Head of the CB or the Deputy (a Veto person can be used). In case one of these two persons is part of the assessment team, the approval can only be given by the person who is not a part of the assessment team. If the documents have been satisfactorily approved, the Final Verification Report is submitted to the Danish Energy Agency along with the relevant documents.

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Page 10 of 18

3 VERIFICATION RESULTS

In the following sections, the results of the verification are stated. The verification results relate to the project performance as documented and described in the final PDD and Monitoring Report (07-01-2010, version 03). The verification findings for each verification subject are presented below:

3.1 FARs from Determination / Previous Verification

The verification team confirms that all FARs presented in the determination report have been correctly addressed by the PPs.

3.2 Project Implementation in accordance with the Project Design Document

The project was implemented in phases since October 2006, finished before the end of the year 2007. When finishing a relevant phase this part is completely operational.

The project is fully implemented according to the description presented in the registered PDD.

The project includes the redesign of the secondary district heating network and a subsequent replacement of in total approximately 190 km of heat and hot portable water pipes by new pre-insulated district heating pipes. Moreover the project comprises the installation of 114 new heat exchangers in 38 heat conversion substations located within the secondary district heating network.

The verifier confirms, through the visual inspection, that all physical features of the proposed JI project activity including data collecting systems and storage have been implemented in accordance with the PDD. The project activity is completely operational since finalizing the last phase in December 2007.

There is no difference between the values of the data and/or variables presented in the MR and the stated data in the PDD. The project activity is completely operational since finalizing the last phase in December 2007.

The estimated ERs in the registered PDD with annual 83.868 t CO_{2e} meets the ER achieved in 2007. This real amount of ER achieved in 2007 was used for estimation of the annual ER during the crediting period of the project.

Because the project was implemented in phases during the monitoring period 2007 in the monitoring period 2008 the result with 110.054 t CO_{2e} ER is higher than it was estimated in the approved PDD. This is caused by an increasing absolute efficiency when implementing a further phase in the frame of the project boundary.

The project was completely implemented before the monitoring period 2008 started.

3.3 Compliance of the Monitoring with the Monitoring Plan

The monitoring has been carried out in accordance with the monitoring plan contained in the PDD. All parameters were monitored and determined as per the Monitoring Plan.

The verification of the parameters required by the monitoring plan is provided as follows:

Data / Parameter:	$Q_{P, DH, primary}$
Data unit:	Gcal
Description:	District heat supplied to the primary network
Source of data used:	Recordings in logbooks are archived in paper form, the values of the daily reports are put into an excel spreadsheet prepared for one month. The project relevant data of one month are summarized in a JI Process Data Log Sheet. The equipment used has been calibrated according to the requirements of the

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Means of verification/Comments:	approved monitoring plan. Monthly reports issued by the JI-Department of ROMAG TPP for the full monitoring period have been provided. This reports were checked with monthly reports and related samples of daily records issued by the Heat Production Department. (May/November 2008). No discrepancies have been found and all data are consistent to the calculation tool.
Cross-check	The parameter that can be used for plausibility crosscheck is the calculated system efficiency of primary network in the Monitoring Excel Spreadsheet Tool. The efficiency is related to total amount of heat delivered to the primary network.

Data / Parameter:	$Q_{P,ps}$
Data unit:	Gcal
Description:	Process steam produced for heavy water producers
Source of data used:	Continuous measuring system transferring data hourly to the TPP central control room (digital). Data were also manually recorded in the logbook and logged for the day The equipment used has been calibrated according to the requirements of the approved monitoring plan.
Means of verification/Comments:	Monthly reports issued by the JI-Department for the full monitoring period have been provided. This reports were checked with monthly reports and related samples of daily records issued by the Heat Production Department. (May/November 2008). No discrepancies have been found and all data are consistent to the calculation tool.
Cross-check	Calculation can be crosschecked by monthly or annual heat balances between fuel consumption and total heat production considering the thermal efficiency of the boilers.

Data / Parameter:	$Q_{P,DH,HCS}$
Data unit:	Gcal
Description:	District heat supplied to heat conversion substations
Source of data used:	Data are collected manually and automatically, acquired and stored with the SCADA-System, every hour and logged for the day. The equipment used has been calibrated according to the requirements of the approved monitoring plan.
Means of verification/Comments:	Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool.
Cross-check	Calculation can be crosschecked with the heat supplied to consumers considering the efficiency of HCS.

Data / Parameter:	$Q_{P,DH,pr.con}$
Data unit:	Gcal
Description:	District heat supplied to consumers connected to the primary network
Source of data used:	Data are collected manually monthly.
Means of verification/Comments:	Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool. Approved monthly reports for the full monitoring period have been supplied
Cross-check	Calculation can be crosschecked with the general heat balance of power plant and supplied networks.

Data / Parameter:	$Q_{P,DH,secondary}$
--------------------------	----------------------

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Data unit:	Gcal
Description:	District heat supplied to secondary network
Source of data used:	Data are collected manually and automatically, acquired and stored with the SCADA-System, every hour and logged for the day.
Means of verification/Comments:	Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool. Approved monthly reports for the full monitoring period have been supplied
Cross-check	Calculation can be crosschecked with the heat supplied to single consumers connected to the HCS.

Data / Parameter:	$Q_{P,DH,consumers}$
Data unit:	Gcal
Description:	District heat supplied to consumers connected to the secondary network
Source of data used:	Data are collected manually monthly.
Means of verification/Comments:	Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool. Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.
Cross-check	Calculation can be crosschecked with the heat supplied to secondary network considering the efficiency of the secondary network.

Data / Parameter:	$Q_{P,DH,pr.new_con}$
Data unit:	Gcal
Description:	District heat supplied to new consumers connected to the primary network
Source of data used:	Data are collected manually monthly.
Means of verification/Comments:	Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool. Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied. New customers will be separately monitored and documented as foreseen in the registered PDD.
Cross-check	Calculation can be crosschecked with the balance of total heat supplied to primary network considering the efficiency of primary network.

Data / Parameter:	$Q_{P,DH,sec.new_con}$
Data unit:	Gcal
Description:	District heat supplied to new consumers connected to the secondary network
Source of data used:	Data are collected manually monthly.
Means of verification/Comments:	Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool. Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied. New customers will be separately monitored and documented as foreseen in the registered PDD.
Cross-check	Calculation can be crosschecked with the balance of total heat supplied to secondary network considering the efficiency of secondary network.

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Data / Parameter:	$CV_{P,lignite}$
Data unit:	Kcal/kg
Description:	Net calorific value of lignite
Source of data used:	Onsite analysis manufacturer
Means of verification/Comments:	Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the Technical Department. The accreditation of the laboratory was checked and results of analyses were crosschecked with monthly reported values.
Cross-check	A second analyse from each delivery is made by ROMAG TPP laboratory. In case of a deviation a backup witness sample will be analysed by both. Net calorific value of lignite is one component for the calculation of the boiler applied fuel heat. The general energy balance of the power plant that is done anyway gives the possibility of crosscheck in combination with the amount of fired lignite.

Data / Parameter:	$CV_{P,oil}$
Data unit:	Kcal/kg
Description:	Net calorific value of oil
Source of data used:	Onsite analysis manufacturer
Means of verification/Comments:	Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the Technical Department. The accreditation of the laboratory was checked and results of analyses were crosschecked with monthly reported values.
Cross-check	Net calorific value of fuel oil is one component for the calculation of the boiler applied fuel heat. The balances of the boilers, only fired with oil, give the possibility of crosscheck in combination with the amount of fired oil.

Data / Parameter:	$V_{P,lignite}$
Data unit:	T
Description:	Quantity of lignite consumed
Source of data used:	invoices, weight sheets, stock survey
Means of verification/Comments:	The total amount of delivered lignite is weighted and invoiced. Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the Technical Department. No discrepancies have been found and all data are consistent to the calculation tool.
Cross-check	The amount of consumed lignite is one component for the calculation of the boiler applied fuel heat. The general energy balance of the power plant that is done anyway gives the possibility of crosscheck in combination with the net calorific value of lignite.

Data / Parameter:	$V_{P,oil}$
Data unit:	T
Description:	Quantity of oil consumed
Source of data used:	invoices, weight sheets, tank level
Means of verification/Comments:	The total amount of delivered oil is weighted and invoiced. Monthly mass balances are representative in accordance with the produced and measured heat. Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the Technical Department. No discrepancies have been found and all data are consistent to the calculation tool.

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta
Turnu-Severin (2008)”



Industrie Service

Page 14 of 18

Cross-check	The amount of consumed oil is one component to calculate the fuel heat applied by the boiler. The balances of the boilers, only fired with oil, give the possibility of crosscheck in combination with the net calorific value of fired oil.
-------------	--

3.4 Assessment of Data and Calculation of Greenhouse Gas Emission Reductions

All data have been available and all the parameters have been monitored in accordance with the monitoring plan.

The reported data have been cross-checked against other sources available as explained above in chapter 3.3.

The verifier confirms that the methods and formulae used to obtain the baseline, project and leakage emissions are appropriate. The same has been done in accordance with the methods and formulae described in the monitoring plan and PDD.

The verifier confirms that all the emission factors and default values (ex-ante values from PDD) have been correctly justified. All the emission factors and default values are explicitly mentioned in the monitoring report.

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Page 15 of 18

4 SUMMARY OF FINDINGS

The verifier can confirm that the MR and related documents are complete and verifiable in accordance with the JI Track 1 requirements. All the findings raised by the verification team, the responses by the PPs and the conclusion from the team are presented in Annex 1. The means of verification and resulting changes in the MR or related documents are identified in the following table:

CAR 1: GSP coordinates of the project site have to be included in the PDD
CAR 1, means of verification
This information has been evaluated with the information on site.
CAR 1, changes in the MR or related documents
GSP coordinates of the project site have been added in the PDD, v.8, that is an update of determined PDD, v.7 with only formal changes. This was a required addition without an effect of project determination.

CAR 2: The Parameter IDs for "District heat supplied to new consumers connected to the primary network" and "District heat supplied to new consumers connected to the secondary network" has to be included in the Monitoring Protocol, sheet: INPUT DATA_NEW CONNECTIONS.
CAR 2, means of verification
Updated MR spreadsheet was checked.
CAR 2, changes in the MR or related documents
The parameter $Q_{P,DH,pr.new_con}$ was added to the MR spreadsheet at the top of the relevant column.

CAR 3: The order of all parameter descriptions mentioned in the MR should follow PDD and Monitoring Manual.
CAR 3, means of verification
Updated MR was checked against PDD and Monitoring Manual.
CAR 3, changes in the MR or related documents
The order of parameters in the MR is now corresponding to the PDD and Monitoring Manual.

CAR 4: The assignment of the values for molar masses of C and CO ₂ has to be changed in the PDD (beginning at page 30) and in the Calculation tool ANNEX 5_EMISSION FAKTOR DATA.
CAR 4, means of verification
Updated PDD and MR was checked that twisted molar masses of C and CO ₂ were corrected.
CAR 4, changes in the MR or related documents
The values of molar masses C and CO ₂ have been changed correspondingly in PDD and Calculation tool 2007. This was only a formal correction without any effect of project determination because the right values were used for calculation.

CAR 5: The emission factors for the specific fuels refer to "Revised 2006 IPCC Guidelines", not to the revision of 1996. That has to be changed, see PDD page 31.
CAR 5, means of verification
PDD V 8, updated with formal changes, was checked.
CAR 5, changes in the MR or related documents
The noted reference was changed accordingly in the PDD. The right corresponding values to "Revised 2006 IPCC Guidelines" have been used already.

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta
Turnu-Severin (2008)”



Industrie Service

Page 16 of 18

CAR 6: Please describe all the parameters mentioned in the MR (2.3. – 2.13.) more clearly, including why the parameter is reported and how it is considered in the calculation. Correct the description under 2.12 and include the announcement of the project emissions.

CAR 6, means of verification

Updated MR was checked regarding a extended and clearely description of parameters.

CAR 6, changes in the MR or related documents

Revised monitoring report 2007 (rev. 1) dated 07 November 2009 includes a more transparent description of all parameters.

CAR 7: Please indicate the issuing date and the corresponding version number at the Front Page sheet of the Excel MR calculation tools.

CAR 7, means of verification

Updated MR Calculation tool was checked.

CAR 7, changes in the MR or related documents

With the provided Version No.3 the front page was edited. Issuing date and the corresponding version number have been added.

CAR 8: Emissions and emission reductions are not mentioned or described in the MR. Due to the Monitoring Plan (IRL No.5, 3.1.6) and the requirements they must be added to the MR.

CAR 8, means of verification

Updated MR was checked regarding these changes

CAR 8, changes in the MR or related documents

With the provided Version No.3 the emissions calculated in the tool have been implemented in the report.

CAR 9: Please indicate the issuing date and version number at the Monitoring Reports.

CAR 9, means of verification

Updated MR was checked regarding these changes.

CAR 9, changes in the MR or related documents

With the provided Version No.3 the issuing date and version number are indicated at the front page of the Monitoring Reports.

CR 1: The situation stated in the PDD regarding backpressure turbines is different to the MR (2.1).

CR 1, means of verification

The situation was clarified with the verified situation onsite and the provided Turbine technical features in IRL 6 - ROMAG TERMO TPP - Main Equipment Technical Features

CR 1, changes in the MR or related documents

There are two backpressure turbines installed. The description in the PDD was updated in V8. The revisions in the PDD do not effect the former determination but refer only to further information and clarifications. Thus the existing positive determination opinion as basis for the approval does not change. The figures in the registered PDD did not changed.

CR 2: The serial number (Turbo-Generator No.5) belongs to a condensing turbine and this refers to the description in the PDD A.2. This is different to the overview in IRL 6.

CR 2, means of verification

The situation was clarified with the verified situation onsite and the provided Turbine technical

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta
Turnu-Severin (2008)”



Industrie Service

Page 17 of 18

features in IRL 6 - ROMAG TERMO TPP - Main Equipment Technical Features
CR 2, changes in the MR or related documents
The project documentation of ROMAG TERMO TPP - Main Equipment Technical Features has been updated for Turbo-Generator No.5 that is indeed a condensing turbine.

CR 3: Due to the verified situation onsite turbo-generator no. 3 is a backpressure machine. This is different to the overview of technical features in IRL 6.
CR 3, means of verification
The situation was clarified with the verified situation onsite and the provided Turbine technical features in IRL 6 - ROMAG TERMO TPP - Main Equipment Technical Features
CR 3, changes in the MR or related documents
The project documentation of ROMAG TERMO TPP - Main Equipment Technical Features has been updated for Turbo-Generator No.3. that is indeed a backpressure turbine

CR 4: Please provide a contract or further evidence (operation permit, concession) that the actual situation of ownership and operation will be covering the project lifetime.
CR 4, means of verification
The status could be clarified with the signed contract from 19.12.2003.
CR 4, changes in the MR or related documents
The concession period of 20 years covers the project lifetime. There was no change of any document necessary.

CR 5: Please show how the JI-Project Department collaborates with the Local Environmental Authority due to procedure PO-RT 82 (IRL no.9) in this case and how a verification of these issues was done by the authority.
CR 5, means of verification
The issued reports containing the output of the periodic control/evaluation activities made by the LEA representatives have been presented.
CR 5, changes in the MR or related documents
There are no changes in the documents.

CR 6: Please provide Internal Working Procedure PO-MCARTH 14.
CR 6, means of verification
This Internal QM-Procedure due to ISO 9001/14001 for management and quality assurance of technical media has been provided to audit team.
CR 6, changes in the MR or related documents
There are no changes in the documents.

CR 7: All cells of the calculation tool are unlocked for verification purposes. Please provide the clean version that is used for data inputs with the locked cells containing the project formulae.
CR 7, means of verification
The final version V No.3 of the calculation tool has been checked so the lock of cells, containing project formulae could be tested.
CR 7, changes in the MR or related documents
The excel calculation tool was converted to an unlocked version only for verification purposes.

FIRST PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)”



Industrie Service

Page 18 of 18

5 VERIFICATION STATEMENT

TÜV SÜD Industrie Service GmbH has performed the first periodic verification for ERs from 2008 of the JI track 1 project: “Energy efficiency improvement of the district heating system in Drobeta Turnu- Severin”. The verification is based on the currently valid documentation of the UN Framework Convention on Climate Change (UNFCCC) and takes into account in general all requirements for JI projects as well as specific national regulations as described in the Romanian National JI Track I Procedure of the Romanian DFP.

The management of ROMAG TPP is responsible for the preparation of the GHG emissions data and the reported GHG emission reductions on the basis set out within the project’s Monitoring Plan indicated in the PDD version 08, dated 07-11-2009. The verifier can confirm that:

- the development and maintenance of records and reporting procedures are in accordance with the monitoring plan;
- the project is operated as planned and described in the project design document;
- the installed equipment being essential for generating emission reduction runs reliably and is calibrated appropriately;
- the monitoring system is in place and generates GHG emission reductions data;
- the GHG emission reductions are calculated without material misstatements;
- the monitoring plan in Monitoring Report is as per the PDD
- that the monitoring plan in latest determined PDD is in accordance with the approach taken regarding baseline setting and monitoring (please see Appendix B of the JI Guidelines – Decision 9 COP/MOP).

Our opinion is based on the project’s GHG emissions and resulting GHG emission reductions reported, which have been both determined through the valid project’s baseline, its monitoring plan and its associated documents.

Based on the information we have seen and evaluated, we confirm the following statement:

Reporting period: From 01-01-2008 to 31-12-2008

Verified emissions in the above reporting period:

Baseline emissions:	621,768	t CO _{2e}
Project emissions:	511,714	t CO _{2e}
Leakage emission:	0	t CO _{2e}
Emission reductions:	110,054	t CO _{2e}

Munich, 03-06-2010

Munich, 03-06-2010

A handwritten signature in blue ink, appearing to read 'Rachel Zhang'.

Rachel Zhang
Deputy Head of the Certification Body “climate
and energy”
TÜV SÜD Industrie Service GmbH

A handwritten signature in blue ink, appearing to read 'Thomas Kleiser'.

Thomas Kleiser
Assessment Team Leader

PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta
Turnu-Severin” **(2008)**



Industrie Service

Annex 1: Verification protocol

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Input by audit team in blue colour

Old text from previous verification (unchanged situation) in black colour

Table of Contents

1. Project Activity Implementation

1.1. Technology

Corrective Action Request No. 1:

GSP coordinates of the project site have to be included in the PDD

Clarification Request No. 2:

Clarification Request No. 1:

Clarification Request No. 3:

Clarification Request No. 4:

1.2. Organization

1.3. Quality Management System

1.4. Remaining FARs from previous Verifications (or forwarded issues of validation report)

Clarification Request No. 5:

2. Monitoring Plan Implementation

2.1. Parameters

Corrective Action Request No. 2:

The Parameter has to be included in the Monitoring Protocol, sheet: INPUT DATA_NEW CONNECTIONS

2.2. Parameters measured directly with instruments

Clarification Request No. 6:

Corrective Action Request No. 3:

2.3. Parameters measured through sampling

2.4. Parameters obtained through external sources and accounting data

2.5. Other parameters not included in the methodology/tool but included in the PDD

3. Data Processing and ER calculation

Corrective Action Request No. 7

Corrective Action Request No. 4:

Corrective Action Request No. 5:

Clarification Request No. 7:

Corrective Action Request No. 8:

4. Additional assessment

4.1. Internal Review

4.2. Peculiarities

4.3. Further additional requirements

4.4. Data Reporting

Corrective Action Request No. 9:

Corrective Action Request No. 6:

5. Compilation and Resolutions of CARs, CRs and FARs

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

1. Project Activity Implementation

1.1. Technology

Location (s)			
	PDD Description	Verified Situation	Conclusion and IRL
Description / Address: <i>Calea Tg. Jiului, Km. 5, Drobeta Turnu-Severin, Mehedinti</i>	<i>ROMAG TPP is located approximately 5 km north-east from Drobeta Turnu-Severin in the Mehedinti Region, Romania</i>	<i>The location of the project site is described correct. There is the ROMAG THERM power plant outside the city connected with the project site, heat distribution network in Drobeta Turnu-Severin.</i>	<input checked="" type="checkbox"/>
GSP coordinates:	Corrective Action Request No. 1: <i>GSP coordinates of the project site have to be included in the PDD</i>	<i>Latitude 44°40 min 25.5 N, Longitude 22°41 min 18 E This information has been added in the PDD and refers to the information stated on site.</i>	CAR #1 <input checked="" type="checkbox"/> IRL 0
Technical Equipment – Main Components			
	PDD Description	Verified Situation	Conclusion and IRL
Description	<i>The CHP plant is equipped with 6 boiler units and 6 turbines. The thermal and electric efficiencies of the power plant amount to approximately 27% and 21%, respectively.</i>	<i>Boiler- and machine-house is one large but compact building. All the boilers and respective machines (turbine and generator) are in line. The operation of all the components could be followed up at the process control panels.</i>	<input checked="" type="checkbox"/> IRL 6
Component 1- 6: Technical Features	<i>Boiler No.1 – No.6</i>	Capacity: <i>258 Gcal/h equiv. 300 MWh each</i>	<input checked="" type="checkbox"/> IRL 6

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

		<p>Manufacturer: <i>SC VULCAN BUCHAREST SA Romania</i> Commissioning date / Serial number: <i>No.1 31.07.1986 / CR1670 / 22244/82</i> <i>No.2 30.06.1987 / CR1670 / 22250/82</i> <i>No.3 27.04.1988 / CRG 1666 / 22721/84</i> <i>No.4 28.11.1988 / CR 1244 / 23723/86</i> <i>No.5 31.05.1990 / CR 1870 / 24729/88</i> <i>No.6 28.02.1991 / CRG 1870 / 24737/89</i></p>	
Component 7: Technical Features	<i>Turbo-generator no. 1, condensing turbine</i>	<p>Capacity: <i>50 MW</i> Manufacturer: <i>SC GENERAL TURBO SA, Romania</i> Commissioning date: <i>31.07.1986</i> Serial number: <i>DSL 50-1 / 3829</i></p>	<input checked="" type="checkbox"/> IRL 6
Component 8: Technical Features	<i>Turbo-generator no. 4, condensing turbine</i>	<p>Capacity: <i>50 MW</i> Manufacturer: <i>SC GENERAL TURBO SA, Romania</i> Commissioning date: <i>31.07.1989</i> Serial number: <i>DSL 50-1 / 3832</i></p>	<input checked="" type="checkbox"/> IRL 6
Component 9: Technical Features	<i>Turbo-generator no. 5, condensing turbine</i>	<p>Capacity: <i>50 MW</i> Manufacturer: <i>SC GENERAL TURBO SA, Romania</i> Commissioning date: <i>08.04.2004</i> Serial number: <i>DSL 50-1 / 2660</i></p> <p>Clarification Request No. 2:</p>	CR #2 IRL 6

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

		<i>The serial number belongs to a condensing turbine and this refers to the description in the PDD A.2. This is different to the overview in IRL No. 6.</i>	This issue was clarified. <input checked="" type="checkbox"/>
Component 10: Technical Features	<i>Turbo-generator no. 6, condensing turbine</i>	Capacity: <i>25 MW</i> Manufacturer: <i>SC GENERAL TURBO SA, Romania</i> Commissioning date: <i>29.12.2004</i> Serial number: <i>SC 25 / 2682</i>	<input checked="" type="checkbox"/> IRL 6
Component 11: Technical Features	<i>Turbo-generator no. 2, backpressure turbine</i>	Capacity: <i>50 MW</i> Manufacturer: <i>SC GENERAL TURBO SA, Romania</i> Commissioning date: <i>30.06.1987</i> Serial number: <i>DKUL / 3226</i> Clarification Request No. 1: <i>The situation stated in the PDD regarding backpressure turbines is different to the MR (2.1).</i> <i>Due to the verified situation onsite and the provided Turbine technical features in IRL 6 the situation was clarified. There are two backpressure turbines installed. The description in the PDD was updated in V8.</i>	CR #1 <input checked="" type="checkbox"/> IRL 6
Component 12: Technical Features	<i>Turbo-generator no. 3, backpressure turbine</i>	Capacity: <i>22 MW</i> Manufacturer: <i>SC GENERAL TURBO SA, Romania</i>	CR #3 IRL 6

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

		<p>Commissioning date: <i>02.08.2007</i> Serial number: <i>DKAR 22 / 22966</i></p> <p>Clarification Request No. 3: <i>Due to the verified situation onsite turbo-generator no. 3 is a backpressure machine. This is different to the overview of technical features in IRL No. 6.</i></p>	<p>This issue was clarified.</p> <p><input checked="" type="checkbox"/></p> <p>IRL 6</p>
<p>Component 13: Technical Features</p>	<p><i>38 Heat conversion substations</i></p>	<p>Capacity: HEAT : 0 –3 Gcal/h; HOT SANITARY WATER : 0-2 Gcal/h Manufacturer: Reconstruction Commissioning date: 10/2006 - 28.02.2007 Serial number: HCS1; HCS2; HCS3; HCS4; HCS5; HCS6; HCS7; HCS8; HCS9; HCS13; HCS17; HCS19; HCS20; HCS21; HCS22; HCS23; HCS24; HCS25; HCS27; HCS29; HCS30; HCS31; HCS32; HCS35; HCS36; HCS38; HCS39; HCS40; HCS41; HCS42; HCS43; HCS53; HCS54; HCS55; HCS59; HCS60; HCS66; HCS67</p>	<p><input checked="" type="checkbox"/></p> <p>IRL No.26/ No.35</p>
<p>Operation Status during verification</p>			
	<p>Verified Situation</p>		<p>Conclusion and IRL</p>
<p>Approvals / Licenses</p>	<p><i>ROMAG Termo TPP is supplying heat to customers of the primary and secondary heat distribution network of the Drobeta Turnu-Severin over many years. The project was implemented to increase the efficiency of the secondary network in the city area. The</i></p>		<p><i>CR #4</i></p>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	<p><i>distribution network is owned and operated by a branch of ROMAG Termo since January 2004 when it was handed over by the municipality.</i></p> <p>Clarification Request No. 4: <i>Please provide a contract or further evidence (operation permit, concession) that the actual situation of ownership and operation will be covering the project lifetime.</i></p>	<p><i>The document has been provided</i> <i>IRL No.36</i> <input checked="" type="checkbox"/></p>
Actual Operation Status	<p>Start date of operation (each site if applicable): <i>14/02/2006</i></p> <p>Under construction <input type="checkbox"/></p> <p>In operation <input checked="" type="checkbox"/></p> <p>Out of operation <input type="checkbox"/></p> <p>Reason and date (if out of operation):</p>	<input checked="" type="checkbox"/>
	<p><i>The data basis for an appropriate operation provide the excel spreadsheets of the annual Monitoring Report that allowed the calculation of energy balances and shows several efficiencies. The operation was verified onsite by visiting the power plant and the central control room for the district heating system with an indication of every HCS in operation. Samples of HCS were visited as well to check the installation and metering system.</i></p>	<input checked="" type="checkbox"/>
Remarks to Special Operational Status During the Verification Period	<p>Phased implementation: <i>The project was implemented between October 2006 and March 2008 in three stages. So it was finalized during the second monitoring period. The progress that was achieved is reflected by growing thermal efficiencies of the secondary network. After reconstruction the HCS were integrated in the project documented by Final Acceptance Reports.</i></p> <p>Special cases: <i>There are a growing number of new connections to customers from HCS that are a part of the project. These connections are monitored separately and considered as not project integrated. This is due to the project specific methodology in the registered PDD.</i></p>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

1.2. Organization

Project Participant (s)		
	Verified Situation	Conclusion and IRL
Entity / Responsible person: ROMAG TPP / General Director Danish Energy Agency / Deputy Programme Director	<i>The responsibilities have not changed regarding to positions in comparison to the registered PDD.</i>	<input checked="" type="checkbox"/>
JI Project management: ROMAG TTP / Eng. Lelia Dobjanschi	<i>The responsibility has not changed due to the person.</i>	<input checked="" type="checkbox"/>

1.3. Quality Management System

General aspects of the Quality Management System		
	Verified Situation	Conclusion and IRL
Quality Management Manual:	<i>The Monitoring Plan Guidelines and Procedures, Version 4 (IRL No.5) is the basic document that detailed guides to fulfil the requirements of reporting accordance to the Monitoring Plan.</i>	<input checked="" type="checkbox"/>
Responsibilities:	<i>The Monitoring Plan refers directly to the Monitoring Plan Guidelines and Procedures. A further QM-Procedure "Management and Monitoring System, JI-Project (IRL No.9) provides all the responsibility in a detailed manner and refers to the JI-Project Organization Chart (IRL No.11)</i>	<input checked="" type="checkbox"/>
Qualification and Training:	<i>Basis of qualification and training of key personal is the "Personal Training Procedure" (IRL No. 16). This is applied to the secondary and high education personnel. The train-</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	<i>ing is organized once per year and includes all requirements regarding the JI-Project. Participation records were verified onsite (IRL No. 17).</i>	
Implementation of QM-system	<i>ROMAG TPP is practicing an approved QM-System based on ISO 9001. All the project relevant documents and procedures are integrated in the system that is strictly applied.</i>	<input checked="" type="checkbox"/>

1.4. Remaining FARs from previous Verifications (or forwarded issues of validation report)

Remaining Requests from Previous Verifications	Summary of project owner response	Audit team Conclusion and IRL
Forward Action Request #1: Environment impacts (degree of improvements, air quality, sustainability of impact, etc.) and social impact (comfort level in buildings, number of jobs created, new business areas) should be verified according to the PDD once per year by the local EPI.	Clarification Request No. 5: <i>Please show how the JI-Project Department collaborates with the Local Environmental Authority due to procedure PO-RT 82 (IRL no.9) in this case and how a verification of these issues was done by the authority.</i>	<i>CR #5</i> <i>Evidence of LEA assessment activities has been provided.</i> <i>IRL 37</i> <input checked="" type="checkbox"/>
Forward Action Request #2: A procedure should be elaborated and implemented which rules the requirements on qualification and the need of training programs for all persons working on the emission reduction project.	Quality Management System Operational Procedure PO-RT 83, Personnel Training, JI Project The Project Manager or his/her deputy is responsible for JI-Project personnel training once a year.	<i>The procedure (IRL No.16) was integrated in the ISO 9001 approved QM-process. It covers all JI-Project related aspects. The training material was shown the audit team during the audit.</i> <i>This issue is considered as solved.</i> <input checked="" type="checkbox"/>
Forward Action Request #3: A procedure should be elaborated and implemented which defines	Quality Management System Operational Procedure PO-RT 82, Management and Monitoring System, JI Project, Annex 1 – Organigramm – JI Project Re-	<i>The main tasks in the Monitoring process for every department are detailed described in</i>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Remaining Requests from Previous Verifications	Summary of project owner response	Audit team Conclusion and IRL
the responsibilities regarding monitoring of JI project.	responsibilities	<p><i>this Procedure (IRL No.9). The interaction of departments and authorities is illustrated in the annexed organigram (IRL No.11)</i></p> <p><i>This issue is considered as solved.</i></p> <p style="text-align: center;"><input checked="" type="checkbox"/></p>
<p>Forward Action Request #4: A procedure should be elaborated and implemented which provides emergency concepts in case of unexpected problems with data access and/ or data quality.</p>	Quality Management System Operational Procedure PO-RT 84, Data Collection During Emergency Situations	<p><i>The procedure (IRL No.12) describes responsibilities and intervention methods that have to be applied when any component of the metering system fails. Generally it is based on the QM-Management System.</i></p> <p><i>This issue is considered as solved.</i></p> <p style="text-align: center;"><input checked="" type="checkbox"/></p>
<p>Forward Action Request #5: A procedure should be elaborated and implemented which includes internal control procedures, which allow the identification and solution of problems at an early stage.</p>	Quality Management System Operational Procedure PO-RT 84, Data Collection During Emergency Situations	<p><i>The clear stated responsibilities for every metering system top down from the power plant to the consumers (IRL No.12) and implemented QM-Procedures (IRL No.9) assure the identification of problems at an early stage. The annual staff training increases the advertency for project related problems.</i></p> <p><i>This issue is considered as solved.</i></p> <p style="text-align: center;"><input checked="" type="checkbox"/></p>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

2. Monitoring Plan Implementation

2.1. Parameters

Parameters					
Meth/tool	PDD	MR	Included in table	Compliance	Conclusion and IRL
	$V_{P, lignite}$	$V_{P, lignite}$	2.4 table 1	Power Plant Fuel Consumption Determination.doc	
	$V_{P, oil}$	$V_{P, oil}$	2.4 table 2	Power Plant Fuel Consumption Determination.doc	
	$CV_{P, lignite}$	$CV_{P, lignite}$	2.3 table 1	Fuels Calorific Values Determination.doc Code: PO – RT 78, Edition 1, revision 1.	
	$CV_{P, oil}$	$CV_{P, oil}$	2.3 table 2	Fuels Calorific Values Determination.doc Code: PO – RT 78, Edition 1, revision 1.	
	$Q_{P, DH, primary}$	$Q_{P, DH, primary}$	2.2 table 1	IRL No.5	
	$Q_{P, ps}$	$Q_{P, ps}$	2.2 table 2	IRL No.5	
	$Q_{P, DH, HCS}$	$Q_{P, DH, HCS}$	2.2 table 3	Heat and Steam Delivered to Consumers.doc, chap.6.2.2, IRL No.14	
	$Q_{P, DH, pr, con}$	$Q_{P, DH, pr, con}$	2.2 table 4	IRL No.14	
	$Q_{P, DH, secondary}$	$Q_{P, DH, secondary}$	2.2 table 5	IRL No.14	
	$Q_{P, DH, consumers}$	$Q_{P, DH, consumers}$	2.2 table 6	IRL No.14	
	$Q_{P, DH, pr, new, con}$		2.2 table 7	Corrective Action Request No. 2:	CAR #2

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Parameters					
Meth/tool	PDD	MR	Included in table	Compliance	Conclusion and IRL
				<p><i>The Parameter has to be included in the Monitoring Protocol, sheet: INPUT DATA_NEW CONNECTIONS</i></p> <p><i>The parameter was added to the MR spreadsheet at the top of the relevant column.</i></p>	<input checked="" type="checkbox"/>
	Q P, DH, sec, new_con		2.2 table 8	<p>See CAR #2</p> <p><i>The parameter was added to the MR spreadsheet at the top of the relevant column.</i></p>	<p>CAR #2</p> <input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

2.2. Parameters measured directly with instruments

Table 1

Parameter and instrumentation Information					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>District heat supplied to the primary network</i>	<i>n. a.</i>	<i>district heat delivered to primary network</i>	<i>Description of title is consistent.</i>	<input checked="" type="checkbox"/>
Parameter ID (if available)	<i>$Q_{P, DH, primary}$</i>	<i>n. a.</i>	<i>$Q_{P, DH, primary}$</i>	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>Gcal</i>	<i>n. a.</i>	<i>Gcal</i>	<i>Used unit is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (reading)	<i>every 8 hours, daily log</i>	<i>n. a.</i>	<i>every 8 hours, daily log</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (recording)	<i>monthly</i>	<i>n. a.</i>	<i>monthly</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Calibration requirements	<i>every 4 years</i>	<i>n. a.</i>	<i>every 4 years</i>	<i>1. Heat computer</i> BV 0084760/23.01.08 BV 0085679/09.09.04 <i>2. Twin Thermo-resistances</i> BV 0084761/23.01.08	<input checked="" type="checkbox"/> IRL No.7

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

				BV 0083121/19.07.06 <i>3. Ultrasonic Flow Meter (FP)</i> BV 06.02 – 001/20.02.08 BV 06.02 – 007/27.09.04 <i>4. Ultrasonic Flow Meter (RP)</i> BV 06.02 – 002/20.02.08 BV 06.02 – 008/27.09.04	
Uncertainty level	<i>low</i>	<i>n. a</i>	<i>0.2 %</i>	<i>The value of the calibrated system is consistent to “low”.</i>	<input checked="" type="checkbox"/>
Measurement Principle (if applicable)	<i>Ultrasonic flow meter, heat calculator</i>	<i>n. a</i>	<i>Ultrasonic flow meter, heat calculator</i>	<i>This is consistent</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Instrument Type:	Heat Meter SONOFLO/CALEC consisting of: 1. Heat Computer CALEC-MB TWIN E 2. Twin Thermo Resistances Pt 100 TPK 3. Ultrasonic Flow Meter (Forward pipe) – SONO 3110/3000 4. Ultrasonic Flow Meter (Return pipe) – SONO 3110/3000				<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Serial Number:	1. 4113149/00 2. 185055-00 3. 335908N310 4. 131204N417	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	1. Heat Computer CALEC-MB TWIN E 2. Twin Thermo Resistances Pt 100 TPK 3. Ultrasonic Flow Meter (Forward pipe) – SONO 3110/3000 4. Ultrasonic Flow Meter (Return pipe) – SONO 3110/3000	<input checked="" type="checkbox"/>
Specific Location:	Romag Thermo TPP, <i>At the fence of CHP</i>	<input checked="" type="checkbox"/>
Measurement Range:	0 – 4000m3/h (0 – 160 Gcal/h)	<input checked="" type="checkbox"/>
Gaps in operating time of instrument :	Period: <i>There were no gaps in operating time for this instrument.</i>	<input checked="" type="checkbox"/>
	Default value used: <i>In case of gaps according to Project Procedure PO-RT94</i>	<input checked="" type="checkbox"/>
	Justification: <i>according to Project Procedure PO-RT94</i>	<input checked="" type="checkbox"/>
	QA/QC aspects	Conclusion and IRL
Source of data	<i>Readouts of instrumentation collected manually every 8 hours in and logged in daily reports.</i> <i>Type: measured electronically (digital), logbook, daily report</i>	<input checked="" type="checkbox"/>
	Procedures: Internal Working Procedure PO-MCRTH 14 <i>QM PO-RT82 Management and Monitoring, training on the job</i> Clarification Request No. 6: <i>Please provide Internal Working Procedure PO-MCRTH 14.</i>	CR #6 IRL No.9 The document has been provided.

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

		IRL No. 38 <input checked="" type="checkbox"/>
	Implementation of procedure: <i>The correctness of the procedure implementation has been assessed by onsite visit at the installation site and following the data flow.</i>	<input checked="" type="checkbox"/> IRL No. 21/22
	Responsibility: <i>Control Room Operating Staff - Turbine Department (PO-RT82)</i>	<input checked="" type="checkbox"/> IRL No.9
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are archived on paper and CDs in two different locations <i>Recordings in logbooks are archived in paper form, the values of the daily reports are put into an excel spreadsheet prepared for one month. The project relevant data of one month are summarized in a JI Process Data Log Sheet.</i>	<input checked="" type="checkbox"/>
Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 82: Management and Monitoring System, Project raw data are processed within the Technical Department, from where they are transferred to JI Project Department, where the final calculation for CO ₂ emission reduction is made, based on the project approved methodology. Cells containing project formulae are locked. <i>Raw data related to Process Steam and Hot Water Production delivered to industrial consumers and district heating system are daily transferred electronically and as hardcopy to the Technical Department. Therefore the Turbine Department is responsible. The Technical Department is processing the data and validating it by calculation of heat balances. The Technical Department transfers the data to the JI-Department that is controlling, recording and archiving the data and performing the calculation. Data losses can be avoided because all data are daily stored electronically and per hardcopy. Row data can be followed down to logbook recordings.</i>	<input checked="" type="checkbox"/> IRL No.9 Annex 2

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	Quality of evidence	Conclusion and IRL
Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. The data flow was followed up from logs to monthly reports for the full monitoring period.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department of ROMAG TPP for the full monitoring period have been provided. This reports were checked with monthly reports and related samples of daily records issued by the Heat Production Department. (May/November 2008). No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 21, 22, 24, 25
	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>The parameter that can be used for plausibility crosscheck is the calculated system efficiency of primary network in the Monitoring Excel Spreadsheet Tool. The efficiency is related to total amount of heat delivered to the primary network.</i>	<input checked="" type="checkbox"/>

Table 2

Parameter and instrumentation Information					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>Process steam produced for heavy water producers</i>	<i>n. a.</i>	<i>Process steam production</i>	<i>As it describes the process steam production that is only delivered to heavy</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

				<i>water producers it is consistent.</i>	
Parameter ID (if available)	<i>Q_{P, ps}</i>	<i>n. a.</i>	<i>Q_{P, ps}</i>	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>Gcal</i>	<i>n. a.</i>	<i>Gcal</i>	<i>Used unit is consistent</i>	<input checked="" type="checkbox"/>
Monitoring frequency (reading)	<i>Every our (manually and automatically) logged for the day</i>	<i>n. a.</i>	<i>Every our (manually and automatically) logged for the day</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (recording)	<i>monthly</i>	<i>n. a.</i>	<i>monthly</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Calibration requirements	<i>every 2 years</i>	<i>n. a.</i>	<i>every 2 years</i>	<i>2006 – 2008, details for every part of the metering equipment are provided in IRL No.26 and can be assessed with documents in IRL No.7</i>	<input checked="" type="checkbox"/> IRL No.7/ No.26
Uncertainty level	<i>low</i>	<i>n. a.</i>	<i>0,1 %</i>	<i>The value of the calibrated system is consistent to “low”.</i>	<input checked="" type="checkbox"/>
Measurement Principle (if applicable)	<i>n. a.</i>	<i>n. a.</i>	<i>Differential pressure Diaphragm, heat calculator</i>	<i>Evidence was supplied by calibration certificates.</i>	<input checked="" type="checkbox"/> IRL No.7
	Technical aspects				Conclusion and IRL
Instrument Type: Instrument 1 - 3					<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	<p>Feeders 16 bar:</p> <ol style="list-style-type: none"> 1. Computer MULTICAL CCA1212 2. Thermo Resistances Pt 100 3. Diaphragm DN = 558.88 4. Differential Pressure Transducer 5. Relative Pressure Transducer <p><i>3 meters for each line A, B, C: Computer "Multical" CCA 1212+thermoreistance Pt100+diaphragm+differential pressure sensor+relative pressure sensor</i></p>	<p>IRL No.19/20</p>
<p>Serial Number:</p>	<p>Feeder 1 – 16 bar:</p> <ol style="list-style-type: none"> 1. Computer – 0242 2. Thermo Resistances – 447 3. Diaphragm – 740-4 4. Differential Pressure Transducer – 3031/01 5. Relative Pressure Transducer – 403/00 <p>Feeder 2 – 16 bar:</p> <ol style="list-style-type: none"> 1. Computer – 0243 2. Thermo Resistances – 51 3. Diaphragm – 740-5 4. Differential Pressure Transducer – 3040 5. Relative Pressure Transducer – 401/00 <p>Feeder 3 – 16 bar:</p> <ol style="list-style-type: none"> 1. Computer – 0244 2. Thermo Resistances – 360 3. Diaphragm – 740-6 4. Differential Pressure Transducer – 3035/01 5. Relative Pressure Transducer – 5024/01 	<p><input checked="" type="checkbox"/> IRL No.19/20</p>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Manufacturer Model Nr.:	Feeders 16 bar: 1. Computer MULTICAL CCA1212 2. Thermo Resistances Pt 100 3. Diaphragm DN = 558.88 4. Differential Pressure Transducer 5. Relative Pressure Transducer	<input checked="" type="checkbox"/> IRL No.19/20
Specific Location:	At the border between Romag Termo TPP and Romag Prod (Heavy Water Producer) <i>TPP , each main pipe 16 bar</i>	<input checked="" type="checkbox"/>
Measurement Range:	Feeders 16 bar: 1 – 16 bar / 0 – 400 t/h	<input checked="" type="checkbox"/>
Gaps in operating time of instrument :	Period <i>There are no gaps in operating time for these instruments. In case of repair or calibration alternate pipe is used.</i>	<input checked="" type="checkbox"/>
	Default value used: <i>n. a.</i>	<input checked="" type="checkbox"/>
	Justification: <i>n. a.</i>	<input checked="" type="checkbox"/>
Instrument Type: Instrument 4 - 6	Feeders 40 bar: 1. Computer MULTICAL CCA1212 2. Thermo Resistances Pt 100 3. Diaphragm DN20 = 226.31 4. Differential Pressure Transducer 5. Relative Pressure Transducer <i>3 meters for each line A, B, C: Computer "Multical"CCA 1212+thermoreistance Pt100+diaphragm+differential pressure sensor+relative pressure sensor</i>	<input checked="" type="checkbox"/> IRL No.19/20
Serial Number:		<input checked="" type="checkbox"/> IRL 19/20

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	<p>Feeder 1 – 40 bar:</p> <ol style="list-style-type: none"> 1. Computer – 0239 2. Thermo Resistances – 943 3. Diaphragm – 740-1 4. Differential Pressure Transducer – 3037/01 5. Relative Pressure Transducer – 401/01 <p>Feeder 2 – 40 bar:</p> <ol style="list-style-type: none"> 1. Computer – 0240 2. Thermo Resistances – 1241 3. Diaphragm – 740-2 4. Differential Pressure Transducer – 3023/01 5. Relative Pressure Transducer – 9002/01 <p>Feeder 3 – 40 bar:</p> <ol style="list-style-type: none"> 1. Computer – 0241 2. Thermo Resistances – 107 3. Diaphragm – 740-3 4. Differential Pressure Transducer – 3036/01 5. Relative Pressure Transducer – 9001/01 	
Manufacturer Model Nr.:	<p>Feeders 40 bar:</p> <ol style="list-style-type: none"> 1. Computer MULTICAL CCA1212 2. Thermo Resistances Pt 100 3. Diaphragm DN20 = 226.31 4. Differential Pressure Transducer 5. Relative Pressure Transducer 	<input checked="" type="checkbox"/>
Specific Location:	<p>At the border between Romag Termo TPP and Romag Prod (Heavy Water Producer)</p> <p><i>Each main pipe 40 bar</i></p>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Measurement Range:	1 – 40 bar / 0 – 120 t/h	<input checked="" type="checkbox"/>
Gaps in operating time of instrument :	Period: <i>There were no gaps in operating time for these instruments. In case of repair or calibration alternate pipe is used.</i>	<input checked="" type="checkbox"/>
	Default value used: <i>In case of gaps according to Project Procedure PO-RT94</i>	<input checked="" type="checkbox"/>
	Justification: <i>According to Project Procedure PO-RT94</i>	<input checked="" type="checkbox"/>
	QA/QC aspects	Conclusion and IRL
Source of data	Type: <i>Continuous measuring system transferring data hourly to the TPP central control room (digital). Data were also manually recorded in the logbook and logged for the day.</i>	<input checked="" type="checkbox"/> Ref Nr.0
	Procedures: Internal Working Procedure PO-MCRTH 14 See CR #6 <i>QM PO-RT82 Management and Monitoring, PO-RT94 Determination of the Power Plant Heat and Steam delivered to consumers, training on the job</i>	CR #6 IRL No.9/ 14 IRL No. 38 <input checked="" type="checkbox"/>
	Implementation of procedure: <i>The correctness of the procedure implementation has been assessed by onsite visit at the installation site and following the data flow.</i>	<input checked="" type="checkbox"/> IRL No. 21/22
	Responsibility: <i>Control Room Operating Staff - Turbine Department</i>	<input checked="" type="checkbox"/> IRL No.9/ 14
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are archived on paper and CDs in two different locations. <i>The records are in paper and in electronic form. Data are archived in data files and stored in different places. (Technical department, JI-Department)</i>	<input checked="" type="checkbox"/> IRL No.9/ 14
Data transfer and protection of input	According to Project Procedure PO – RT – 82: Management and Monitoring System,	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

data for calculations	<p>Project raw data are processed within the Technical Department, from where they are transferred to JI Project Department, where the final calculation for CO₂ emission reduction is made, based on the project approved methodology. Cells containing project formulae are locked.</p> <p><i>Raw data related to Process Steam and Hot Water Production delivered to industrial consumers and district heating system are daily transferred electronically and as hardcopy to the Technical Department. Therefore the Turbine Department is responsible. The Technical Department is processing the data and validating it by calculation of heat balances.</i></p> <p><i>The Technical Department transfers the data to the JI-Department that is controlling, recording and archiving the data and performing the calculation.</i></p> <p><i>Data losses can be avoided because all data are daily stored electronically and per hardcopy. Raw data can be followed down to logbook recordings.</i></p>	<p>IRL No.9 Annex 2</p>
	Quality of evidence	Conclusion and IRL
Completeness of data	<p><i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. The data flow was followed up from logs to monthly reports for the full monitoring period.</i></p>	<p><input checked="" type="checkbox"/> IRL No.9</p>
Data verification	<p>Consistency of raw data with calculation tool:</p> <p><i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports and related samples of daily records issued by the Heat Production Department. (May/November 2008). No discrepancies have been found and all data are consistent to the calculation tool.</i></p>	<p><input checked="" type="checkbox"/> IRL No. 21, 22, 24, 25</p>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>Calculation can be crosschecked by monthly or annual heat balances between fuel consumption and total heat production considering the thermal efficiency of the boilers.</i>	<input checked="" type="checkbox"/>

Table 3

Parameter and instrumentation Information					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>District heat supplied to heat conversion substations</i>	<i>n. a.</i>	<i>District heat supplied to heat conversion substations</i>	<i>Description of title is consistent.</i>	<input checked="" type="checkbox"/>
Parameter ID (if available)	$Q_{P,DH,HCS}$	<i>n. a.</i>	$Q_{P,DH,HCS}$	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>Gcal</i>	<i>n. a.</i>	<i>Gcal</i>	<i>Unit is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (reading)	<i>Every our (manually and automatically) logged for the day</i>	<i>n. a.</i>	<i>Every our (manually and automatically) logged for the day</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (recording)	<i>monthly</i>	<i>n. a.</i>	<i>monthly</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Calibration requirements	<i>Every 4 years</i>	<i>n. a.</i>	<i>Every 4 years</i>	Based on the following Verification Permits (BV):	<input checked="" type="checkbox"/> IRL No.7

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

				1 Heat Computer V 0048706/14.01.09 V 0011784/04.05.06 2. Twin Thermo Resistances V 0048706/14.01.09 V 027656/04.05.06. 3. Ultrasonic Flow Transducer V 0048706/14.01.09 V 0011787/04.05.06	<i>The situation was documented for HCS no.3, All the project related 49 HCS are included in the calibration campaign</i>
<i>Uncertainty level</i>	<i>low</i>	<i>n. a.</i>	<i>2 %</i>	<i>The value of the calibrated system is consistent to "low". The valid calibration permits cover the whole monitoring period.</i>	<input checked="" type="checkbox"/>
Measurement Principle (if applicable)	<i>Heat meter</i>	<i>n. a.</i>	<i>Ultrasonic</i>	<i>This is consistent. More specification is provided within followed.</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Instrument Type:					<input checked="" type="checkbox"/> IRL No.26

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	Heat Meter KAMSTRUP A/S consisting of: 1. Heat Computer MULTICAL 2. Twin Thermo Resistances 3. Ultrasonic Flow Transducer ULTRAFLOW	
Serial Number:	1. Heat Computer - 4966623 2. Twin Thermo Resistances - 3589423 3. Ultrasonic Flow Transducer - 3589267	<input checked="" type="checkbox"/> IRL No.26
Manufacturer Model Nr.:	1. Heat Computer MULTICAL 2. Twin Thermo Resistances 3. Ultrasonic Flow Transducer ULTRAFLOW	
Specific Location:	<i>HCS 3, district heating</i>	<input checked="" type="checkbox"/>
Measurement Range:	0 – 5 Gcal/h	<input checked="" type="checkbox"/>
Gaps in operating time of instrument :	Period: <i>There were no gaps in operating time for these instruments.</i>	<input checked="" type="checkbox"/>
	Default value used: In case of gaps according to Project Procedure PO-RT94. Heat delivered to consumers related to the HCS the instrument fails can be used.	<input checked="" type="checkbox"/>
	Justification: According to Project Procedure PO-RT94.	<input checked="" type="checkbox"/>
	QA/QC aspects	Conclusion and IRL
Source of data	<i>Data are collected manually and automatically, acquired and stored with the SCADA-System, every hour and logged for the day.</i> Type: Digital	<input checked="" type="checkbox"/> IRL No.1/No.3
	Procedures: Internal Working Procedure PO-MCRTH 14 See CR #6 <i>QM PO-RT82 Management and Monitoring, PO-RT94 Determination of the Power Plant Heat and Steam delivered to consumers, training on the job</i>	CR #6 <i>IRL No.9/14</i> IRL No. 38 <input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	Implementation of procedure: <i>The correctness of the procedure implementation has been assessed by onsite visit at the installation site and following the data flow.</i>	<input checked="" type="checkbox"/> IRL No. 21/22
	Responsibility: District Heating Department Staff	<input checked="" type="checkbox"/> IRL No.9/ 14
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are processed within District Heating Department and are archived on paper and CDs in two different locations.	<input checked="" type="checkbox"/> IRL No.14
Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 94, project data are transferred from District Heating Department to JI Project Department manually. <i>Input of data and calculation is performed by JI Department of ROMAG TPP.</i>	<input checked="" type="checkbox"/> IRL No.14
	Quality of evidence	Conclusion and IRL
Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 27, 28
	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>Calculation can be crosschecked with the heat supplied to consumers considering the efficiency of HCS.</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Table 4

Parameter and instrumentation Information					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>District heat supplied to consumers connected to the primary network</i>	<i>n. a.</i>	<i>District heat supplied to consumers connected to the primary network</i>	<i>Description of the title is consistent.</i>	<input checked="" type="checkbox"/>
Parameter ID (if available)	<i>$Q_{P,DH,pr.con}$</i>	<i>n. a.</i>	<i>$Q_{P,DH,pr.con}$</i>	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>Gcal</i>	<i>n. a.</i>	<i>Gcal</i>	<i>Unit is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (reading)	<i>Manually, monthly</i>	<i>n. a.</i>	<i>Manually, monthly</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (recording)	<i>monthly</i>	<i>n. a.</i>	<i>monthly</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Calibration requirements	<i>Every 4 years</i>	<i>n. a.</i>	<i>Every 4 years</i>	1. Heat Computer BV 0218320/ 05.12.06 2. Twin Thermo-Resistances BV 70288/05.12.06, 3. Flow Transducer BV 0218320/ 05.12.06. Before the project implementation there was no meas-	<input checked="" type="checkbox"/> <i>IRL No.29</i> <i>The situation was documented for private heat station Gheorghe Titeica Nr.38</i> <i>All the stations of</i>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

				uring equipment installed. The billing of heat was made based on heated area.	<i>consumers connected to the primary network (379 similar) are included in the calibration campaign</i>
Uncertainty level	<i>low</i>	<i>n. a.</i>	<i>2 %</i>	<i>The value of the calibrated system is consistent to "low". The valid calibration permits cover the whole monitoring period.</i>	<input checked="" type="checkbox"/>
Measurement Principle (if applicable)	<i>Heat meter</i>	<i>n. a.</i>	<i>Ultrasonic</i>	<i>This is consistent. More specification is provided within followed.</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Instrument Type:	Heat Meter POLLUSTAT EX consisting of: 1. Heat Computer 2. Twin Thermo-Resistances 3. Flow Transducer				<input checked="" type="checkbox"/> IRL No.26
Serial Number:	1. Heat Computer – 6466008 2. Twin Thermo-Resistances – 07427				<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	3. Flow Transducer 6466008	IRL No.26
Manufacturer Model Nr.:	POLLUSTAT EX	<input checked="" type="checkbox"/>
Specific Location:	Private House – Druga Dumitru; 38 Gheorghe Titeica St., Drobeta Turnu Severin.	<input checked="" type="checkbox"/>
Measurement Range:	0 – 1 Gcal/h	<input checked="" type="checkbox"/>
Gaps in operating time of instrument :	Period: <i>There were no gaps in operating time for these instruments.</i>	<input checked="" type="checkbox"/>
	Default value used: <i>None default values have been used.</i>	<input checked="" type="checkbox"/>
	Justification: <i>According to Project Procedure PO-RT94.</i>	<input checked="" type="checkbox"/>
	QA/QC aspects	Conclusion and IRL
Source of data	<i>Data are collected manually monthly.</i> Type: digital	<input checked="" type="checkbox"/> IRL No.1/No.3
	Procedures: Internal Working Procedure PO-MCRTH 14 See CR #6 <i>QM PO-RT82 Management and Monitoring, PO-RT94 Determination of the Power Plant Heat and Steam delivered to consumers, training on the job</i>	CR #6 <i>IRL No.9/14</i> IRL No. 38 <input checked="" type="checkbox"/>
	Implementation of procedure: <i>The correctness of the procedure implementation has been assessed by onsite visit at the installation site and following the data flow.</i>	<input checked="" type="checkbox"/> IRL No. 21/22
	Responsibility: District Heating Department Staff	<input checked="" type="checkbox"/> IRL No.9/

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

		14
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are processed within District Heating Department and are archived on paper and CDs in two different locations.	<input checked="" type="checkbox"/> IRL No.14
Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 94, project data are transferred from District Heating Department to JI Project Department manually. <i>Input of data and calculation is performed by JI Department.</i>	<input checked="" type="checkbox"/> IRL No.14
	Quality of evidence	Conclusion and IRL
Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 27, 28
	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>Calculation can be crosschecked with the general heat balance of power plant and supplied networks.</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Table 5

Parameter and instrumentation Information					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>District heat supplied to secondary network</i>	<i>n. a.</i>	<i>District heat supplied to secondary network</i>	<i>Description of the title is consistent.</i>	<input checked="" type="checkbox"/>
Parameter ID (if available)	$Q_{P,DH,secondary}$	<i>n. a.</i>	$Q_{P,DH,secondary}$	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>Gcal</i>	<i>n. a.</i>	<i>Gcal</i>	<i>Unit is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (reading)	<i>Every our (manually and automatically) logged for the day</i>	<i>n. a.</i>	<i>Every hour (manually and automatically) logged for the day</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (recording)	<i>monthly</i>	<i>n. a.</i>	<i>monthly</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Calibration requirements	<i>Every 4 years</i>	<i>n. a.</i>	<i>Every 4 years</i>	HEAT System- latest 2 calibrations: 29.11.06 14.01.09. HOT SANITARY WATER System latest 2 calibrations: 04.05.2006	<input checked="" type="checkbox"/> IRL No.30 <i>The situation was documented for HCS no.3, All the project related 49 HCS are</i>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

				14.01.2009	<i>included in the calibration campaign</i>
Uncertainty level	<i>low</i>	<i>n. a.</i>	<i>2 %</i>	<i>The value of the calibrated system is consistent to "low". The valid calibration permits cover the whole monitoring</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

				<i>period.</i>	
Measurement Principle (if applicable)	<i>Heat meter</i>	<i>n. a.</i>	<i>Ultrasonic</i>	<i>This is consistent. More specification is provided within followed.</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Instrument Type:	Heat Meters KAMSTRUP A/S consisting of: 1. Heat Computer MULTICAL 2. Twin Thermo-Resistances 3. Ultrasonic Flow Transducer ULTRAFLOW				<input checked="" type="checkbox"/> IRL No.26
Serial Number:	HEAT 1. Heat Computer – 4966675 2. Twin Thermo-Resistances - 3589411 3. Ultrasonic Flow Transducer – 3589305 HOT SANITARY WATER 1. Heat Computer – 4966559 2. Twin Thermo-Resistances - 3589432 3. Ultrasonic Flow Transducer – 4966559				<input checked="" type="checkbox"/> IRL No.26
Manufacturer Model Nr.:	1. Heat Computer MULTICAL , 2. Twin Thermo-Resistances , 3. Ultrasonic Flow Transducer ULTRAFLOW				<input checked="" type="checkbox"/> IRL No.26
Specific Location:	HCS no.3, district heating				<input checked="" type="checkbox"/>
Measurement Range:	HEAT : 0 –3 Gcal/h; HOT SANITARY WATER : 0-2 Gcal/h				<input checked="" type="checkbox"/> IRL No.26
Gaps in operating time of instrument	Period: <i>There were no gaps in operating time for these instruments.</i>				<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

:	Default value used: <i>In case of gaps</i> according to Project Procedure PO-RT94. Heat delivered to consumers related to the HCS the instrument fails can be used.	<input checked="" type="checkbox"/>
	Justification: According to Project Procedure PO-RT94.	<input checked="" type="checkbox"/>
	QA/QC aspects	Conclusion and IRL
Source of data	<i>Data are collected manually and automatically, acquired and stored with the SCADA-System, every hour and logged for the day.</i> Type: Digital	<input checked="" type="checkbox"/> IRL No.1/No.3
	Procedures: Internal Working Procedure PO-MCARTH 14 See CR #6 <i>QM PO-RT82 Management and Monitoring, PO-RT94 Determination of the Power Plant Heat and Steam delivered to consumers, training on the job</i>	CR #6 <i>IRL No.9/14</i> IRL No. 38 <input checked="" type="checkbox"/>
	Implementation of procedure: <i>The correctness of the procedure implementation has been assessed by onsite visit at the installation site and following the data flow.</i>	<input checked="" type="checkbox"/> IRL No. 21/22
	Responsibility: District Heating Department Staff	<input checked="" type="checkbox"/> IRL No.9/14
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are processed within District Heating Department and are archived on paper and CDs in two different locations.	<input checked="" type="checkbox"/> IRL No.14
Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 94, project data are transferred from District Heating Department to JI Project Department manually. <i>Input of data and calculation is performed by JI Department.</i>	<input checked="" type="checkbox"/> IRL No.14
	Quality of evidence	Conclusion and IRL

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 27, 28
	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>Calculation can be crosschecked with the heat supplied to single consumers connected to the HCS.</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Table 6

Parameter and instrumentation Information					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>District heat supplied to consumers connected to the secondary network</i>	<i>n. a.</i>	<i>District heat delivered to consumers connected to secondary network</i>	<i>As it describes the heat to consumers connected to the secondary network it is consistent</i>	<input checked="" type="checkbox"/>
Parameter ID (if available)	$Q_{P,DH,consumers}$	<i>n. a.</i>	$Q_{P,DH,consumers}$	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>Gcal</i>	<i>n. a.</i>	<i>Gcal</i>	<i>Unit is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (reading)	<i>Manually, monthly</i>	<i>n. a.</i>	<i>Manually, monthly</i>	<i>This is consistent. The system will be improved to SCADA (after completing the connections of local Heat Meters to the new installed M Bus cable)</i>	<input checked="" type="checkbox"/> IRL No. 0
Monitoring frequency (recording)	<i>monthly</i>	<i>n. a.</i>	<i>monthly</i>	<i>monthly</i>	<input checked="" type="checkbox"/>
Calibration requirements	<i>Every 4 years</i>	<i>n. a.</i>	<i>Every 4 years</i>	Evidence of the latest 2 calibrations: HEAT 1. Heat Computer BV 000062797/12.11.07 2. Twin Thermo-	<input checked="" type="checkbox"/> IRL No.31 <i>The situation was documented for one of</i>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

				<p>Resistances BV 000062647/12.11.07</p> <p>3. Flow Transducer BV 000062650/12.11.07</p> <p>HOT SANITARY WATER</p> <p>1. Heat Computer BV 241/ 21.07.08, 2. Twin Thermo-Resistances BV 000062647/21.07.2008 3. Flow Transducer BV 000062503/21.07.2008</p> <p>Before the project implementation there was no measuring equipment installed. The billing of heat was made based on heated area.</p>	<p><i>similar consumer connected to HCS no.54, All the project related 1.502 consumers are included in the calibration campaign according to their time of connection.</i></p>
Uncertainty level	<i>low</i>	<i>n. a.</i>	<i>2 %</i>	<p><i>The value of the calibrated system is consistent to "low".</i></p> <p><i>The valid calibration permits cover the whole monitoring period.</i></p>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Measurement Principle (if applicable)	<i>Heat meter</i>	<i>n. a.</i>	<i>Ultrasonic</i>	<i>This is consistent. More specification is provided within followed.</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Instrument Type:	Heat Meter US ECHO/Botosani – Romania consisting of: 1. Heat Computer – ELTRAM CF 55 2. Twin Thermo-Resistances 3. Flow Transducer – USECHO II ELSAFLO.				<input checked="" type="checkbox"/> IRL No.26
Serial Number:	HEAT 1. Heat Computer – 07729981 2. Twin Thermo-Resistances – 0700190 3. Flow Transducer – 07725981 HOT SANITARY WATER 1. Heat Computer – 07741904; 2. Twin Thermo-Resistances – 0700103; 3. Flow Transducer – 07730054.				<input checked="" type="checkbox"/> IRL No.26
Manufacturer Model Nr.:	1. Heat Computer – ELTRAM CF 55 2. Twin Thermo-Resistances 3. Flow Transducer – USECHO II ELSAFLO				<input checked="" type="checkbox"/> IRL No.26
Specific Location:	Private House – Marica Stefan;16 Decebal St., Drobeta Turnu Severin, (PT54)				<input checked="" type="checkbox"/> IRL No.26
Measurement Range:	HEAT: 0-1Gcal/h, HOT SANITARY WATER: 0-0,5 Gcal/h				<input checked="" type="checkbox"/>
Gaps in operating time of instru-	Period: <i>There were no gaps in operating time for these instruments.</i>				<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

ment :	Default value used: <i>In case of gaps</i> according to Project Procedure PO-RT94. Heat supplied to secondary network related to the HCS the consumer is connected can be used.	<input checked="" type="checkbox"/>
	Justification: According to Project Procedure PO-RT94.	<input checked="" type="checkbox"/>
	QA/QC aspects	Conclusion and IRL
Source of data	<i>Data are collected manually monthly.</i> Type: digital	<input checked="" type="checkbox"/> IRL No.1/No.3
	Procedures: Internal Working Procedure PO-MCARTH 14 See CR #6 <i>QM PO-RT82 Management and Monitoring, PO-RT94 Determination of the Power Plant Heat and Steam delivered to consumers, training on the job</i>	CR #6 <i>IRL No.9/14</i> IRL No. 38 <input checked="" type="checkbox"/>
	Implementation of procedure: <i>The correctness of the procedure implementation has been assessed by onsite visit at the installation site and following the data flow.</i>	<input checked="" type="checkbox"/> IRL No. 21/22
	Responsibility: District Heating Department Staff	<input checked="" type="checkbox"/> IRL No.9/ 14
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are processed within District Heating Department and are archived on paper and CDs in two different locations.	<input checked="" type="checkbox"/> IRL No.14
Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 94, project data are transferred from District Heating Department to JI Project Department manually. <i>Input of data and calculation is performed by JI Department.</i>	<input checked="" type="checkbox"/> IRL No.14
	Quality of evidence	Conclusion and IRL

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 27, 28
	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>Calculation can be crosschecked with the heat supplied to secondary network considering the efficiency of the secondary network.</i>	<input checked="" type="checkbox"/>

Table 7

Parameter and instrumentation Information					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>District heat supplied to new consumers connected to the primary network</i>	<i>n. a.</i>	<i>District heat delivered to new consumers connected to the primary network</i>	<i>As it describes the heat to new consumers connected to the primary network it is consistent.</i> Corrective Action Request No. 3:	<i>CAR #3 This issue was solved.</i> <input checked="" type="checkbox"/> IRL

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

				<i>The order of parameter descriptions in the MR should follow PDD and Monitoring Manual</i>	No.1, No.3
Parameter ID (if available)	<i>$Q_{P,DH,pr.new_con}$</i>	<i>n. a.</i>	<i>$Q_{P,DH,pr.new_con}$</i>	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>Gcal</i>	<i>n. a.</i>	<i>Gcal</i>	<i>Unit is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (reading)	<i>Manually, monthly</i>	<i>n. a.</i>	<i>Manually, monthly</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (recording)	<i>monthly</i>	<i>n. a.</i>	<i>monthly</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Calibration requirements	<i>Every 4 years</i>	<i>n. a.</i>	<i>Every 4 years</i>	<p>Evidence of the latest calibration:</p> <p>1. Heat Computer BV 000112638/04.09.09</p> <p>2. Twin Thermo-Resistances BV 000112638/04.09.09</p> <p>3. Flow Transducer BV 000112638/04.09.09.</p> <p>The connection has been made in September 2009 (Commissioning Protocol dated 18.09.2009)</p>	<input checked="" type="checkbox"/> <p>IRL No.32 <i>The situation was documented for one of similar consumers recently new connected to primary network.</i> <i>All project related 197 consumers are included in the calibration campaign according to</i></p>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

					<i>their time of connection.</i>
Uncertainty level	<i>low</i>	<i>n. a.</i>	<i>2 %</i>	<i>The value of the calibrated system is consistent to "low" uncertainty level that is stated in the PDD. The valid calibration permits cover the whole monitoring period.</i>	<input checked="" type="checkbox"/>
Measurement Principle (if applicable)	<i>Heat meter</i>	<i>n. a.</i>	<i>Ultrasonic</i>	<i>This is consistent. More specification is provided within followed.</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Instrument Type:	Heat Meter ACTARIS – Romania consisting of: 1. Heat Computer – ELSONIC COMPACT 2. Twin Thermo-Resistances 3. Flow Transducer – ELSONIC COMPACT				<input checked="" type="checkbox"/> IRL No.26
Serial Number:	1. Heat Computer – 0879515; 2. Twin Thermo-Resistances – 0711708; 3. Flow Transducer – 0879515				<input checked="" type="checkbox"/> IRL No.26
Manufacturer Model Nr.:	1. Heat Computer – ELSONIC COMPACT 2. Twin Thermo-Resistances 3. Flow Transducer – ELSONIC COMPACT				<input checked="" type="checkbox"/> IRL No.26

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Specific Location:	Private House – Rosculet Lenuta; 8, Aurelian St., Drobeta Turnu Severin	<input checked="" type="checkbox"/> IRL No.26
Measurement Range:	0-1Gcal/h	<input checked="" type="checkbox"/>
Gaps in operating time of instrument :	Period: <i>There were no gaps in operating time for these instruments.</i>	<input checked="" type="checkbox"/>
	Default value used: <i>In case of gaps</i> according to Project Procedure PO-RT94.	<input checked="" type="checkbox"/>
	Justification: According to Project Procedure PO-RT94.	<input checked="" type="checkbox"/>
	QA/QC aspects	Conclusion and IRL
Source of data	<i>Data are collected manually monthly.</i> Type: digital	<input checked="" type="checkbox"/> IRL No.1/No.3
	Procedures: Internal Working Procedure PO-MCRTH 14 See CR #6 <i>QM PO-RT82 Management and Monitoring, PO-RT94 Determination of the Power Plant Heat and Steam delivered to consumers, training on the job</i>	CR #6 <i>IRL No.9/14</i> IRL No. 38 <input checked="" type="checkbox"/>
	Implementation of procedure: <i>The correctness of the procedure implementation has been assessed by onsite visit at the installation site and following the data flow.</i>	<input checked="" type="checkbox"/> IRL No. 21/22
	Responsibility: District Heating Department Staff	<input checked="" type="checkbox"/> IRL No.9/ 14
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are processed within District Heating Department and are archived on paper and CDs in two different locations.	<input checked="" type="checkbox"/> IRL No.14

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 94, project data are transferred from District Heating Department to JI Project Department manually. <i>Input of data and calculation is performed by JI Department.</i>	<input checked="" type="checkbox"/> IRL No.14
	Quality of evidence	Conclusion and IRL
Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 27, 28
	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>Calculation can be crosschecked with the balance of total heat supplied to primary network considering the efficiency of primary network.</i>	<input checked="" type="checkbox"/>

Table 8

Parameter and instrumentation Information					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>District heat sup-</i>	<i>n. a.</i>	<i>District heat deliv-</i>	<i>As it describes the heat</i>	<i>See</i>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	<i>plied to new consumers connected to the secondary network</i>		<i>ered to new consumers connected to the secondary network</i>	<i>to new consumers connected to the secondary network it is consistent.</i>	<i>CAR #3 This issue was solved. <input checked="" type="checkbox"/> IRL No.1, No.3</i>
Parameter ID (if available)	<i>Q_{P,DH,sec,new_con}</i>	<i>n. a.</i>	<i>Q_{P,DH,sec,new_con}</i>	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>Gcal</i>	<i>n. a.</i>	<i>Gcal</i>	<i>Unit is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (reading)	<i>Manually, monthly</i>	<i>n. a.</i>	<i>Manually, monthly</i> <i>When the SCADA-System will be fully operational data are monitored every our (manually and automatically) logged for the day</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Monitoring frequency (recording)	<i>monthly</i>	<i>n. a.</i>	<i>monthly</i>	<i>This is consistent</i>	<input checked="" type="checkbox"/>
Calibration requirements	<i>Every 4 years</i>	<i>n. a.</i>	<i>Every 4 years</i>	HEAT 1. Heat Computer BV 00007530/04.11.08 2. Twin Thermo-Resistances BV	<input checked="" type="checkbox"/> IRL No.33 <i>The situation was documented for one of similar con-</i>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

				<p>00007530/04.11.08 3. Flow Transducer BV 00007530/04.11.08</p> <p>HOT SANITARY WATER 1. Heat Computer BV 000096028/27.02.09 2. Twin Thermo-Resistances BV 000096028/27.02.09 3. Flow Transducer BV 000096028/27.02.09.</p> <p>HEAT :The connection has been made in September 2008 (Commissioning Protocol dated 04.11.2008) HOT SANITARY WATER: The connection has been made in August 2009</p>	<p><i>sumers recently new connected to secondary network.</i> <i>All project related 437 consumers are included in the calibration campaign according to their time of connection</i></p>
Uncertainty level	<i>low</i>	<i>n. a.</i>	<i>2 %</i>	<p><i>The value of the calibrated system is consistent to "low".</i> <i>The valid calibration</i></p>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

				<i>permits cover the whole monitoring period.</i>	
Measurement Principle (if applicable)	<i>Heat meter</i>	<i>n. a.</i>	<i>Ultrasonic</i>	<i>This is consistent. More specification is provided within followed.</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Instrument Type:	Heat Meter ACTARIS – Romania consisting of: 1. Heat Computer – ELSONIC COMPACT 2. Twin Thermo-Resistances 3. Flow Transducer – ELSONIC COMPACT				<input checked="" type="checkbox"/> IRL No.26
Serial Number:	HEAT 1. Heat Computer – 08792500 2. Twin Thermo-Resistances – 09981 3. Flow Transducer – 08792500 HOT SANITARY WATER: 1. Heat Computer – 08792500 2. Twin Thermo-Resistances – 0711222 3. Flow Transducer – 08792500				<input checked="" type="checkbox"/> IRL No.26
Manufacturer Model Nr.:	1. Heat Computer – ELSONIC COMPACT 2. Twin Thermo-Resistances – 3. Flow Transducer – ELSONIC COMPACT				<input checked="" type="checkbox"/> IRL No.26
Specific Location:	Private House Nicolici Stefan; 25, KISELEFF St., Drobeta Turnu Severin (PT10)				<input checked="" type="checkbox"/> IRL No.26
Measurement Range:	0-1 Gcal/h				<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Gaps in operating time of instrument :	Period: <i>There were no gaps in operating time for these instruments.</i>	<input checked="" type="checkbox"/>
	Default value used: <i>In case of gaps</i> according to Project Procedure PO-RT94.	<input checked="" type="checkbox"/>
	Justification: According to Project Procedure PO-RT94.	<input checked="" type="checkbox"/>
	QA/QC aspects	Conclusion and IRL
Source of data	<i>Data are collected manually monthly.</i> Type: digital	<input checked="" type="checkbox"/> IRL No.1/No.3
	Procedures: Internal Working Procedure PO-MCRTH 14 See CR #6 <i>QM PO-RT82 Management and Monitoring, PO-RT94 Determination of the Power Plant Heat and Steam delivered to consumers, training on the job</i>	CR #6 <i>IRL No.9/14</i> IRL No. 38 <input checked="" type="checkbox"/>
	Implementation of procedure: <i>The correctness of the procedure implementation has been assessed by onsite visit at the installation site and following the data flow.</i>	<input checked="" type="checkbox"/> IRL No. 21/22
	Responsibility: District Heating Department Staff	<input checked="" type="checkbox"/> IRL No.9/ 14
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are processed within District Heating Department and are archived on paper and CDs in two different locations.	<input checked="" type="checkbox"/> IRL No.14
Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 94, project data are transferred from District Heating Department to JI Project Department manually. <i>Input of data and calculation is performed by JI Department.</i>	<input checked="" type="checkbox"/> IRL No.14
	Quality of evidence	Conclusion

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

		and IRL
Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the District Heating Department. No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 27, 28
	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>Calculation can be crosschecked with the balance of total heat supplied to secondary network considering the efficiency of secondary network.</i>	<input checked="" type="checkbox"/>

2.3. Parameters measured through sampling

Table 1

Sampling information					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>Net calorific value of lignite</i>	<i>n. a.</i>	<i>Lower calorific value (MR) / Net calorific value of</i>	<i>Description of title is consistent.</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

			<i>lignite (Calculation tool)</i>		
Parameter ID (if available)	<i>CV_{P,lignite}</i>	<i>n. a.</i>	<i>CV_{P,lignite}</i>	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>kcal/kg</i>	<i>n. a.</i>	<i>kcal/kg</i>	<i>Unit is consistent.</i>	<input checked="" type="checkbox"/>
Sampling frequency	Based on onsite analysis and billing records	<i>n. a.</i>	Before delivery, for each lot of lignite	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Sampling point	<i>Onsite analysis manufacturer</i>	<i>n. a.</i>	<i>Onsite analysis manufacturer</i>	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Uncertainty level	<i>low</i>	<i>n. a.</i>	± 50 Kcal/Kg	<i>The uncertainty level of the certified analysing system is consistent to "low".</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Sampling Principle:	Systemic Samples				<input checked="" type="checkbox"/>
Methodology of Sampling:	ISO 1988				<input checked="" type="checkbox"/> IRL No.26
Sample Analysed by:	ICEMENERG – Laboratory; Address - 8, Energeticienilor Bld., Bucharest				<input checked="" type="checkbox"/> IRL No.26
Certification of Analyser/ Laboratory:	Romanian Accreditation Association – RENAR (recognized as National Accreditation Body by Order no. 354/2003 of the Ministry of Industry and Resources, issued on behalf of the Romanian Government)				<input checked="" type="checkbox"/> IRL No.26
Methodology of Sample Analysis (if applicable)	SR ISO 1928/1995				<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Measurement Range:	800 – 3000 Kcal/Kg	<input checked="" type="checkbox"/>
Gaps in sampling frequency	Period: <i>n. a.</i>	<input checked="" type="checkbox"/>
	Default value used: <i>n. a.</i>	<input checked="" type="checkbox"/>
	Justification: <i>n. a.</i>	<input checked="" type="checkbox"/>
	QA/QC aspects	Conclusion and IRL
Source of data	Type: Certificates (Record Book)	<input checked="" type="checkbox"/>
	Procedures: PO – RT – 78 <i>Fuels Calorific Values Determination</i>	<input checked="" type="checkbox"/>
	Implementation of procedure: <i>The responsible JI-Project management was interviewed during audit how sampling and analysing processes are conducted. The accreditation of the laboratory was checked and results of analyses were crosschecked with monthly reported values.</i>	<input checked="" type="checkbox"/> IRL No.10, 27, 28, 34
	Responsibility: Head of Calorimetric Laboratory	<input checked="" type="checkbox"/>
	Representativeness: Lignite samplings are split in three portions, and separate analysis are carried out at the level of Supplier and Consumer, while the third portion is kept as witness sample. In case of differences higher than 50 kcal/Kg the witness sample will be analyzed and its value will be considered as final value.	<input checked="" type="checkbox"/> IRL No.26
	Reproducibility: Lignite samplings are split in three portions, and separate analysis are carried out at the level of Supplier and Consumer, while the third portion is kept as witness sample.	<input checked="" type="checkbox"/> IRL No.26

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are processed within District Heating Department and are archived on paper and CDs in two different locations	<input checked="" type="checkbox"/> IRL No.14
Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 82: Management and Monitoring System, Project raw data are processed within the Technical Department, where from are transferred to JI Project Department, where the final calculation for CO ₂ emission reduction is made, based on the project approved methodology. Cells containing project formulae are locked	<input checked="" type="checkbox"/> IRL No.26
	Quality of evidence	Conclusion and IRL
Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the Technical Department. No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 27, 28
	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>A second analyse from each delivery is made by ROMAG TPP laboratory. In case of a deviation a backup witness sample will be analysed by both. The amount of consumed lignite is one component to calculate the fuel heat applied by the boiler. The general energy balance of the power plant that is done anyway gives the possibility of crosscheck in combination with the amount of fired lignite.</i>	<input checked="" type="checkbox"/>

Table 2

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Sampling information					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>Net calorific value of oil</i>	<i>n. a.</i>	<i>Fuel oil lower calorific value (MR) / Net calorific value of fuel oil (Calculation tool)</i>	<i>Description of title is consistent.</i>	<input checked="" type="checkbox"/>
Parameter ID (if available)	<i>CV_{P,oil}</i>	<i>n. a.</i>	<i>CV_{P,oil}</i>	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>kcal/kg</i>	<i>n. a.</i>	<i>kcal/kg</i>	<i>Unit is consistent.</i>	<input checked="" type="checkbox"/>
Sampling frequency	Based on onsite analysis and billing records	<i>n. a.</i>	For each lot of fuel oil.	<i>This is consistent.</i>	<input checked="" type="checkbox"/>
Sampling point	<i>Onsite analysis manufacturer</i>	<i>n. a.</i>	Fuel oil supplier and Consumer (before unloading)	<i>This is consistent when onsite means at TPP site before unloading.</i>	<input checked="" type="checkbox"/>
Uncertainty level	<i>low</i>	<i>n. a.</i>	± 50 Kcal/Kg	<i>The value of the certified analyse system is consistent to "low".</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Sampling Principle:	Random sampling				<input checked="" type="checkbox"/>
Methodology of Sampling:	SR ISO 1928/1995				<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

		IRL No.26
Sample Analysed by:	ICEMENERG – Laboratory; Address - 8, Energeticienilor Bld., Bucharest	<input checked="" type="checkbox"/> IRL No.26
Certification of Analyser/ Laboratory:	Romanian Accreditation Association – RENAR (recognized as National Accreditation Body by Order no. 354/2003 of the Ministry of Industry and Resources, issued on behalf of the Romanian Government)	<input checked="" type="checkbox"/> IRL No.26
Methodology of Sample Analysis	SR ISO 1928/1995	<input checked="" type="checkbox"/>
Measurement Range:	8000 – 10000 Kcal/Kg	<input checked="" type="checkbox"/>
Gaps in sampling frequency	Period: <i>n. a.</i>	<input checked="" type="checkbox"/>
	Default value used: <i>n. a.</i>	<input checked="" type="checkbox"/>
	Justification: <i>n. a.</i>	<input checked="" type="checkbox"/>
	QA/QC aspects	Conclusion and IRL
Source of data	Type: Certificates (Record Book)	<input checked="" type="checkbox"/>
	Procedures: PO – RT – 78 <i>Fuels Calorific Values Determination</i>	<input checked="" type="checkbox"/> IRL No.10
	Implementation of procedure: <i>The responsible JI-Project management was interviewed during audit how sampling and analysing processes are conducted. The accreditation of the laboratory was checked and results of analyses were crosschecked with monthly reported values. The first analyse is made by the supplier. The second analyse from each delivery is made by ROMAG TPP laboratory. In case of a deviation a backup witness sample will be analysed by both.</i>	<input checked="" type="checkbox"/> IRL No.10, 27, 28, 34
	Responsibility: Head of Calorimetric Laboratory	<input checked="" type="checkbox"/>
	Representativeness: <i>The sampling is done for every delivery of fuel oil before unloading</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	<i>into the tank storage.</i>	
	Reproducibility: <i>There are two samples that are analyzed taken at the same time by the supplier and TPP.</i>	<input checked="" type="checkbox"/>
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are processed within District Heating Department and are archived on paper and CDs in two different locations	<input checked="" type="checkbox"/> IRL No.14
Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 82: Management and Monitoring System, Project raw data are processed within the Technical Department, where from are transferred to JI Project Department, where the final calculation for CO ₂ emission reduction is made, based on the project approved methodology. Cells containing project formulae are locked	<input checked="" type="checkbox"/> IRL No.26
	Quality of evidence	Conclusion and IRL
Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the Technical Department. No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 27, 28
	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>Net calorific value of fuel oil is one component for the calculation of the boiler applied fuel heat. The balances of the boilers, only fired with oil, give the possibility of cross-check in combination with the amount of fired oil.</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

2.4. Parameters obtained through external sources and accounting data

Table 1

External sources and accounting information <i>use a separate table for each single parameter</i>					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>Quantity of lignite consumed</i>	<i>n. a.</i>	<i>Total power plant lignite consumption (MR) / Quantity of lignite consumed (Calculation tool)</i>	<i>Description of title is consistent.</i>	<input checked="" type="checkbox"/>
Parameter ID (if available)	$V_{P,lignite}$	<i>n. a.</i>	$V_{P,lignite}$	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>T</i>	<i>n. a.</i>	<i>T</i>	<i>Unit is consistent</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Description of Data / Data Refers to:	<i>Delivered and invoiced Lignite consumed in boilers of TPP According to Project Procedure "PO – RT – 81 Power Plant Fuel Consumption Determination"</i>				<input checked="" type="checkbox"/>
Date of Data:	<i>Year 2008</i>				<input checked="" type="checkbox"/>
Gaps in data	Period: <i>n. a.</i>				<input checked="" type="checkbox"/>
	Default value used: <i>n. a.</i>				<input checked="" type="checkbox"/>
	Justification: <i>n. a.</i>				<input checked="" type="checkbox"/>
	QA/QC aspects				Conclusion and IRL

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Source of data	Type: <i>invoices, weight sheets, stock survey</i>	<input checked="" type="checkbox"/>
	Responsibility: <i>TPP coal department</i>	<input checked="" type="checkbox"/> IRL No.9
	Representativeness: <i>The total amount of delivered lignite is weighted and invoiced. Monthly mass balances are representative in accordance with the produced and measured heat.</i>	<input checked="" type="checkbox"/>
Reliability of Data Source:	According to Project Procedure "PO – RT – 81 Power Plant Fuel Consumption Determination"	<input checked="" type="checkbox"/> IRL No.8
Is the Data up-to-date?	<i>All data are actual values regarding the reported years.</i>	<input checked="" type="checkbox"/>
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are processed within District Heating Department and are archived on paper and CDs in two different locations	<input checked="" type="checkbox"/> IRL No.14
Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 82: Management and Monitoring System, Project raw data are processed within the Technical Department, where from are transferred to JI Project Department, where the final calculation for CO ₂ emission reduction is made, based on the project approved methodology. Cells containing project formulae are locked	<input checked="" type="checkbox"/> IRL No.26
	Quality of evidence	Conclusion and IRL
Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the Technical Department. No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 27, 28

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>The amount of consumed lignite is one component for the calculation of the boiler applied fuel heat. The general energy balance of the power plant that is done anyway gives the possibility of crosscheck in combination with the net calorific value of lignite.</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Table 2

External sources and accounting information <i>use a separate table for each single parameter</i>					
	PDD	Meth/Tool	MR	Verified	Conclusion and IRL
Parameter title	<i>Quantity of oil consumed</i>	<i>n. a.</i>	<i>Total power plant fuel oil consumption (MR) / Quantity of fuel oil consumed (Calculation tool)</i>	<i>Description of title is consistent.</i>	<input checked="" type="checkbox"/>
Parameter ID (if available)	$V_{P,oil}$	<i>n. a.</i>	$V_{P,oil}$	<i>Parameter ID is consistent</i>	<input checked="" type="checkbox"/>
Data Unit	<i>T</i>	<i>n. a.</i>	<i>T</i>	<i>Unit is consistent</i>	<input checked="" type="checkbox"/>
	Technical aspects				Conclusion and IRL
Description of Data / Data Refers to:	<i>Delivered and invoiced oil consumed in boilers of TPP</i> According to Project Procedure "PO – RT – 81 Power Plant Fuel Consumption Determination"				<input checked="" type="checkbox"/>
Date of Data:	<i>Year 2008</i>				<input checked="" type="checkbox"/>
Gaps in data	Period: <i>n. a.</i>				<input checked="" type="checkbox"/>
	Default value used: <i>n. a.</i>				<input checked="" type="checkbox"/>
	Justification: <i>n. a.</i>				<input checked="" type="checkbox"/>
	QA/QC aspects				Conclusion and IRL

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Source of data	Type: <i>invoices, weight sheets, tank level</i>	<input checked="" type="checkbox"/>
	Responsibility: <i>Boiler department</i>	<input checked="" type="checkbox"/> IRL No.9
	Representativeness: <i>The total amount of delivered oil is weighted and invoiced. Monthly mass balances are representative in accordance with the produced and measured heat.</i>	<input checked="" type="checkbox"/> IRL No.9
Reliability of Data Source:	According to Project Procedure "PO – RT – 81 Power Plant Fuel Consumption Determination"	<input checked="" type="checkbox"/> IRL No.8
Is the Data up-to-date?	<i>All data are actual values regarding the reported years.</i>	<input checked="" type="checkbox"/>
Archiving of raw data and protection measures	According to Project Procedure PO – RT – 94 project data are processed within District Heating Department and are archived on paper and CDs in two different locations	<input checked="" type="checkbox"/> IRL No.14
Data transfer and protection of input data for calculations	According to Project Procedure PO – RT – 82: Management and Monitoring System, Project raw data are processed within the Technical Department, where from are transferred to JI Project Department, where the final calculation for CO ₂ emission reduction is made, based on the project approved methodology. Cells containing project formulae are locked	<input checked="" type="checkbox"/> IRL No.26
	Quality of evidence	Conclusion and IRL
Completeness of data	<i>Evidence of completeness of data is provided by the implemented and verified QM-Procedure. Approved monthly reports for the full monitoring period have been supplied.</i>	<input checked="" type="checkbox"/> IRL No.9
Data verification	Consistency of raw data with calculation tool: <i>Monthly reports issued by the JI-Department for the full monitoring period have been provided. These reports were checked with monthly reports issued by the Technical Department. No discrepancies have been found and all data are consistent to the calculation tool.</i>	<input checked="" type="checkbox"/> IRL No. 27, 28

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	Consistency of calculation tool with monitoring report: <i>All data provided in the Monitoring Report 2008 are consistent with the annual values in the calculation tool.</i>	<input checked="" type="checkbox"/>
Crosscheck (if available)	<i>The amount of consumed oil is one component to calculate the fuel heat applied by the boiler. The balances of the boilers, only fired with oil, give the possibility of crosscheck in combination with the net calorific value of fired oil.</i>	<input checked="" type="checkbox"/>

2.5. Other parameters not included in the methodology/tool but included in the PDD

Other information <i>use a separate table for each single parameter</i>				
	PDD	MR	Verified	Conclusion and IRL
Parameter title	<i>n. a.</i>	<i>n. a.</i>	<i>n. a.</i>	<i>n. a.</i>
Parameter ID (if available)	<i>n. a.</i>	<i>n. a.</i>	<i>n. a.</i>	<i>n. a.</i>
Data Unit	<i>n. a.</i>	<i>n. a.</i>	<i>n. a.</i>	<i>n. a.</i>
	Technical aspects			Conclusion and IRL
Description of Data / Data Refers to:	<i>Description e.g. invoice of electricity consumed, NCV of gas consumed from gas provider, IPCC</i>			
Date of Data:	<i>Date</i>			
Gaps in data	Period: <i>applicable for missing data; include several periods if necessary separated by /</i>			
	Default value used: <i>description</i>			
	Justification: <i>the theoretical most conservative approach shall be used</i>			

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	QA/QC aspects	Conclusion and IRL
Source of data	Type: <i>e.g. reports, website, certificates</i>	
	Responsibility: <i>e.g. function of responsible for the data acquisition</i>	
	Representativeness: <i>how is verified that the data is representative for the period within the relevant frequency and/or monitoring period?</i>	
Reliability of Data Source:	<i>e.g.: certification of data source</i>	
Archiving of raw data and protection measures	<i>Describe how the data will be archived, e.g. in CDs, in archive (for paper). Is there any redundancy and / or IT solution of data protection measures</i>	
Data transfer and protection of input data for calculations	<i>Manual or digital transfer from raw data source to input data for calculations (in calculation tool); how is it done and who does it? Protection measures in the calculation tool to avoid unintentional errors or data losses</i>	
	Quality of evidence	Conclusion and IRL
Completeness of data	<i>Include a statement that sufficient evidence is available, both in terms of frequency and in covering the full monitoring period. Any deviation shall also be described above in Gaps in operating time of instrument</i>	
Data verification	Consistency of raw data with calculation tool: <i>Include a statement on how the data used in the calculation tool (transferred data) has been verified against the raw data e.g. the total flow for each month has been verified based on the logbook data (raw data) available on-site and no discrepancies have been found</i>	
	Consistency of calculation tool with monitoring report: <i>Include also an statement that the data in the monitoring report is consistent with the calculation tool</i>	
Crosscheck (if available)	<i>If comparable information is available from sources other than that used in the monitoring report, then the DOE shall cross check the monitoring report against the other</i>	

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

3. Data Processing and ER calculation

Description of data processing from transferred data to final results in the calculation tool		
Step	Description	Conclusion and IRL
Consistency	<i>All abbreviations and units used in the MR and the calculation tool are consistent with the PDD. They are traceable to the raw data what clearly corresponding to parameters.</i>	<input checked="" type="checkbox"/>
Calculation Tool description	<p><i>The single sheets and parameters are clearly described and transparent. The description follows exactly the PDD and the MR. The revision number is indicated at the Front Page sheet, but issuing date was not filled into the foreseen place.</i></p> <p>Corrective Action Request No. 7</p> <p><i>Please indicate the issuing date and the corresponding version number at the Front Page sheet of the Excel MR calculation tools.</i></p> <p><i>All formulae, intermediate steps and constants described transparently including correct units and in compliance with the PDD. The transparent description of the sheets leads to long formula description for the cells with complex calculations. The values are traceable clearly by analysing the related links properly.</i></p>	<p>CAR #7</p> <p>This was solved in Version 3</p> <p><input checked="" type="checkbox"/></p> <p>IRL No.2, IRL No.4</p>
Elimination of not plausible data (if applicable)	<i>n. a.</i>	
Transformation from useable data to input data for further calculation (if applicable)	<i>n. a.</i>	

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Ex-ante data	<i>n. a.</i>	
Default parameter	<p><i>Molar masses:</i> $M_{CO_2} = 44,01 \text{ g/mol}$ $M_C = 12,01 \text{ g/mol}$</p> <p>Corrective Action Request No. 4: <i>The assignment of the values has to be changed in the PDD (beginning at page 30) and in the Calculation tool ANNEX 5_EMISSION FAKTOR DATA</i> <i>Carbon factors for fuels:</i> <i>Lignite 27,60 t C/TJ</i> <i>Fuel oil 21,10 t C/TJ</i></p> <p>Corrective Action Request No. 5: <i>These values refer to "Revised 2006 IPCC Guidelines", see PDD page 31</i></p> <p><i>Oxidation factors: Are issued by the Ministry of Environment and also used in emission calculation of EU-ETS</i> <i>Lignite 97,00 %</i> <i>Fuel oil 99,50 %</i></p>	<p>CAR #4 <i>This issue is closed.</i></p> <p>CAR #5 <i>This issue is closed.</i></p> <p><input checked="" type="checkbox"/></p>
Formulae check	<i>All formulae included in the calculation tool are in compliance with the pictured formulae in the PDD, D.1.1.2</i>	<input checked="" type="checkbox"/>
Rounding functions	<i>There were no rounding functions applied in the Calculation tool. Calculation is due to Excel properties.</i>	<input checked="" type="checkbox"/>
Calculation tool changes and protection measures	<p><i>The final calculation for CO2 emission reduction is made in the JI Project Department, based on the project approved methodology. According to Project Procedure PO – RT – 82: Management and Monitoring System, Project raw data are processed within the Technical Department, where from are transferred to JI Project Department. Data inputs into the tool are only done by authorised staff members of this department. The blank tool is prepared for data input includes Baseline Data and all calculation steps.</i></p> <p>Cells containing project formulae are locked.</p> <p>Clarification Request No. 7:</p>	<p>CR #7</p>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	<p><i>All cells of the calculation tool are unlocked for verification purposes. Please provide the clean version that is used for data inputs with the locked cells containing the project formulae.</i></p> <p><i>The calculation tool has not to be modified due to fixed calculation of the emission reduction. New connections to primary and secondary network are considered by measured values that influence the results of the calculation.</i></p>	<p><i>This was provided with final Version No.3</i> <i>IRL No.2,</i> <i>IRL No.4</i> <input checked="" type="checkbox"/></p>
Reported data	<p><i>The actual reported data in the Monitoring Report of the year 2008 are consistent with the results of the corresponding calculation tool.</i></p> <p>Corrective Action Request No. 8: <i>Emissions and emission reductions are not mentioned or described in the MR. Due to the Monitoring Plan (IRL No.5, 3.1.6) and the requirements they must be added to the MR.</i></p>	<p><i>CAR #8</i> <i>This was added in final Version No.3</i> <i>IRL No.1,</i> <i>IRL No.3</i> <input checked="" type="checkbox"/></p>

4. Additional assessment

4.1. Internal Review

Description and performance of internal review		
	Description	Conclusion and IRL
Procedure	<p><i>The QM-Procedure PO-PT 82 – Management and Monitoring System JI-Project describes the responsibilities of all project involved TPP departments. The organigram in Annex 1 illustrates the cross-linked</i></p>	<p><input checked="" type="checkbox"/> <i>IRL No.9</i></p>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

	<i>structure. Annex 2 contents the details regarding acquisition and handling of all necessary data. Finally all data, already approved at the department level are monthly provided to the JI-Department. There the delivered data are reviewed with additional raw data, e.g. daily records. The JI-Department issues a monthly JI-Project report that is reviewed and signed by PM and DPM. The approved data are put into the calculation tool. The Monitoring Report bases upon the annual results and is independently reviewed and signed by PM and DPM.</i>	
Documentation	<i>In the monthly JI-Project report (JI Process Data Log Sheet) the JI-Project Manager has to sign that the review of the data sheet and the data log has been performed and all procedures have been followed.</i>	<input checked="" type="checkbox"/> IRL No.27 / No. 28
Responsibilities	<i>The General Director of TPP ROMAG THERMO approves the Project Monitoring Reports finally.</i>	<input checked="" type="checkbox"/> IRL No.9

4.2. Peculiarities

Description of Peculiarities and unexpected Daily Events during the verification period		
	Description	Conclusion and IRL
Performance	<i>The project was implemented in steps since October 2006, finished before the end of 2007 and finally accepted in March 2008. This leads to increasing baseline and project emissions. This is because baseline emissions are only considered for reconstructed parts and with every step of implementation the efficiency of the installation in the project boundary is improving. The performance of the implemented modernisation of the district heating system leads to the expected results. There were no further peculiarities in the operation of the system in the Monitoring Period of 2008. The annual maintenance of the whole network is performed in summer season and needs only a couple of days.</i>	<input checked="" type="checkbox"/> IRL No.35
Documentation	<i>n. a.</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Measures	<i>There are no additional measures necessary then the implemented procedures and common maintenance.</i>	<input checked="" type="checkbox"/>
----------	---	-------------------------------------

4.3. Further additional requirements

Description of additional requirements to be checked		
	Description	Conclusion and IRL
<i>environmental issues</i>	<i>There are no additional requirements indicated in the PDD.</i>	<input checked="" type="checkbox"/>

4.4. Data Reporting

Description of the Monitoring Report		
	Comments and Results	Conclusion and IRL
Compliance with UNFCCC regulations	<p><i>The project is applying a project specific methodology approach. All requirements from the project specific methodology approach are fulfilled. The Monitoring Plan and the PDD are consistent.</i></p> <p><i>The Monitoring Report must include the description of the emissions and the emission reduction.</i></p> <p>Corrective Action Request No. 9:</p> <p><i>Please indicate the issuing date and version number at the Monitoring Reports.</i></p> <p><i>Verification period is from 1. January 2008 to 31 December 2008.</i></p>	<p>See CAR #8</p> <p><input checked="" type="checkbox"/></p> <p>CAR #9</p> <p>This was added in final Version No.3</p> <p>IRL No.1,</p>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

		IRL No.3 <input checked="" type="checkbox"/>
Completeness and Transparency	<p><i>The description of parameters in the MR mostly unclear. The description under 2.12 fails, because these are the baseline emissions.</i></p> <p>Corrective Action Request No. 6:</p> <p><i>Please describe the parameters in the MR more clearly, including why the parameter is reported and how it is considered in the calculation. Correct the description under 2.12 and include the announcement of the project emissions.</i></p>	CAR #6 This issue is partly solved. See CAR #8
Correctness	<i>All of the provided values were correctly transferred from the assessed calculation tool to the MR.</i>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

5. Compilation and Resolutions of CARs, CRs and FARs

Corrective Action Requests by audit team			
	Comments and Results	Ref	Conclusion and IRL
Issue	Corrective Action Request No.1 <i>GSP coordinates of the project site have to be included in the PDD</i>	1.1	<input checked="" type="checkbox"/> IRL No.0
Response	<i>Latitude 44°40 min 25.5 N, Longitude 22°41 min 18 E</i>		
Assessment	<i>GSP coordinates of the project site have been added in the PDD, v.8, that is an update of determinated PDD, v.7 with only formal changes. This was a required addition without an effect of project determination..</i>		
Issue	Corrective Action Request No.2 <i>The Parameter IDs for "District heat supplied to new consumers connected to the primary network" and "District heat supplied to new consumers connected to the secondary network" has to be included in the Monitoring Protocol, sheet: INPUT DATA_NEW CONNECTIONS</i>	2.1	<input checked="" type="checkbox"/> IRL No.2/ No.4
Response	<i>Corrected spreadsheet MR 2008</i>		
Assessment	<i>The parameter was added to the MR spreadsheet at the top of the relevant column.</i>		
Issue	Corrective Action Request No.3 <i>The order of all parameter descriptions mentioned in the MR should follow the order in the PDD and the Monitoring Manual.</i>	2.2, Table 7	<input checked="" type="checkbox"/> IRL No.1/ No.3
Response	<i>Corrected Monitoring Reports MR 2008</i>		
Assessment	<i>The order of parameters is corresponding to the PDD and Monitoring Manual.</i>		
Issue	Corrective Action Request No.4 <i>The assignment of the values for molar masses of C and CO2 has to be changed in the PDD (beginning at page 30) and in the Calculation tool ANNEX 5_EMISSION FAKTOR</i>	3.	<input checked="" type="checkbox"/> IRL No.0/

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Corrective Action Requests by audit team			
	<i>DATA.</i>		No.2 / 4
Response	<i>PDD v.8, 07.11.2009; 091107_TurnuSeverin_MR_Spreadsheet_08</i>		
Assessment	<i>The values of molar masses have been changed correspondingly in PDD and Calculation tool 2008.</i>		
Issue	<u>Corrective Action Request No.5</u> <i>The emission factors for the specific fuels refer to "Revised 2006 IPCC Guidelines", not to the revision of 1996. That has to be changed, see PDD page 31.</i>	3.	<input checked="" type="checkbox"/> IRL No.0
Response	<i>PDD V 8, updated with formal changes, was checked.</i>		
Assessment	<i>The noted reference was changed accordingly in the PDD. The right corresponding values to "Revised 2006 IPCC Guidelines" have been used already.</i>		
Issue	<u>Corrective Action Request No.6</u> <i>Please describe all the parameters mentioned in the MR (2.3. – 2.13.) more clearly, including why the parameter is reported and how it is considered in the calculation. Correct the description under 2.12 and include the announcement of the project emissions.</i>	4.4	<i>This issue is partly solved. See CAR #8</i>
Response	<i>Revised monitoring report 2008 (rev. 1) dated 07 November 2009</i>		
Assessment	<i>The description of the parameters now is correct and the characterisation is clear and reasonable.</i>		
Issue	<u>Corrective Action Request No.7</u> <i>Please indicate the issuing date and the corresponding version number at the Front Page sheet of the Excel MR calculation tools.</i>	3	This was solved in Version 3 <input checked="" type="checkbox"/> IRL No.2, IRL No.4
Response	Updated Excel MR calculation tool for 2008		
Assessment	<i>With the provided Version No.3 the front page was edited.</i>		

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Corrective Action Requests by audit team			
Issue	Corrective Action Request No.8 <i>Emissions and emission reductions are not mentioned or described in the MR. Due to the Monitoring Plan (IRL No.5, 3.1.6) and the requirements they must be added to the MR.</i>	3.	<i>This was added in final Version No.3</i>
Response	Updated Monitoring Report for 2008		<i>IRL No.1,</i>
Assessment	<i>With the provided Version No.3 the emissions calculated in the tool have been implemented in the reports.</i>		<i>IRL No.3</i> <input checked="" type="checkbox"/>
Issue	Corrective Action Request No.9 <i>Please indicate the issuing date and version number at the Monitoring Reports.</i>	4.4	<i>This was added in final Version No.3</i>
Response	Updated Monitoring Report for 2008		<i>IRL No.1,</i>
Assessment	<i>With the provided Version No.3 the issuing date and version number are indicated at the front page of the Monitoring Report.</i>		<i>IRL No.3</i> <input checked="" type="checkbox"/>
Clarification Requests by audit team			
	Comments and Results	Ref	Conclusion and IRL
Issue	Clarification Request No. 1 <i>The situation stated in the PDD regarding backpressure turbines is different to the MR (2.1).</i>	1.1	<input checked="" type="checkbox"/> <i>IRL No.0,</i> <i>IRL No.6</i>
Response	There are two backpressure turbines installed. The description in the PDD was updated in V8. The revisions in the PDD do not effect the former determination but refer only to further information and clarifications. Thus the existing positive determination opinion as basis for the approval does not change. The figures in the registered PDD did not change.		
Assessment	<i>Due to the verified situation onsite and the provided Turbine technical features in IRL 6 the situation was clarified.</i>		
	Comments and Results	Ref	Conclusion

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Corrective Action Requests by audit team			
			and IRL
Issue	Clarification Request No. 2 <i>The serial number belongs to a condensing turbine and this refers to the description in the PDD A.2. This is different to the overview in IRL 6.</i>	1.1	<input checked="" type="checkbox"/> IRL No.6
Response	Turbo-generator No. 5 is indeed a condensing unit. Respective documentation has been updated. See: ANNEX 1 - 1.1 Project Technology		
Assessment	<i>The project documentation of ROMAG TERMO TPP - Main Equipment Technical Features has been updated.</i>		
Issue	Clarification Request No. 3 <i>Due to the verified situation onsite turbo-generator no. 3 is a backpressure machine. This is different to the overview of technical features in IRL 6.</i>	1.1	<input checked="" type="checkbox"/> IRL NO.6
Response	Turbo-generator No. 3 is indeed a backpressure unit. Respective documentation has been updated. See: ANNEX 1 - 1.1 Project Technology		
Assessment	<i>The project documentation of ROMAG TERMO TPP - Main Equipment Technical Features has been updated.</i>		
Issue	Clarification Request No. 4 <i>Please provide a contract or further evidence (operation permit, concession) that the actual situation of ownership and operation will be covering the project lifetime.</i>	1.1	<i>The document has been provided.</i> IRL No.36
Response	Excerpt from Concession Contract [page 2, paragraph 4 whose translation is the following: "4. CONCESSION PERIOD: Concession period is 20 years (twenty) as of the Signing Date of the Concession Contract"]		
Assessment	<i>The concession period of 20 years, beginning with the signed contract on 19.12.2003, covers the project lifetime.</i>		<input checked="" type="checkbox"/>
Issue	Clarification Request No. 5 <i>Please show how the JI-Project Department collaborates with the Local Environmental Au-</i>	1.4	<i>Evidence of LEA as-</i>

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Corrective Action Requests by audit team			
	<i>thority due to procedure PO-RT 82 (IRL no.9) in this case and how a verification of these issues was done by the authority.</i>		<i>essment activities has been provided. IRL No.37 <input checked="" type="checkbox"/></i>
Response	Periodic site visits are made by the LEA representatives to control/evaluate various aspects related to the project progress. Reports containing the output of the control/evaluation activities are issued.		
Assessment	<i>The protocols including checklist, documenting the assessment of the LEA for the Monitoring period 2008 has been provided.</i>		
Issue	Clarification Request No. 6 <i>Please provide Internal Working Procedure PO-MCRTH 14.</i>	2.2	<i>IRL No.38 <input checked="" type="checkbox"/></i>
Response	Internal Working Procedure PO-MCRTH 14 (being an internal procedure it is only in Romanian language)		
Assessment	<i>This Internal QM-Procedure for management and quality assurance of technical media has been provided and describes responsibilities and processes due to ISO 9001/14001.</i>		
Issue	Clarification Request No. 7 <i>All cells of the calculation tool are unlocked for verification purposes. Please provide the clean version that is used for data inputs with the locked cells containing the project formulae.</i>	3	<i>IRL No.2, No.4 <input checked="" type="checkbox"/></i>
Response	Respective documentation has been updated.		
Assessment	<i>All cells of the calculation tool including project formulae are locked in the final version V No.3.</i>		
Forward Action Requests by audit team			
	Comments and Results	Ref	Conclusion and IRL
Issue	Forward Action Request No. 1	<i>Reference</i>	

Verification Protocol

Project Title: Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin (2008)

Date of Completion: 2010/06/03

Number of Pages: 71

Corrective Action Requests by audit team			
Response		from tables above e.g. 4.4	
Assessment			

PERIODIC VERIFICATION

“Energy efficiency improvement of the district heating system in Drobeta
Turnu-Severin” **(2008)**



Industrie Service

Annex 2: Information Reference List

Final Report	03-06-2010	Verification of the JI Project, track 1 Energy Efficiency Improvement of the District Heating System in Drobeta Turnu-Severin, 2008 Information Reference List	Page 1 of 4	 Industrie Service
--------------	------------	--	----------------	--

Ref. No.	Author/Editor/ Issuer	Title/Type of Document. Publication place	Issuance and/or submission date(dd/mm/yyyy)	Additional Information (Relevance in CDM Context)
0.	Grue & Hornstrup	PDD "Energy efficiency improvement of the district heating system in Drobeta Turnu-Severin, V 8 http://ji.unfccc.int/JIITLProject/DB/09PG38GL1EVUCD8D8JUNQEI4RPHUVJ/details	07/11/2009	V 1, 15/06/2006 V 8, 07/11/2009
1.	ROMAG-THERMO	Monitoring Report 2007, V 3	07/11/2009	V 3, 07/01/2010
2.	ROMAG-THERMO	091107_Turnu_Severin_MR_Spreadsheet_07	07/11/2009	V 3, 07/01/2010
3.	ROMAG-THERMO	Monitoring Report 2008, V 3	07/11/2009	V 3, 07/01/2010
4.	ROMAG-THERMO	091107_Turnu_Severin_MR_Spreadsheet_08	07/11/2009	V 3, 07/01/2010
5.	Grue & Hornstrup	Monitoring Plan, Guidelines and Procedures, Version 4	2009-11-07	
6.	ROMAG-THERMO	ROMAG TERMO TPP - Main Equipment Technical Features	07/11/2009	
7.	ROMAG-THERMO	Calibration and validity permits for steam and heat metering system	National Institute for Metrology 2004 – 2008, certificate	Steam and heat output, heat to consumers
8.	ROMAG-THERMO	PO – RT 81 Fuel consumption	Internal document – 2007 – 2008	
9.	ROMAG-THERMO	PO – RT 82 Management and Monitoring System, JI-Project, QM System	Internal QM document, May 2009	
10.	ROMAG-	PO – RT 78 Coal calorific value determination, ROMAG - TERMO Power Plant	Internal document –	Laboratory

Final Report	03-06-2010	Verification of the JI Project, track 1 Energy Efficiency Improvement of the District Heating System in Drobeta Turnu-Severin, 2008 Information Reference List	Page 2 of 4	 Industrie Service
--------------	------------	--	-------------	--

Ref. No.	Author/Editor/ Issuer	Title/Type of Document. Publication place	Issuance and/or submission date(dd/mm/yyyy)	Additional Information (Relevance in CDM Context)
	THERMO	Calorimetrical Laboratory	2007 – 2008	standard
11.	ROMAG-THERMO	Organizational scheme, JI Project Responsibilities	Internal document – 2009	
12.	ROMAG-THERMO	PO – RT 84 Data collection during emergencies (back-up)	Internal document – 2009	
13.	ROMAG-THERMO	Manual logbook (8 hours) for energy sent to primary network. Form 351	Internal document – 2007 – 2008	
14.	ROMAG-THERMO	PO – RT 94 Heat and steam recording procedure	Internal document – 2009	
15.	ROMAG-THERMO	Daily average heat/steam records	02/07 2007 and 05/11 2008	Cross checks
16.	ROMAG-THERMO	PO – RT 83 Personnel training procedure	2009	
17.	ROMAG-THERMO	Training participation lists	2007/2008	
18.	ROMAG-THERMO	Training session in JI monitoring procedure	Version 6, 15.06.2009	
19.	ROMAG-THERMO	Steam_heat_metering equip.pdf		Serial no. of meters.
20.	ROMAG-THERMO	Steam_metering equip.pdf		Serial no. of meters.
21.	ROMAG-THERMO	Heat Delivered to the Primary Network 1.jpg	08-09 2009	Manual recording of the meters

Final Report	03-06-2010	Verification of the JI Project, track 1 Energy Efficiency Improvement of the District Heating System in Drobeta Turnu-Severin, 2008 Information Reference List	Page 3 of 4	 Industrie Service
--------------	------------	--	-------------	--

Ref. No.	Author/Editor/ Issuer	Title/Type of Document. Publication place	Issuance and/or submission date(dd/mm/yyyy)	Additional Information (Relevance in CDM Context)
22.	ROMAG-THERMO	Heat Delivered to the Primary Network 2.jpg	08-09 2009	Manual recording of the meters
23.	ROMAG-THERMO	Calibrare_cantare.pdf		Calibration for weighbridge for coal
24.	ROMAG-THERMO	Docji_13.pdf	07.2007	Cross check for July 2007
25.	ROMAG-THERMO	Docji_13.pdf	11.2008	Cross check for November 2008
26.	ROMAG-THERMO	Information and details regarding VP, 2. Monitoring Plan Implementation	11/2009	
27.	ROMAG-THERMO	JI Process Data Log Sheet	Jan 2007 – Dec 2007	Monthly reports
28.	ROMAG-THERMO	JI Process Data Log Sheet	Jan 2008 – Dec 2008	Monthly reports
29.	S.C. Termo Actic S.R.L., Drobeta Turnu-Severin	Calibration protocol Pollustat EX, Private HCS Gheorghe Titeica Nr. 38	05.12.2006	Consumer connected to primary network, sample
30.	BRML Craiova	Calibration protocols of all devices HCS P.T.3	14.01.2009/ 29.11.2006	heat supplied to secondary network, sample PT 3
31.	S.C. Termo	Calibration protocol US Echo DN 25/ DN 20; casa: Marica Stefan, Decebal Nr. 16	12.11.2007/	heat supplied to

Final Report	03-06-2010	Verification of the JI Project, track 1 Energy Efficiency Improvement of the District Heating System in Drobeta Turnu-Severin, 2008 Information Reference List	Page 4 of 4	 Industrie Service
--------------	------------	--	----------------	--

Ref. No.	Author/Editor/ Issuer	Title/Type of Document. Publication place	Issuance and/or submission date(dd/mm/yyyy)	Additional Information (Relevance in CDM Context)
	Actic S.R.L., Drobeta Turnu-Severin	(PT 54)	21.07.2008	consumers, secondary network, sample
32.	RAAN Suc. ROMAG-Thermo, Sectia Termoficare	Calibration protocol, New consumer primary network; Private HCS Ruculescu Lenuta, Aurelian No.8/10	04.09.2009	New consumer connected to primary network, sample
33.	RAAN Suc. ROMAG-Thermo, Sectia Termoficare	Calibration protocol, New consumer secondary network, Casa Nicolici Stefan, Kiseleff Nr.25 (PT10)	04.11.2008/ 27.02.2009	New consumer connected to secondary network, sample
34.	S.C. Filiala ICEMENERG S.A. Bucurest	Determination of oxidation factor, 2007 / 2008	31.05.2007/ 31.03.2009	
35.	ROMAG-THERMO	Momorandum related to the implementation process of the JI-Project	07/11/2009	
36.	ROMAG-THERMO	Excerpt from Concession Contract	19.12.2003	Concession period
37.	APM MH	LEA Reports, Semi Annual QA – Checklist for local EPA, 2007, 2008	17.01.2008 / 06.07.2009	
38.	ROMAG-THERMO	PO-MCRTH 14, Internal QM-Procedure, Technical Media	July 2009	
39.	Romanian DFP	Letter of Approval	23.11.2006	