



Industrie Service

Choose certainty.
Add value.

Verification Report

S.C. Hidroelectrica S.A.

First Periodic Verification of the JI Track 1 Project
**“Modernization of 4 hydro units in Portile de Fier II
hydrostation ”**

Monitoring period : 01-01-2008 to 31-12-2011

Report No. 600500937

28 November 2012

TÜV SÜD Industrie Service GmbH
Carbon Management Service
Westendstrasse 199 - 80686 Munich - GERMANY

FIRST PERIODIC VERIFICATION

“Modernization of 4 hydro units in Portile de Fier II hydrostation”

Page 1 of 21



Industrie Service

Report No.	Date of first issue	Version No.:	Revision date	No. of pages
600500937	04-07-2012	4	28-11-2012	21
Subject:			First Periodic Verification of the JI Track 1 project “Modernization of 4 hydro units in Portile de Fier II hydro station”	
Executing Operational Unit:				
TÜV SÜD Industrie Service GmbH, Carbon Management Service Westendstrasse 199 - 80686 Munich, Federal Republic of Germany				
Project Participants involved in the JI activity:				
S.C. Hidroelectrica S.A. (project owner and client) Str. Constantin Nacu, Nr. 3, Sector 2 Ro – 020995 Bucuresti Romania				
SenterNovem Juliana van Stolberglaan 3 2595 CA The Hague, The Netherlands (now part of Agentschap NL) NL Energie& Klimaat Croeselaan 15 3521 BJ Utrecht, The Netherlands)				
Registration number / Project Title			Registered as RO1000204 on: http://ji.unfccc.int/JI_Parties/DB/5T6DPV4N47Z6OW3HI1GX0QKFOUI6YL/viewDFP	
Monitoring period:			01-01-2008 to 31-12-2011	
First Monitoring Report (version/date)			Version 1.0 / 20-02-2012	
Final Monitoring Report (version/date)			Version 4.0 / 05-11-2012	



Summary:

The Certification Body “climate and energy” of TÜV SÜD Industrie Service GmbH has been ordered by S.C. Hidroelectrica S.A to carry out the first periodic verification of the registered JI Track-1 project “Modernisation of 4 hydro units in Portile de Fier II hydrostation”.

The verification is based on requirements of the UN Framework Convention on Climate Change (UNFCCC) and the host country specific requirements. In this context, the specific guidance from the Designated Focal Point (host country) in his responsibility for the approval of JI track 1 projects, relevant provisions set by the Marrakech Accords, the Kyoto Protocol and the JI-SC (Supervisory Committee) for JI Track-2 projects have been taken into consideration. The verification of this JI project has been performed by document review, interviews by e-mail and inspection on-site.

The verifier confirms that the project is implemented as planned and described in re-determined project design documents (TÜV SÜD Determination Report No. 1068445b, Revision 2, determination date 14-11-2008), Monitoring Plan rev. 1, dated October 2007 with Annexes 5, 6 and 7 and the Baseline Study performed by KPMG in July 2002. Installed equipment being essential for generating emission reduction runs reliably and is calibrated appropriately. The monitoring system is in place and the project does generate GHG emission reductions. The verifier confirms also that the monitoring plan of the project activity is in accordance with the applied methodology. The management of S.C. Hidroelectrica S.A. is responsible for the preparation of the GHG emissions data and the reported GHG emissions reductions on the basis set out within the Monitoring Plan rev. 1, dated October 2007 with Annexes 5, 6 and 7.

The verifier can confirm that the GHG emission reduction for the entire monitoring period is calculated without material misstatements. Our opinion relates to the project’s GHG emissions and resulting GHG emissions reductions reported and related to the valid project baseline and monitoring plan, and further associated documents. The emission reductions calculated for this monitoring period are higher than the values indicated in the Monitoring Plan rev. 1, dated October 2007. In 2008 and 2011 the generated ERUs were lower than predicted ex-ante (as average value), meanwhile, in 2009 and 2010 the generated ERUs were higher than predicted. These differences are due to the variable hydrology on the Danube in the specific year.

Based on the information received and evaluated we confirm the following statement:

Reporting period: from 01/01/2008 to 31/12/2011

Verified Emission Reduction in the above reporting period:

2008: 49,174 t CO₂e (leakage and project emissions are 0)

2009: 74,471 t CO₂e (leakage and project emissions are 0)

2010: 121,951 t CO₂e (leakage and project emissions are 0)

2011: 36,587 t CO₂e (leakage and project emissions are 0)

Total Emission reductions: **282,183 t CO₂e.**

Assessment Team Leader:

Robert Mitterwallner

Assessment Team Members:

Georgios Agrafiotis

Constantin Zaharia

Technical reviewer :

Olena Maslova, Karin Wagner

Certification Body responsible:

Thomas Kleiser



Abbreviations

ACM	Approved Consolidated Methodology
AIE	Accredited Independent Entity
BM	Build Margin
CAR	Corrective Action Request
CM	Combined Margin
CMP	Conference of the Parties serving as the Meeting of the Parties to the Kyoto Protocol
CO_{2,e}	Carbon dioxide equivalent
CAR	Corrective action request
CR	Clarification Request
DFP	Designated Focal Point
DVM	Determination and Verification Manual, Annex 4 of JISC 19 report
EIA / EA	Environmental Impact Assessment / Environmental Assessment
ER	Emission Reduction
EUR	Emission Reduction Units
FAR	Forward Action Request
FSR	Feasibility Study Report
GHG	Greenhouse Gas(es)
GWP	Global Warming Potential
IPCC	Intergovernmental Panel on Climate Change
IRL	Information Reference List
JI	Joint Implementation
KP	Kyoto Protocol
MP	Monitoring Plan
MR	Monitoring Report
NGO	Non-Governmental Organisation
OM	Operational Margin
PDD	Project Design Document
PP	Project Participant
QA/QC	Quality assurance/quality control
TÜV SÜD	TÜV SÜD Industrie Service GmbH
UNFCCC	United Nations Framework Convention on Climate Change



Main Documents (referred to in this report)

Methodology (name / version)	Project specific, JI track 1	
Scope	1.	
Technical Area	1.2	
Determined PDD:	TÜV SÜD Determination Report No. 1068445b, Revision 2, dated 14-11-2008	
Revised Monitoring Plan:	October 2007, rev. 1	
	Version	Date
Published Monitoring Report	1.0	22-02-2012
Revised Monitoring Report	4.0	05-11-2012
Project documentation link:	http://ji.unfccc.int/JI_Parties/DB/5T6DPV4N47Z6OW3HI1GX0QKFOUI6YL/viewDFP	

Table of Contents

Page

1	Introduction	5
1.1	Objective	5
1.2	Scope.....	5
1.3	GHG Project Description.....	6
2	Methodology.....	7
2.1	Verification Process	7
2.2	Verification Team	8
2.3	Review of Documents	8
2.4	On-site Assessment and follow-up Interviews	9
2.5	Quality of Evidence to Determine Emission Reductions.....	9
2.6	Resolution of Clarification, Corrective Action and Forward Action Requests	9
2.7	Internal Quality Control	10
3	Verification Results	11
3.1	FARs from PRE-JI Verification.....	11
3.2	Project Implementation in accordance with the re-determined Project design documents	13
3.3	Compliance of the Monitoring System with the Monitoring Plan.....	13
3.4	Assessment of Data and Calculation of Greenhouse Gas Emission Reductions	17
4	Summary of Findings	19
5	Verification Statement.....	21

Annex 1: Verification Protocol

Annex 2: Information Reference List



1 INTRODUCTION

1.1 OBJECTIVE

S.C. Hidroelectrica S.A. has commissioned an independent verification by TÜV SÜD Industrie Service GmbH (TÜV SÜD) of its determined JI track 1 project “Modernization of 4 hydro units in Portile de Fier II hydrostation”.

The objective of the periodic verification is to verify that actual monitoring systems and procedures are in compliance with the monitoring systems and procedures described in the monitoring plan for the respective period. Furthermore, the periodic verification evaluates the GHG emission reduction data and expresses a conclusion with a high, but not absolute, level of assurance about whether the reported GHG emission reduction data is free of material misstatements and verifies that the reported GHG emission data is sufficiently supported by evidence, i.e. monitoring records.

The verification shall consider both quantitative and qualitative information on emission reductions. Quantitative data comprises the monitoring reports submitted to the verifier by the project entity. Qualitative data comprises information on internal management controls, calculation procedures, and procedures for transfer, frequency of emissions reports, review and internal audit of calculations/data transfers.

The verification work ensures that the project activity is assessed against all applicable JI Track-1 requirements in the host country as specified by the Designated Focal Point (DFP) for JI/CDM project implementation in Romania. The JI requirements as reference include also the JI modalities and procedures and subsequent decisions by the COP/MOP and documents released by the JI-SC and available on the UNFCCC JI website <http://ji.unfccc.int/index.html>.

The objective of the verification work ensures that the project activity complies with the requirements as specified in the appendix B of the JI guidelines on the aforementioned UNFCCC JI website <http://unfccc.int/resource/docs/2005/cmp1/eng/08a02.pdf#page=2>. These guidelines are considered valid for JI Track-2 as also for JI Track-1. According to this assessment TÜV SÜD should:

- Ensure that the project activity has been implemented and operated as per the registered MP and that all physical features (technology, project equipment, monitoring and metering equipment) of the project are in place;
- Ensure that the published MR and other supporting documents provided are complete and verifiable and in accordance with applicable JI Track-1 requirements in the host country;
- Ensure that actual monitoring systems and procedures comply with the monitoring systems and procedures described in the monitoring plan and the applicable approved methodology;
- Evaluate the data recorded and stored as per the methodology of approved MP;
- Evaluate the GHG emission reduction data and express a conclusion about whether the reported GHG emission reduction data is verifiable and sufficiently supported by evidence, i.e. monitoring records.

1.2 SCOPE

The verification scope encompasses an independent and objective review and ex-post determination of the monitored reductions in GHG emissions by the Accredited Independent Entity.

FIRST PERIODIC VERIFICATION

“Modernization of 4 hydro units in Portile de Fier II hydrostation”

Page 6 of 21



Industrie Service

The verification is based on the submitted monitoring report, the determined project design documents including its monitoring plan approved by the Romanian DFP and the baseline study; the applied monitoring methodology, relevant decisions, clarifications and guidance from the CMP and the JISC and any other information, references and national regulations relevant to the project activity's resulting emission reductions. These documents are reviewed against the requirements of the Kyoto Protocol, the JI Modalities and Procedures and related rules and guidance as well as against requirements as described in the Romanian National Guidelines and Procedures for JI Track 1 projects.

Based on the requirements in the JI DVM, TÜV SÜD has applied a rule-based approach for the verification of the project. The principles of accuracy, completeness, relevance, reliability and credibility were combined with a conservative approach to establish a traceable and transparent verification opinion.

The verification considers both quantitative and qualitative information on emission reductions.

The verification is not meant to provide any consultancy towards the client. However, stated requests for clarifications, corrective and/or forward actions may provide input for improvement of the monitoring activities.

The project was finally approved by the Designated Focal Point for JI/CDM project implementation in the Romania on 24.12.2010 and has the reference number RO-1000204. Relevant associated documents are published on the Romanian web page at: http://www.mmediu.ro/protectia_mediului/schimbari_climatice/5_Proiecte_JI/SITUATIA-PROIECTELOR-JI-LoE-SI-LoA.pdf

1.3 GHG PROJECT DESCRIPTION

Project activity:	“Modernization of 4 hydro units in Portile de Fier II hydrostation”
DFP registration number:	RO1000204
UNFCCC link:	http://ji.unfccc.int/JI_Parties/DB/5T6DPV4N47Z6OW3HI1GX0QKFOUI6YL/viewDFP
Project Participants:	S.C. Hidroelectrica S.A. (project owner) SenterNovem (now : Agentschap NL)
Location of the project:	Ostrovul Mare, Romania N:44° 18' 30”,E:22° 34’(Latitude 44.30°,Longitude 22.56°)
Date of registration as track 1:	24-12-2010
Starting date of the crediting period:	01-01-2008

The purpose of this project is to generate additional electricity at the refurbished turbine-generator units on the Portile de Fier II Hydro Station (in the following: PdF II) in Romania and supply the generated electricity in to the public grid. The PdFII hydro power plant is situated at Km 863 + 358 on the river Danube 60 km downstream of the city of Drobeta Turnu Severin, Romania. The initial hydro power project Portile de Fier II was developed and implemented by the Romanian and Yugoslavian authorities and became operational in 1985. The whole power plant complex is managed by the joint Serbian-Romanian commission. It consists of 2 identical parts, 8 turbine units on the Serbian side and 6 units on the Romanian side, each with a rated capacity of 27 MW. Besides this hydropower complex, two additional units are installed and operational in the power plant Gogosu, at the Romanian side, which is not part of this project activity.



Industrie Service

The 8 turbine-generator units on the Portile de Fier II hydro power station were refurbished from the initial 27 MW rated capacity up to 31 MW rated capacity. The works have been implemented by VA TECH HYDRO Ltd. and consisted of the replacement of the turbine blades. The present JI track 1 project activity covers only the additional electricity generation at the refurbished four turbine-generator units on the Portile de Fier II hydro power station, HG 3, HG 4, HG 5 and HG 7.

The implementation status of the project in the verification period is presented in the table below:

Turbine Unit	Commissioning of the refurbished Turbine Unit
HG 3	12-01-2007
HG 4	21-12-2005
HG 5	24-01-2008
HG 7	06-03-2009

2 METHODOLOGY

2.1 VERIFICATION PROCESS

The verification process is based on the approach depicted in JI guidelines and, in particular, refer to the Guidance on Criteria for baseline setting and monitoring, chapter C. – Guidance on monitoring. Accordingly relevant requirements as set by the JI-SC for JI Track-2 are applied for JI Track-1 as long as there are no further host country requirements existing (and indicated in the national regulations and procedures) specifically for JI Track 1 projects. Following the good monitoring practices and its reporting the approved Joint Implementation Determination and Verification Manual (DVM) was also taken into consideration.

Standard auditing techniques have been adopted. The means of verification for the fulfillment of the requirements and reporting are as per the DVM. Thus, compliance with JI relevant guidance is ensured, too.

The work starts with a contract review and the appointment of the TÜV SÜD assessment team covering the technical scope(s) and area(s) as well as relevant host country experience for evaluating of this JI project activity. The principles of consistency and transparency, impartiality, independency and safeguarding against conflicts of interest and confidentiality were considered by the TÜV SÜD Certification Body (CB) and the management of the department before accepting the verification contract.

Once the monitoring report is published on TÜV SÜD publication platform in internet “netinform” (as it is the matter of JI Track-1 project), the TÜV SÜD assessment team has carried out a desk review, on-site inspection, follow-up actions, resolution of issues identified and prepared a verification report.

The verification report and other supporting documents then undergo an internal quality control by the TÜV SÜD Certification Body before its submission to the DFP (host country) for the final approval.

In order to ensure transparency, assumptions are clearly and explicitly stated, audit evidences and further background material are clearly referenced in Annex 2 of this report. Project and methodology-specific checklists and a customised protocol have been developed for the project. The protocol shows criteria (requirements) in a transparent manner, the discussion of each criterion by the assessment team and results of the subsequent verification.

The verification protocol (Annex 1) serves the following purposes.

- It organizes, details and clarifies the requirements a JI project is expected to meet;



- It ensures a transparent verification process where the verifier will document how a particular requirement has been proved and the conclusion provided by the verifying team

The findings are the essential part of this verification report, which are summarized in Annex 1 of the verification protocol

2.2 VERIFICATION TEAM

The appointment of the verification team takes into account the technical area(s), sectoral scope(s) and relevant host country experience required amongst team members for verifying the ER achieved by the project activity in the relevant monitoring period for this verification.

The verification team consisted of the following members:

Name	Qualification	Coverage of scope 1	Coverage of technical area 1.1	Host country experience
Robert Mitterwallner	ATL	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Georgios Agrafiotis	Verifier	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Constantin Zaharia	Verifier			<input checked="" type="checkbox"/>

The on-site verifier was Mr. Constantin Zaharia. During the on-site visit from 28-02-2012 to 01-03-2012 a telephone conference has been held with participation of the other 2 team members and the PP.

Robert Mitterwallner is located at TÜV SÜD Industrie Service in Munich since 1990 and has a background as auditor for environmental management systems, as expert in environmental permit procedures for industrial plants and as expert for environmental impact studies assessment. He has received training in the JI determination/verification and CDM validation/verification process and applied successfully as GHG Determiner, GHG Validator, GHG Verifier as well as Assessment Team Leader and Technical Reviewer for climate change projects, among others, in the scope energy industries. He is experienced with hydro power determinations/validations and is appointed as Auditor for Renewable Energy Certification.

Georgios Agrafiotis has been appointed as verifier for the determination, validation and verification in JI and for voluntary projects within TÜV SÜD Industrie Service GmbH. He received intensive training at Carbon Management Service with TÜV SÜD and participated as GHG auditor in more than 40 validation and verification processes with various scopes.

Constantin Zaharia is environmental engineer and is working as freelancer for the Carbon Management Service Department of TÜD SÜD Industry Service GmbH, Germany.

2.3 REVIEW OF DOCUMENTS

The first MR was assessed based on all the relevant documents. The aims of the desk review were:

- verify the completeness of the data and the information presented in the MR,
- check the compliance of the MR with respect to the monitoring plan depicted in the registered Determination Report. Particular attention to the frequency of measurements,



Industrie Service

the quality of the metering equipment including calibration requirements, and the quality assurance and quality control procedures was paid,

- evaluate the data management and the quality assurance and quality control system in the context of their influence on the generation and reporting of emission reductions.

A complete list of all documents reviewed is available in annex 2 of this report.

2.4 ON-SITE ASSESSMENT AND FOLLOW-UP INTERVIEWS

From 28-02-2012 to 01-03-2012, TÜV SÜD performed a physical site inspection including on-site interviews with the project participants as to:

- confirm the implementation and operation of the project,
- review the data flow for generating, aggregating and reporting of the monitoring parameters,
- confirm the correct implementation of procedures for operation and data collection,
- cross-check the information provided in the MR with other sources,
- check the monitoring equipment against the monitoring plan presented in the project design documents and the applied methodology, including calibrations, maintenance, etc.,
- review the calculations and assumptions used to obtain the GHG data and ER,
- check if the QC/QA procedures are in place for preventing and correcting of errors or/and omissions in the reported data.

A list of the persons interviewed during this verification activity is included in annex 2.

2.5 QUALITY OF EVIDENCE TO DETERMINE EMISSION REDUCTIONS

Among several evidences submitted, the following relevant and reliable evidence material has been used by the audit team during the verification process:

- License (IRL2)
- Monitoring Plan (IRL4)
- Monitoring reports (IRL33)
- Raw data (IRL13)
- Data from cross-check instruments (IRL14-IRL15)
- Quality assurance and quality control documents (IRL4, IRL8)
- Calibration documents (IRL16)

Sufficient evidences and data covering the full verification period in the required frequency is available to validate the figures stated in the final monitoring reports. The source of the evidences and data will be discussed in chapter 3 of this report. Specific cross-checks have been done in cases when further sources were available. The monitoring report figures were checked by the audit team against the raw data. It can be confirmed that the data collection system meets the requirements of the monitoring plan as per the applied methodology.

2.6 RESOLUTION OF CLARIFICATION, CORRECTIVE ACTION AND FORWARD ACTION REQUESTS

The objective of this phase of the verification process is to resolve any outstanding issues, which require clarification for TÜV SÜD's conclusion on the reported GHG emission reduction.



Industrie Service

The findings raised as Forward Action Requests (FARs) (if any) indicated in previous reports (determination/verification) were discussed and resolved during this phase through communication between the PP and TÜV SÜD.

To guarantee the transparency of the verification process, the concerns raised in the desk review, the on-site audit assessments and the follow up interviews together with the responses that have been provided by the PP are documented in Annex 1 (verification protocol).

A **Corrective Action Request** is raised where TÜV SÜD identifies:

- non-conformities in monitoring and/or reporting with the monitoring plan and/or methodology;
- that the evidence provided is not sufficient to prove conformity;
- mistakes in assumptions, data or calculations that impair the ER calculations;
- FARs raised during determination or previous verifications that are not solved until the on-site visit.

A **Clarification Request** is raised where TÜV SÜD does not have enough information or the information is not transparent in order to confirm a statement or data.

A **Forward Action Request** is raised where TÜV SÜD identifies that monitoring and/or reporting require special attention or adjustments for the next verification period.

Information or clarifications provided as a response to a CAR, CR or FAR could also lead to a new request.

2.7 INTERNAL QUALITY CONTROL

As a final step of the verification process, the verification documents including the verification report and the annexes have to undergo an internal quality control by the Certification Body (CB) “climate and energy”. Technical Reviewers appointed by the CB carry out the review work. Each report has to be finally approved either by the Head of the CB or the Deputy. In case one of these two persons is part of the assessment team, the approval can only be given by the person who is not a part of the assessment team work. If the documents have been satisfactorily approved, the Request for Issuance is submitted to the involved parties along with the relevant documents.



3 VERIFICATION RESULTS

In the following sections, the results of the verification are stated. The verification results relate to the project performance as documented and described in the re-determined project design documents, the Determination Report, and the final Monitoring Reports (version 4, submitted on 05-11-). The verification findings for each verification subject are presented below.

3.1 FARS FROM PRE-JI VERIFICATION

No FARs resulted from the determination. Five FARs have been raised in the TÜV SÜD Initial and Pre-JI Verification Report No. 600500232, dated 06-06-2011:

Forward Action Request 1:
<p>QM/QA application on Project activity: Please provide operational procedures regarding implementation of the approved QM/QA systems related to the emission reduction project activity (data cross check, meter calibration cross check, data transfer cross check).</p>
<p>FAR 1, means of verification The Annex 5 of the Monitoring Plan (IRL 8) together with updated procedures PO-HE-PF-138 and PO-HE-PF-190 (IRL 21, 22) including QM/QA activity and the procedures related to the JI Project have been submitted. The QM/QA system is documented and operational as checked during the site verification.</p>
<p>FAR 1, changes in the MR or related documents n/a</p>
Forward Action Request 2
<p>Emission Reductions Calculation: For a systematic cross check of the measured raw data and the data used for the emission reduction calculations, following information has to be provided for the next periodic verification: - An excel workbook (with parameter description for each column) with the same model equations should be provided for a systematic cross check of the daily and monthly results (instead of using the implicit FORTRAN calculation). - Indication of any deviation between the monthly measured electricity data at the internal electricity meters and the external meters (owned and operated by the state entity OMEPA) installed at the 110 kV high-voltage line (operated by CEZ).</p>
<p>FAR 2, means of verification During the verification excel workbooks (IRL 38) were provided to the audit team: Spot checking between the monthly measured electricity data at the internal electricity meters and the external meters (IRL 14,15) was performed during the audit showing adequate results</p>
<p>FAR 2, changes in the MR or related documents n/a</p>
Forward Action Request 3
<p>Monitoring Report Format The Monitoring Report has to follow the CDM MR template of UNFCCC.</p>



FAR 3, means of verification
The Monitoring Report (IRL 33) has been checked and it is confirmed that the CDM MR template of UNFCCC was used.
FAR 3, changes in the MR or related documents
n/a
Forward Action Request 4
<i>Project Description</i>
A transparent project description has to be integrated in the Monitoring Report as follows: - Scope of the Project (increase of turbine capacity and turbine efficiency of four turbine units HG3, HG4, HG35 and HG7 by refurbishment works) - The cascade system covering both PdF I and PdF II and impact on plant operation (interdependance) - Information on the implementation of refurbishment works at each turbine unit and the incommissioning dates (timeline) - Information on power generation forecast due to project implementation and the measured power of the refurbished turbine units and discussion of any deviations -. Information on the impact of the operational status (turbine history: repair/maintenance etc.) of the turbines related to power generation.
FAR 4, means of verification
As part of the change in MR template, (see FAR 3 above), a project description has been integrated in the Monitoring Reports, Chapter B.1 (IRL 33).
FAR 4, changes in the MR or related documents
n/a
Forward Action Request 5
<i>Monitoring and Data management</i>
The monitoring report has to refer to monthly data reading & recording and transfer procedure(s) at the external meters by OMEPA (or CEZ). Any periodic meter calibration has to be mentioned in the MR. - Monthly data sheet containing the electricity measured at the external electricity meter and supplied to the grid signed by Hidroelectrica and the grid operator (CEZ) staff has to be provided as annex to the MR. - Monthly data sheet containing the data on supplied electricity to the grid read & recorded at the internal electricity meters covering the verification period have to be provided as annex to MR. - An Excel workbook with a cross check of data recorded at the external meter (installed at the 110 kV TM line at the TM station) and at the internal meter onsite (SCADA) covering the verification period has to be provided.
FAR 5, means of verification
The following documents were provided: - MR with monthly data reading & recording and transfer procedure(s) at the external meters by OMEPA. The calibrations (main/back-up) are included too (IRL 16) - Invoices with the grid operator CEZ (IRL 13) - Data recorded at the external meter (installed at the 110 kV TM line at the TM station) and at the internal meter onsite (SCADA) covering the verification period were provided



for cross-check (IRL 14)
FAR 5, changes in the MR or related documents
n/a

3.2 PROJECT IMPLEMENTATION IN ACCORDANCE WITH THE RE-DETERMINED PROJECT DESIGN DOCUMENTS

The project is implemented according to the final Monitoring Plan, incl. annexes. The refurbished turbine unit HG5 was re-started on 24-01-2008 and the refurbished turbine unit HG7 was re-started on 06-03-2009.

The Project consists of:

- Replacement of blades at turbine-generator units HG3, HG4, HG5 and HG7 at the PdF II hydro station as to increase electricity generation capacity (refurbishment)
- Turbine efficiency increase achieved by the refurbishment works

The verifier confirms, through the visual inspection of the turbines and corresponding design schemes that all physical features of the proposed JI project activity including data collecting and storage systems have been implemented in accordance with the final Monitoring Plan, incl. annexes. The project as described above is completely operational since 11-01-2007, as was confirmed during on-site visit.

In the monitoring period 01-01-2008 to 31-12-2011, the result of the emission reductions with 282,183 t CO_{2,e} differs from the estimated value of 217,000 t CO_{2,e} in the final Monitoring Plan dated October 2007 because the estimated values are calculated with the energy produced in the average hydraulic year. The difference occurs due to the hydrology on the Danube in the specific year.

The following table summarizes the difference between PDD estimations and Project emissions:

Year	2008	2009	2010	2011	Total ERU
CEF (tCO ₂ /GWh)	838	819	800	781	-
ERU (t CO ₂)	55,000	55,000	53,500	53,500	217,000
ERU (tCO ₂) realised	49,174	74,471	121,951	36,587	282,183


3.3 COMPLIANCE OF THE MONITORING SYSTEM WITH THE MONITORING PLAN

The monitoring system has been implemented in accordance with the re-determined monitoring plan incl. annexes (IRL 4).

All parameters during the monitoring period were monitored and evaluated as per the Monitoring Plan. Hereby following parameters have been verified (meter specific details see chapter 2.2. of the protocol):

Data / Parameter:	P
Data unit:	MWh
Description:	Electricity generated by the hydro units: The hourly output for each hydro unit (P) is measured at the terminals of each unit by class 0.2% ABB meters installed both in the Romanian and in the Serbian power plants.



	<p>The net electricity is calculated by subtracting the internal consumption calculated as 1% of the total energy produced.</p> <p>The net electricity measured at the 110 kV high-voltage TM station :” Stația 110/20/6 KV Ostrovul Mare, calibrated and maintained by Elster Rometrics S.R.L. in accordance with the regional grid operator CEZ, are used as back-up in case of failure of a turbine meter together with the correspondent meter of the turbine – see below.</p> <p>Data from TB meters are contained in the monthly protocols signed by the Hidroelectrica and the grid operator Transelectrica (represented by the regional grid operator SC CEZ Distribuție COMC SA).</p> <p>Data from HG meters are automatically sent to the Serbian part and checked twice per year during the official meetings.</p>
<p>Source of data used:</p>	<p>The scheme below presents the meter connection. With green colour are the Project units.</p>  <p>The net electricity measured at the 110 kV high-voltage TM station :” Stația 110/20/6 KV Ostrovul Mare”, (TB I, TB II and TB III) is the data source used for back-up.</p> <p>Following data sources were used :</p> <ul style="list-style-type: none"> - net electricity data recorded at meters on 110 kV HV line (CEZ) - raw data recorded at the meters at the turbine-generator units (Hidroelectrica) - SCADA data recorded and archived at Hidroelectrica HQ in Turnu Severin <p>The metering equipment used has been calibrated according to the requirements of the approved monitoring plan, e.g. the meters are checked by the company Elster Rometrics S.R.L. in accordance with the regional grid operator CEZ. CEZ acts for the grid operator Transelectrica and is in charge of the maintenance and calibration of the metering devices. The accuracy of the used meters is 0.2 %.</p>
<p>Means of verification/Comments:</p>	<p>According to the project specific methodology, the net electricity supplied to the grid is measured hourly and recorded monthly. The hourly measured electricity is used in applied model equations as to determine the additional electricity achieved by the refurbishment works. This additional electricity amount consists of two components : $E_A + E_B$</p> <p>$E_A = E_a + E_b$</p> <ul style="list-style-type: none"> - E_a : Additional electricity achieved by the refurbishment of the turbine blades. E_a is determined with the hourly measured Electricity data. - E_b : Additional electricity achieved by the improved efficiency of the turbine-generator units. E_b is determined by using the hourly measured electricity together with the calculated head in the efficiency head-power chart developed by the company EPFL. - E_B : Additional electricity achieved by the enhanced energy potential in the entire Portile de Fier cascade following the refurbishment works and the elevation of the head at PdF II. Only $\frac{1}{4}$ of the E_B is considered in the final balances, because $\frac{1}{2}$ of E_B is attributed to the power complex on the Serbian side of the cascade, $\frac{1}{2}$ of the remaining amount is considered for 4 of the total 8 units at PdF II.



	The hourly data (IRL 29) included in the workbook has been verified with data in the monthly logbooks (IRL 24) and by random daily checks (see Annex 1). AIE confirms that the data management is in compliance with para. 101 of the DVM.																																																				
Cross-check	<p>The electricity output of the turbine-generator units is measured with the meters installed at the turbine. The measured electricity at the 110 kV Transelectrica (CEZ) 110 kV TM station is measured by CEZ in accordance with the national grid operator Transelectrica..</p> <p>The electricity data recorded by the meters at the 110 kV HV station Transelectrica have been cross checked against the measurements of the meters at the turbines (IRL 14). The deviation is found to be less than 1 % and therefore within the approved uncertainty level.</p> <p>The meters situation is presented in the table below:</p> <table border="1"> <thead> <tr> <th rowspan="2">Meter</th> <th rowspan="2">Parameter</th> <th rowspan="2">Serial number</th> <th colspan="2">metrological verification report</th> </tr> <tr> <th>Number</th> <th>Validity (years) Calibration date</th> </tr> </thead> <tbody> <tr> <td>HG3 (G3)</td> <td>Energy produced (main)</td> <td>2698070</td> <td>152737/23.11.06</td> <td>8 2006</td> </tr> <tr> <td>HG4 (G4)</td> <td>Energy produced (main)</td> <td>2688032 2685387</td> <td>01524900/08.11.05 2195790/10.09.10</td> <td>5 2005 8 2010*</td> </tr> <tr> <td>HG5 (G5)</td> <td>Energy produced (main)</td> <td>2709048</td> <td>1529289/26.09.07</td> <td>8 2007</td> </tr> <tr> <td>HG7 (G7)</td> <td>Energy produced (main)</td> <td>2720905</td> <td>2192291/15.01.09</td> <td>8 2009</td> </tr> <tr> <td>HG6</td> <td>Energy produced (backup)</td> <td>5010056</td> <td>1524516/23.08.05</td> <td>5 2005**</td> </tr> <tr> <td>HG8</td> <td>Energy produced (backup)</td> <td>5019949 2698069</td> <td>01521698/18/09.03 0152737/23.11.2006</td> <td>10 2003 8 2006</td> </tr> <tr> <td>TB II</td> <td>Energy delivered 110kV block II Unit #3 and #4 (backup)</td> <td>5013693</td> <td>1520283/07.11.2002</td> <td>10 2002</td> </tr> <tr> <td>TB III</td> <td>Energy delivered 110kV block III Unit #5 and #6 (backup)</td> <td>5013695</td> <td>1520664/14.02.2003</td> <td>10 2006</td> </tr> <tr> <td>TB IV</td> <td>Energy delivered 110kV block IV Unit #7 and #8 (backup)</td> <td>5013694 5013692</td> <td>1522459/31.03.04 0152739/23.11.06</td> <td>5 2004 10 2006***</td> </tr> </tbody> </table> <p>* calibrated on 10.09.2010 and installed on 28.09.2010 ** calibrated on 23.08.2005 and installed on 22.06.2011 *** calibrated on 23.11.2006 and installed on 10.04.2009</p> <p>The cascade effect is subject to bi-lateral cross-check between Romania and Serbia.</p>	Meter	Parameter	Serial number	metrological verification report		Number	Validity (years) Calibration date	HG3 (G3)	Energy produced (main)	2698070	152737/23.11.06	8 2006	HG4 (G4)	Energy produced (main)	2688032 2685387	01524900/08.11.05 2195790/10.09.10	5 2005 8 2010*	HG5 (G5)	Energy produced (main)	2709048	1529289/26.09.07	8 2007	HG7 (G7)	Energy produced (main)	2720905	2192291/15.01.09	8 2009	HG6	Energy produced (backup)	5010056	1524516/23.08.05	5 2005**	HG8	Energy produced (backup)	5019949 2698069	01521698/18/09.03 0152737/23.11.2006	10 2003 8 2006	TB II	Energy delivered 110kV block II Unit #3 and #4 (backup)	5013693	1520283/07.11.2002	10 2002	TB III	Energy delivered 110kV block III Unit #5 and #6 (backup)	5013695	1520664/14.02.2003	10 2006	TB IV	Energy delivered 110kV block IV Unit #7 and #8 (backup)	5013694 5013692	1522459/31.03.04 0152739/23.11.06	5 2004 10 2006***
Meter	Parameter				Serial number	metrological verification report																																															
		Number	Validity (years) Calibration date																																																		
HG3 (G3)	Energy produced (main)	2698070	152737/23.11.06	8 2006																																																	
HG4 (G4)	Energy produced (main)	2688032 2685387	01524900/08.11.05 2195790/10.09.10	5 2005 8 2010*																																																	
HG5 (G5)	Energy produced (main)	2709048	1529289/26.09.07	8 2007																																																	
HG7 (G7)	Energy produced (main)	2720905	2192291/15.01.09	8 2009																																																	
HG6	Energy produced (backup)	5010056	1524516/23.08.05	5 2005**																																																	
HG8	Energy produced (backup)	5019949 2698069	01521698/18/09.03 0152737/23.11.2006	10 2003 8 2006																																																	
TB II	Energy delivered 110kV block II Unit #3 and #4 (backup)	5013693	1520283/07.11.2002	10 2002																																																	
TB III	Energy delivered 110kV block III Unit #5 and #6 (backup)	5013695	1520664/14.02.2003	10 2006																																																	
TB IV	Energy delivered 110kV block IV Unit #7 and #8 (backup)	5013694 5013692	1522459/31.03.04 0152739/23.11.06	5 2004 10 2006***																																																	

Data / Parameter:	Head
Data unit:	m
Description:	The upstream and downstream water levels are measured by level meters ("Telelimnmetru") positioned on the Danube river. The head is calculated as

FIRST PERIODIC VERIFICATION

“Modernization of 4 hydro units in Portile de Fier II hydrostation”



Industrie Service

	the difference between the measured upstream water level data and downstream water level data .The measuring devices are constructed as to avoid any disturbances caused by waves (“hydraulic noise”) or floating effects. The accuracy of the level meter devices is 0.15% (checked during the re-determination of the project – IRL 32).
Source of data used:	Electronic raw data gained from automatic readings of the level-meters are transferred electronically to the SCADA system. The calculated head data is used for the determination of efficiency factors in the head-power charts established by EPFL.
Means of verification/Comments:	<p>According to the applied calculation model, the water levels are monitored continuously; they are read hourly and recorded monthly. The difference between upstream and downstream level data results in the Head.</p> <p>The hourly data (IRL 29) included in the workbook has been verified with data in the monthly logbooks (IRL 24) and by random daily checks (see Annex 1). AIE confirms that the data management is in compliance with para. 101 of the DVM.</p>
Cross-check	The maintenance and calibration of the level-meters is controlled by the Romanian and Serbian authorities in charge of the hydro power plant operations at Portile de Fier II. The cross-check by Romanian and Serbian authorities is continuous. The annual calibration of the devices is performed by geodesic measurements led by the common technical staff of both sides. Together with the total electricity production data, the head is included also into the regular bi-annual reports and cross checked in meetings (IRL 20).

Data / Parameter:	Increased efficiency $\Delta \eta_t$
Data unit:	%
Description:	<p>Turbine efficiency factors are determined by using the measured hourly generated electricity and the calculated head in the model data head-power chart developed by EPFL (Ecole Federal Polytechnic Lausanne).</p> <p>The efficiency factors in the unfurbished status are determined in a separate head-power chart. The difference is used in the model to calculate the energy increase due to turbine efficiency improvements, as outlined in the Monitoring Plan.</p>
Source of data used:	The entity EPFL has developed a simulation model for the refurbished turbines. The model data for the reference (non-furbished) turbines was simulated as well. The turbine efficiency η_t was determined by using the recorded hourly energy and the head and apply them in to the model data for refurbished and non-refurbished turbines. The difference $\Delta \eta = (\eta_{tr} - \eta_{tn})$ is indicated as the increase in efficiency.
Means of verification/Comments:	<p>According to the model equations described in the Monitoring Plan, the efficiency factors are read on the head-power charts established by EPFL. The hourly determined head / power data pair is used to read the efficiency factors under refurbished and non-furbished conditions.</p> <p>In ranges where the head-power data chart does not have matching model data, the next available lower power data at the same head is chosen and the efficiency readings are repeated with the new data pair (same head/lower power).</p> <p>The hourly data (IRL 29) included in the workbook has been verified with data in the monthly logbooks (IRL 24) and by random daily checks (see Annex 1). AIE confirms that the data management is in compliance with para. 101 of the DVM.</p>



Cross-check	<p>The project participant has handed over the complete head-power chart regarding the refurbished/non-furbished conditions.</p> <p>In ranges where the head-power data chart does not have a matching model data, the next available lower power data at the same head is chosen and the efficiency readings are repeated with the new data pair (same head/low power). The data was cross checked on exemplary head/power data pairs and found to be correct and conservative.</p>
-------------	--

The monitoring activities are strictly organised and written down in the re-determined Monitoring Plan. The responsibilities are determined and quality assurance measures are implemented on-site. The clear distribution of the monitoring duties has been demonstrated by the staff during the on-site visit (IRL 8).

The staff gets regular training on monitoring procedures (IRL 37 of the First Periodic Verification). The company Hidroelectrica has a certified quality and environmental management system (ISO 9001, ISO 14001), where the training and qualification procedures have been described and implemented.

3.4 ASSESSMENT OF DATA AND CALCULATION OF GREENHOUSE GAS EMISSION REDUCTIONS

All data have been available and all the parameters have been monitored in accordance with the monitoring plan.

The reported data of P, H, η_t , have been cross-checked against other sources available as explained above in chapter 3.3. As a result, the verifier confirms that the data of P, H, η_t are consistent and viable.

The input data of the calculations have been checked against the raw data. The verifier confirms that there are no deviations between raw data and input data. The audit team has been provided with data covering the whole verification period (01-01-2008 to 31-12-2011).

The calculations are based on a FORTRAN programme. The verification team performed spot checks for the whole monitoring period 2008 – 2011 (see the Annex 1 - Verification Protocol). Moreover, any value of the excel documents can be traced back using the information for “Head”, “Power” and ASTRÖ model – “ASTRÖ Test Report No. T241”. There were no inconsistencies found. The algorithms and formulas of the Fortran program have been checked during on-site visit by spot checks (four spot checks for each of the monitoring year 2008 – 2011, see Annex 1). Based on the random spot checks done on-site and his expertise, the verifier confirms that the algorithms and formulas implemented in the Fortran program were verified and accepted. Furthermore, the verifier confirms that the algorithms and formulas given in the monitoring reports are consistent with those in the Fortran program.

In the case of $\Delta\eta_t$, the turbine efficiency increase has been chosen in a conservative manner as described in chapter 3.3.

The external grid emission factor was fixed ex-ante

The electronic transfer of raw data to usable data was cross checked. No mistakes have been detected.

FIRST PERIODIC VERIFICATION

“Modernization of 4 hydro units in Portile de Fier II hydrostation”

Page 18 of 21



Industrie Service

The observations of the audit team left no doubt that the monitoring process has been implemented in accordance with the procedures described in the Monitoring Plan presented in the determined project design documents.

As already pointed out in chapter 3.2 of this report, the monitored emission reductions were lower than the estimated value in the final Monitoring Plan ver. 1 dated October 2007. The reason is that the estimated values are calculated with the energy produced in the average hydraulic year and in fact 2008 and 2011 resulted in a rather low water flow compared to the average value as of the MP, meanwhile 2009 and 2010 were years with a relatively high flow. This justification is deemed to be reasonable for the AIE.



4 SUMMARY OF FINDINGS

The verifier can confirm that the published MR and related documents are complete and verifiable in accordance with the JI track 1 requirements. All the findings raised by the verification team, the responses by the PPs and the conclusion of the audit team are presented in Annex 1.

The means of verification and resulting changes in the MR or related documents are summarized in the table below:

<p><u>Corrective Action Request 1:</u> On the first page of the MRs a date and a version number shall be included.</p>
<p>CAR 1, means of verification The new Monitoring Reports include on the first page: Version 2, July 19, 2012 (IRL 33), as checked with the documents.</p>
<p>CAR 1, changes in the MR or related documents MR version 2</p>
<p><u>Corrective Action Request 2:</u> - All grammar mistakes, formal mistakes, typos, inconsistencies and non-conservative assumptions have to be revised in the MR</p>
<p>CAR 2, means of verification Corrections have been made, as checked in the new Monitoring Reports (IRL 33):</p> <ul style="list-style-type: none"> - The “net value” corrected in MRs 2009-2011 - The yearly ERUs values are rounded - The SI units and abbreviations are correctly used - A legend has been included at page 6 for identification of the scheme - The year 2012 has been excluded from calculations - In the table with meters calibration has been indicated the date of the last calibration performed - The discussion presented in Chapter E.6 regarding the revision of the monitoring methodology has been deleted - Chapter E.5 has been reviewed - In Chapter E.1 the formula for baseline calculation is now included - The monitoring parameters are now consistent with MP
<p>CAR 2, changes in the MR or related documents MR version 2</p>
<p><u>Corrective Action Request 3:</u> In the documents “E_200x”:</p> <ul style="list-style-type: none"> - Title is missing - The parameters Ebr and Enet are not defined - URE is used for emission reduction (English) - The data presented in Excel files are not transparent <p>Correction is requested</p>
<p>CAR 3, means of verification The “E-200x” files include a title and were corrected. The parameters Ebr and Enet are defined in the new version of the Monitoring Report (IRL 33, 35)</p>
<p>CAR 3, changes in the MR or related documents MR version 2</p>
<p><u>Corrective Action Request 4:</u> There is no header with data/units in the Excel files</p>



Correction is requested
CAR 4, means of verification
The new excel files include a header with data/units (IRL34), however see CAR 6 below.
CAR 4, changes in the MR or related documents
Excel calculation files ver. 02
<u>Corrective Action Request 5</u>
Chapter E.6 shall be revised considering only the difference between ex-ante values estimated in the MP ver.1 dated October 2007 and Project values.
CAR 5, means of verification
The Monitoring Reports, Version 2, July 19, 2012, is corrected (IRL 33).
CAR 5, changes in the MR or related documents
MR version 2
<u>Corrective Action Request 6</u>
<ol style="list-style-type: none"> 1. The Excel calculation files have the same name as the initial ones. A version number shall be included in the name of the files 2. The hour “1” from 01/01/yyyy is missing 3. Definition of the parameters η_{ref} and η_{next} is missing
CAR 6, means of verification
The new Excel calculation files, version 02.1, (IRL 38) have been provided and all the corrections performed
CAR 6, changes in the MR or related documents
Excel calculation files ver. 02.1
<u>Clarification Request 1:</u>
According to the document “evidenta contori PFI si PFII.docx” (IRL 16), on 22.06.2011, the meter QYG5019956 has been replaced, but there is no information regarding the new meter installed. Evidence regarding the new meter installed at HG 6 on 22.06.2011 shall be provided to the TUV SUD verification team.
CR 1, means of verification
The new meter, QWG 002685388 (IRL 37) has been installed on 13.06.2012 and between 30.05 2011 – 05.07.2012 the unit HG 6 has been out of operation (IRL 36) due to modernisation
CR 1, changes in the MR or related documents
N/A
<u>Clarification Request 2:</u>
An explanation regarding the low energy production during the year 2011 and high energy production in year 2010 is requested.
CR 2, means of verification
During 2011 the flow on Danube was low, respectively 4209 m ³ /s comparing with the median stream flow for Danube of 5520 m ³ /s; 2011 was a very dry year. This information has been compared with level meter records and found consistent
CR 2, changes in the MR or related documents
N/A



5 VERIFICATION STATEMENT

TÜV SÜD Industrie Service GmbH has performed the first periodic verification of the JI track 1 project: “Modernization of 4 hydro units in Portile de Fire II hydro station”.

The verification is based on the currently valid documentation of the UN Framework Convention on Climate Change (UNFCCC) and takes into account in general all requirements for JI projects as well as specific national regulations as described in the Romanian National JI Track I Procedure of the Romanian DFP.

The management of SC Hidroelectrica S.A. is responsible for the preparation of the GHG emissions data and the reported GHG emission reductions on the basis set out within the project re-determined Monitoring Plan.

The verifier can confirm that:

- the development and maintenance of records and reporting procedures are in accordance with the monitoring plan;
- the units HG3, HG4, HG5 and HG7 are operated as planned and described in the project design document;
- the installed equipment being essential for generating emission reduction runs reliably and is calibrated appropriately;
- the monitoring system is in place and generates GHG emission reductions data;
- the GHG emission reductions are calculated without material misstatements;
- the monitoring plan in Monitoring Report is as per the re-determined MP
- that the re-determined monitoring plan is in accordance with the approach taken regarding baseline setting and monitoring (please see Appendix B of the JI Guidelines – Decision 9 COP/MOP).

Our opinion is based on the project GHG emissions and resulting GHG emission reductions reported, which have been determined through the approved project baseline, monitoring plan and associated documents.

Based on the information we have checked and evaluated, we confirm the following statement:

Reporting period: from 01-01-2008 to 31-12-2011

Emission reductions in 2008:	49,174
Emission reductions in 2009:	74,471
Emission reductions in 2010:	121,951
Emission reductions in 2011:	36,587

Total Emission Reductions (ERU): 282,183 t CO₂e

Munich, 28-11-2012

Munich, 28-11-2012

Thomas Kleiser
Certification Body “climate and energy”

Robert Mittewallner
Assessment Team Leader

FIRST PERIODIC VERIFICATION

“Modernization of 4 hydro units in Portile de Fier II hydrostation”



Industrie Service

Annex 1: Verification Protocol

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

Table of Contents

Project Activity Implementation	
1.1. Technology	
1.2. Organization	
1.3. Quality Management System	
1.4. Remaining FARs from previous Verifications (or forwarded issues of validation report)	
2. Data Management System	
2.1. Description	
2.2. Raw Data Archiving and Protection measures	
2.3. Data transfer	
2.4. Data Processing	
3. Monitoring Plan Implementation	
3.1. List of Parameter to be monitored	
3.2. Monitoring Instrumentation	
3.2.1. Instrument (QWG002685387 ELSTER)	
3.2.2. Instrument (QYG002688032 ELSTER)	
3.2.3. Instrument (QYG002 698 070, ELSTER)	
3.2.4. Instrument (QWG002 709 048, ABB)	
3.2.5. Instrument (QWG002 720 905, ABB)	
3.2.6. Instrument (QYG 5019956, ABB)	
3.2.7. Instrument (QWG002698069, ABB)	
3.2.8. Instrument (YWG 005 013 693, ABB)	
3.2.9. Instrument (YWG005 013 695, ABB)	
3.2.10. Instrument (YWG005013692, ELSTER)	
3.2.11. Instrument (Level meters, TLN)	
3.3. Sampling Information (not relevant)	
3.4. Accounting information (not applicable)	
3.5. External Data	
3.6. Others (not applicable)	
4 Data Verification	
4.1 Internal Review	
4.2 Usage of default values (not applicable)	
4.3 Reproducibility	
4.4 Peculiarities	
4.5 Reliability and Plausibility	
4.6 Completeness and Correctness	
5 Additional requirements (not relevant)	
6 Data Reporting	

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Project Activity Implementation

1.1. Technology

PDD	Verified Situation	Conclusion
Location (s)		
<p>Description / Address:</p> <p>The project Portile de Fier II is located on the island Ostrovul Mare at the Danube river 60 km downstream of the city Drobeta Turnu Severin.</p> <p>The large hydropower plant Portile de Fier II consists of 8 turbine + generator units. The refurbished (new turbine blades) turbine units No. 3, 4, 5 and 7 are considered within the project boundary "CO₂ reduction by modernization of 4 hydro units within Portile de Fier II". The purpose of the project is to increase the installed power and the efficiency of the existing units No. 3, No. 4, 5 and 7 and reduce the fossil fuel power generation.</p>	<p>The project site has been visited on 29 February 2012. The turbine + generator units and corresponding measuring and maintenance equipment were checked and documented (print screens). The operational control center within the plant has been visited. Furthermore the HV TM-station (operated and maintained by CEZ) has been entered for meter readings.</p>	<input checked="" type="checkbox"/>
GPS coordinates:	N: 44° 18' 30", E: 22° 34'	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

PDD	Verified Situation	Conclusion
Technical Equipment – Main Components		
<p>Component 1 : Turbine unit HG 4 Horizontal bulb type turbine</p>	<p>The refurbished unit No.4 was commissioned on 21.12.2005.</p>	<input checked="" type="checkbox"/>
<p><i>Technical Features</i> <i>Turbine unit HG 4</i> The original installed capacity of the turbine unit 3 (27 MW) was increased to 31.4 MW after refurbishment, The type of the refurbished turbines is KOT 32-7,80 – horizontal Kaplan turbines. The maximum power is 32.5 MW. Maximum water flow for electricity production is 475 m³/s (earlier 425 m³/s).</p> <p><i>Generator HG 4 :</i> The generator was refurbished by ABB..</p>	<p>The refurbishment works for the turbine + generator unit included many components :</p> <ul style="list-style-type: none"> - turbine - generator - auxiliary installation and - automation <p>The power increase was achieved by a flow rate increase from 425 m³/s to 475 m³/s per turbine unit. Further power increase was achieved by modifications at the turbine equipment (efficiency increase). The refurbishment works were completed by VA TECH (turbine).</p> <p>The generators are all identical. The generators are capsulated, synchronous horizontal of bulb type, directly coupled to the hydraulic driving turbines. The type is IM 5402 (A4). Design power 32.00 MVA. Voltage: 6.3 kV. Current: 2933 A. Rotation speed: 62.5 rot/min.</p> <p>The cooling of the units is provided by processed water : There are separate cooling systems for stator and rotor. The turbine oil is cooled by a separate close circuit (water + heat exchangers).</p>	<input checked="" type="checkbox"/>
<p>Component 2 : Turbine unit HG 3</p>	<p>Similar with HG 4</p>	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

PDD	Verified Situation	Conclusion
<p><i>Component 2 :</i> <i>Technical Features</i> <i>Turbine HG 3</i></p> <p><i>Generator HG 3</i></p>	The refurbished turbine unit No.3 was set in operation on 12.01.2007.	<input checked="" type="checkbox"/>
<p>Component 3 : Turbine HG 5 see description for No. 4</p>	The turbine unit No.5 was set in operation by 24.01.2008.	<input checked="" type="checkbox"/>
<p><i>Component 3 :</i> <i>Technical Features</i> <i>Turbine HG 5 :</i> see description for turbine No. 4</p> <p><i>Generator HG 1</i></p>	Similar with HG 4	<input checked="" type="checkbox"/>
<p>Component 4 : Turbine HG 7</p>	The turbine unit No.7 was set in operation by 06.03.2009.	<input checked="" type="checkbox"/>
<p><i>Component 4 :</i> <i>Technical Features</i> <i>Turbine HG 7 :</i></p> <p><i>Generator HG 7</i></p>	Similar with HG 4	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

PDD	Verified Situation	Conclusion
Operation Status during verification		
Approvals / Licenses N/A	The operation of the refurbished units and the supply of the additional generated energy into the grid was approved by ANRE licence issued on 24.07.2001 and updated on 08.07.2005. Validity period 25 years.	<input checked="" type="checkbox"/>
Actual Operation Status N/A	Under construction <input type="checkbox"/> In operation <input checked="" type="checkbox"/> Out of operation <input type="checkbox"/>	<input checked="" type="checkbox"/>
Remarks to Special Operational Status During the Verification Period	The operation regime of the power plant is linked to the national grid demands and to demand of the contractors. Evidence on the annual operation time (turbine log) for the turbines No. 1,2,3 for the whole crediting period 2008 – 2011 has been provided to the verification team IRL (17). Overflow has been documented for each of the monitoring period 2008 – 2011 (IRL 15 – Sesiunea 74 - 84). (Serbian-Romanian_Sessions)	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

1.2. Organization

PDD	Verified Situation	Conclusion
Project Participant (s)		
Entity / Responsible person: S.C. Hidroelectrica S.A. is the plant operator and project owner. Senter Novem is the purchaser of the generated ERUs.	The hydro power plant is operated and managed by S.C. Hidroelectrica S.A., a state owned company. The generated electricity is supplied into the Romanian power grid.	<input checked="" type="checkbox"/>
CDM / VER Project management: As per the contract No. ERU 01/01 and internal management decision No. 370, Mr. Dragos Zachia signs for general executive and Mr. Dragos Novac is in charge of the technical implementation and management of the project.	Mr Dragos Novac is the executive in charge of the project implementation. Mr. Cristian Bocse is responsible for the implementation of the methodologies for the calculation of ERUs . Mrs. Dana Horhoianu is coordinator of the project at Hidroelectrica Headquarters in Bucharest.	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

1.3. Quality Management System

PDD	Verified Situation	Conclusion
Quality Management Manual : Hidroelectrica S.A. implements a QM system ISO 9001 at its headquarters in Bucharest.	Quality control and quality assurance procedures concerning the “CO2 reduction project” at the power plant PdF I are not integrated in the existing Quality Management Systems (ISO 9001, ISO 14001, OHSAS 18001) implemented in Hidroelectrica S.A. However, the procedures on data processing, calibration and maintenance of metering devices, operation of turbine equipment and internal reviews are included in the current working procedures “Reglementari SCDE” common for Romanian/Serbian parties (IRL 20)	<input checked="" type="checkbox"/>
Responsibilities: Mr. Dragos Zachia is in charge of the project management coordination and implementation.	An organigramme with general responsibilities in the project management has been provided to the audit team. Mr. Christian Bocse in charge of data processing and calculation procedures. Staff in charge of other important topics like calibration and maintenance of metering devices, management of SCADA data acquisition and processing system, plant manager of PdF II (Mr. Dot) has not been named in the organigramme. See Annex 5 to MP (IRL 8).	<input checked="" type="checkbox"/>
Qualification and Training: Mr. Christian Bocse is responsible for the technical process design.	Technical details on the project were explained by Mr. Christian Bocse. He is also in charge of the methodology for the calculation of additional energy amounts. Information on the metering devices (calibration, functionality), process diagramme (single line diagram) and data processing were provided by Mr. Ciprian Rachitan. Mr. Danut Caplea is responsible for the SCADA system and data safety measures.	<input checked="" type="checkbox"/>
Implementation of QM-system	Evidence on the implementation of quality management efforts linked with the data acquisition and safety (e.g. ISO 9001, ISO 14001 and OHSAS) provided during the audit.	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

1.4. Remaining FARs from previous Verifications (or forwarded issues of validation report)

Remaining Requests from Previous Verifications	Summary of project owner response	Audit team conclusion
<p><u>Forward Action Request No.1</u></p> <p><i>QM/QA application on Project activity:</i></p> <p>Please provide operational procedures regarding implementation of the approved QM/QA systems related to the emission reduction project activity (data cross check, meter calibration cross check, data transfer cross check).</p>	<p>- The QM/QA activity and the procedure therein are described in Annex 5 of the Monitoring Plan</p>	<p>The Annex 5 to MP has been checked and it can be confirmed that all the steps, starting with raw data up to the Monitoring Report elaboration, are included (IRL 8).</p> <p>This issue is closed.</p>
<p><u>Forward Action Request No.2</u></p> <p><i>Emission Reductions Calculation:</i></p> <p>For a systematic cross check of the measured raw data and the data used for the emission reduction calculations, following information has to be provided for the next periodic verification:</p> <p>- An excel workbook (with parameter description for each column) with the same model equations should be provided for a systematic cross check of the daily and monthly results (in-</p>	<p>During the verification the following were provided to the audit team:</p> <p>- An excel workbook (with parameter description for each column) with the same model equations.</p> <p>- spot checking of the deviation between the monthly measured electricity data at the internal electricity meters and the external meters was performed during the audit showing adequate results</p>	<p>The documents have been provided and checked.</p> <p>This issue is closed.</p>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Remaining Requests from Previous Verifications	Summary of project owner response	Audit team conclusion
<p>stead of using the implicit FORTRAN calculation).</p> <p>- Indication of any deviation between the monthly measured electricity data at the internal electricity meters and the external meters (owned and operated by the state entity OMEPA) installed at the 110 kV high-voltage line (operated by CEZ).</p>		
<p><u>Forward Action Request No.3</u></p> <p><i>Monitoring Report Format</i> The Monitoring Report has to follow the CDM MR template of UNFCCC.</p>	<p>The CDM MR template of UNFCCC was used when issuing the Monitoring Report format.</p>	<p>The following documents have been provided:</p> <ul style="list-style-type: none"> • “PdF II 2008 eng 20 feb 2012” (and for 2009, 2010 and 2011) • PdF II 2008 eng final (and for 2009, 2010 and 2011), dated 12/03/2012. This document is a result of the discussions during the site verification. <p>Both documents follow the CDM MR template of UNFCCC, however</p> <p><u>Corrective Action Request No.1</u> On the first page of the MRs a date and a version number shall be included.</p>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Remaining Requests from Previous Verifications	Summary of project owner response	Audit team conclusion
<p><u>Forward Action Request No.4</u></p> <p><i>Project Description</i></p> <p>A transparent project description has to be integrated in the Monitoring Report as follows: - Scope of the Project (increase of turbine capacity and turbine efficiency of four turbine units HG3, HG4, HG35 and HG7 by refurbishment works)</p> <ul style="list-style-type: none"> - The cascade system covering both PdF I and PdF II and impact on plant operation (interdependence) - Information on the implementation of refurbishment works at each turbine unit and the incommissioning dates (timeline) - Information on power generation forecast due to project implementation and the measured power of the refurbished turbine units and discussion of any deviations - Information on the impact of the operational status (turbine history: repair/maintenance etc.) of the turbines related to power generation 	<p>A project description has been integrated in the Monitoring Reports.</p> <p>The cascade system covering both PdF I and PdF II and impact on plant operation (interdependence) was included in the Monitoring Report of PdF II where this interdependence is taken into account.</p> <p>Information on the implementation of refurbishment works at each turbine unit and the commissioning dates were included in the Monitoring Reports</p> <p>Information on power generation forecast due to project implementation and the measured power of the refurbished turbine units and discussion of any deviations were included in the Monitoring Plans.</p> <p>During the monitoring period 2008 – 2011 there were no special events or malfunctions, except the normal planned outage period for maintenance works, and therefore no impact could be reported.</p>	<p>The description has been included in the last version of MR (“PdF I 2008 eng final” – for ex.) (IRL 6)</p> <p>However, see CAR #1 above.</p>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Remaining Requests from Previous Verifications	Summary of project owner response	Audit team conclusion
<p><u>Forward Action Request No.5</u></p> <p><i>Monitoring and Data management</i> The monitoring report has to refer to monthly data reading & recording and transfer procedure(s) at the external meters by OMEPA (or CEZ). Any periodic meter calibration has to be mentioned in the MR.</p> <ul style="list-style-type: none"> - Monthly data sheet containing the electricity measured at the external electricity meter and supplied to the grid signed by Hidroelectrica and the grid operator (CEZ) staff has to be provided as annex to the MR. - Monthly data sheet containing the data on supplied electricity to the grid read & recorded at the internal electricity meters covering the verification period have to be provided as annex to MR. - An Excel workbook with a cross check of data recorded at the external meter (installed at the 110 kV TM line at the TM station) and at the internal meter onsite (SCADA) covering the verification period has to be provided. 	<p>All required data and information were submitted.</p>	<p>The MR has been completed with the requested information, however See CAR #1 above</p>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

2. Data Management System

2.1. Description

Structure of raw data archiving				
Describe all the different data collection systems				
Type	Name	Responsible	Procedures	Comments
Manual	No manual data records	NA	NA	NA
<i>PLC 1</i>	Personal Computer (PC) with integrated server onsite PdF II	General Coordinator, IT manager, Calibration/Maintenance Manager	The metered raw data (generated electricity, levels) stored in a computer onsite. It is managed by a SCADA system.	<input checked="" type="checkbox"/>
<i>PLC 2</i>	PC with integrated server at Hidroelectrica headquarters in Turnu Severin	General Coordinator, IT Manager, Calibration/Maintenance Manager	The metered raw data (generated electricity, level) is simultaneously transferred to a computer system at Hidroelectrica offices in Turnu Severin. It is managed by a SCADA system.	<input checked="" type="checkbox"/>
<i>Accounting</i> N/A	<i>Invoice</i> N/A	NA	NA	NA
<i>External data</i>	The generated electricity supplied to the grid -	The regional grid operator CEZ is responsible	CEZ is the operator of the Oltenia region and work on the	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

	recorded with meters sealed and controlled by CEZ, the regional grid operator.	for calibration and maintenance of meters. Therefore the metered data is regarded as “external”.	system grids up to 110 kV	
<i>External data</i>	Grid Emission Factor - issued by the Romanian authorities and accepted during the assessment of the baseline.	Technical Coordinator, Operation manager	See the web page of the grid operator ANRE www.anre.ro	<input checked="" type="checkbox"/>
<i>External data</i>	Turbine Efficiency data vintage - report provided by the company EPFL, Switzerland.	Technical Coordinator, Operation manager	The turbine efficiency data is determined according to a mathematical simulation, which was prepared by the company EPFL, Switzerland. The model covers the efficiency of refurbished and the non-refurbished (original status) turbine units	The comprehensive EPFL model results are used for the purpose of energy increase calculations. This is done by implementing a programme (FORTRAN), which allows a numerical solution for individual operational conditions depending on actual flow rate, head and power. The reports were handed over to the audit team.
Further Remarks: The raw data is recorded and processed automatically.				

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

2.2. Raw Data Archiving and Protection measures

Name	Description of data archiving and protection measures	Risks and comments	Concl.
<i>Form a</i> No manual data records	na	na	<input checked="" type="checkbox"/>
<i>Computer a</i> Personal Computer (PC) with integrated server on-site PdF II.	<p>The metered raw data (generated electricity, levels) is stored in a computer onsite. It is part of a SCADA system used for raw data acquisition, transfer, processing and archiving.</p> <p>The data is archived in a data storage system managed by the IT department. The data is recorded in external backup CD, which are kept in an air conditioned room in the Hidroelectrica building in Turnu Severin.</p>	<p>QM procedures: PO-HE-PF-129 ed.5, rev.0 "Administration of the software licensees and the informatics system of SH Portile de Fier; PO-HE-PF-190 ed.2, rev.0 "Electronic archiving of the documents.</p> <p>The verification team randomly checked the information from the computer a with the external data (invoice data) measured at the 110 kV HV station (IRL- 13)</p>	<input checked="" type="checkbox"/>
<i>Computer b</i> Personal Computer (PC) with integrated server at Hidroelectrica headquarters in	<p>The measured raw data (generated electricity, level) is simultaneously transferred to a computer system at Hidroelectrica offices in Turnu Severin. The data is read by optical sensors and transferred by :</p> <ol style="list-style-type: none"> radio frequency transmission fibre optic cable network of Telecom Romania 	na	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

<p>Turnu Severin</p>	<p>See below:</p>		
<p>Invoice N/A</p>	<p>na</p>	<p>na</p>	<p><input checked="" type="checkbox"/></p>
<p>Form e The generated electricity supplied to the grid - recorded with meters sealed and controlled by CEZ, the regional grid oper-</p>	<p>Note : The additional energy gained by various refurbishment measures is not identified or marked separately in the invoices. Therefore the invoices cannot be used for a comprehensive cross check of this energy fraction. However the daily/monthly generated total energy (power) data can be used for the crosscheck of the daily power data used in the calculations.</p>	<p>The delivered/consumed energy is calculated with an algorithm established between the two parties at the power plant and at block level by SC Hidroelectrica SA – SH Portiile de Fier II and SC CEZ SA. The invoicing and reimbursing to the grid (on the wholesale market) is made at Hidroelectrica SA level according</p>	<p><input checked="" type="checkbox"/></p>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

ator.		to the Commercial Code provisions of the wholesale market in accordance with the commercial contracts/amendments concluded by Hidroelectrica (IRL 14).	
Grid Emission Factor issued by the Romanian authorities and accepted during the assessment of the baseline.	EF is provided by ANRE.	EF is provided by ANRE.	<input checked="" type="checkbox"/>
Turbine Efficiency data vintage - report provided by the company EPFL, Switzerland	The data is provided by EPFL report	The data is provided by EPFL report	<input checked="" type="checkbox"/>
Further Remarks: The raw data are stored in a redundant system (computer a and computer b) and is traceable also with the invoices between Hidroelectrica and CEZ. <i>The risks of losing the archived data are insignificant.</i>			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

2.3 Data transfer

Description of data transfer from raw data archiving to calculation tool			
Name	Description and responsibilities	Risks and comments	Concl.
<i>Form a</i> No manual data records	na	na	<input checked="" type="checkbox"/>
<i>Computer a</i> Personal Computer (PC) with integrated server onsite PdF II	See remarks in 2.1 and 2.2	See remarks in 2.1 and 2.2	<input checked="" type="checkbox"/>
<i>Computer b</i> Personal Computer (PC) with integrated server at Hidroelectrica headquarters in Turnu Severin	See remarks in 2.1 and 2.2	See remarks in 2.1 and 2.2	<input checked="" type="checkbox"/>
<i>Invoice</i> N/A	See remarks in 2.1 and 2.2	See remarks in 2.1 and 2.2	<input checked="" type="checkbox"/>
<i>Form e</i> The generated electricity supplied to the grid - recorded with meters sealed	See remarks in 2.1 and 2.2	See remarks in 2.1 and 2.2	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

and controlled by Transelectrica, the grid operator.			
Grid Emission Factor issued by the Romanian authorities and accepted during the assessment of the baseline.	See remarks in 2.1 and 2.2	See remarks in 2.1 and 2.2	<input checked="" type="checkbox"/>
Turbine Efficiency data vintage - report provided by the company EPFL, Switzerland.	See remarks in 2.1 and 2.2	See remarks in 2.1 and 2.2	<input checked="" type="checkbox"/>
Further Remarks: Data transfer is performed automatically			<input checked="" type="checkbox"/>

2.4 Data Processing

Description of data processing from transferred data to final results in the calculation tool			
Step	Description	Risks and comments	Concl.
Consistency	The methodology is based on the calculation of various metered	na	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

	data and test model data.		
Calculation Tool description	The calculation procedure has been described in the Monitoring Plan and corresponding annexes. As mentioned before, a huge data vintage with many recorded parameter data has been used for the calculation of additional energy, i.e. hourly and daily values were determined by using a numeric program (FORTRAN) implemented and demonstrated by the Operation Manager, Mr. Cristian Bocse. Details on the calculation procedures (some assumptions / simplifications) have been described by Mr. Cristian Bocse.	The raw data used for calculations are transferred automatically into the calculation computer. The risk is only if the computer program (FORTRAN) is not working properly. Spot check calculations were done by the audit team as a cross check using the excel tables with parameters for energy calculation. No discrepancies were found.	<input checked="" type="checkbox"/>
Transformation from transferred data to useable data	The raw data sources used for energy calculations have been presented to the audit team for a spot check. The data submitted in a CD makes it partly possible to recalculate and check the results. Not all raw data was handed over to the audit team (see CR#8, CR#9 in 2.1).	No data can be missed. If data is missing, the registers are available and the data is collected again from these registers. Data are compared with previous data and any discrepancy can be either remarked from data collection or from data computation	<input checked="" type="checkbox"/>
Elimination of not plausible data	The issue of not plausible data has not been mentioned.	The risk of not plausible data is much reduced because the information is recorded automatically and checked twice on both computers (PdF and Headquarter in Turnu Severin)	<input checked="" type="checkbox"/>
Transformation from useable data to input data for further calculation	Data for η (efficiencies) are taken from tables provided by EPFL.	Control steps for the handling of usable data have been described in plausible way.	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Ex-ante data	na		<input checked="" type="checkbox"/>
Default parameter	The EF for the grid were taken ex-ante and accepted during the initial determination of the project	N/A	<input checked="" type="checkbox"/>
Formulae check	$\Delta E = E_A + E_B \quad [\text{Mwh}]$ <p>where:</p> <ol style="list-style-type: none"> E_A – Additional electric energy generated due to the increase of the installed capacity and efficiency <p>The calculation for the entire additional electric energy generated is done with the formula:</p> $E_A = E_a + E_b = \sum_1^{8760} ((P - P_{27}) + \Delta\eta * P) \quad [\text{Mwh}]$ <p>where:</p> <p>P = hourly measured energy by the counters (hourly medium power) [Mw]</p> <p>P_{27} = maximum power (depending on the head) of old hydrounits [Mw], where</p> <p>head = difference between the upstream and downstream levels measured [m]</p> <p>$\Delta\eta$ = increased efficiency represented by the difference between the efficiency of the refurbished hydrounits and the efficiency of the old hydrounits</p> <p>E_B - Additional electric energy for the entire Portile de Fier hydro-</p>	They were checked at the time of PDD development and during the project Determination. There are no changes of these formulae in the mean time	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

	<p>electric system</p> $E_B = (dE2+dE1)/2 \text{ (dE1 has a negative value)}$ <p>Due to the fact that only for 4 units are within the project boundary only half of the additional electric energy for the entire Portile de Fier hydroelectric system of the Romanian side is considered.</p> <p>The initial electric energy generation (if the heads h_2 and h_G would not be increased) for Portile de Fier II (respectively Gogosu) are daily calculated</p> $E_{2(h_2-df_2)} = \eta_{(h_2-dh_2)} \times (h_2-dh_2) \times Q_{(h_2-dh_2)} \text{ respectively}$ $E_{G(h_G-df_G)} = \eta_{(h_G-dh_G)} \times (h_G-dh_G) \times Q_{(h_G-dh_G)}$ <p>The gain from Portile de Fier II is: $dE2 = E2+EG-E_{2(h-dh_2)}-E_{G(h-dh_2)}$ where $E2$ and EG represent the daily electric energy generation.</p> <p>The calculation for the initial electric energy generation (if h_1 would not be decreased) is done in a similar way for Portile de Fier I</p> $E_{1(h_1-df_1)} = \eta_{(h_1-dh_1)} \times (h_1-dh_1) \times Q_{(h_1-dh_1)}$ <p>The loss for Portile de Fier I is as follows: $dE1 = E1-E_{1(h_1+dh_1)}$ where: $E1$ represents the daily generation.</p>		
--	---	--	--

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Rounding functions	The results with digits are rounded as a mean of conservative approach.	The rounding used in the initial PDD was accepted at that time.	<input checked="" type="checkbox"/>
Calculation tool changes and protection measures	The workbook could be filled only by the person responsible for workbook filling and in this regard no unauthorized changes could occur.	Mr. Constantin Guran (Romanian – Serbian operation coordinator) is the person dedicated to assure the control barriers into the calculation tool as to assure the use of original data from the measuring period. All data for a specific period are confirmed and included in the Annex 1 of the bi-annual Report (this Annex 1 is signed by Mr. Guran.	<input checked="" type="checkbox"/>
Further Remarks: Faulty similar calculations by both parties may result from calculation or faulty monthly readings. Faulty monthly readings are automatically corrected either by data interpretation or by subsequent data readings.			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



3. Monitoring Plan Implementation

3.1. List of Parameter to be monitored

ID-PDD	ID-Meth.	ID-Internal	Description	Conclusion
Instrumentation				
P	-	-	Electricity meters	<input checked="" type="checkbox"/>
Upstream level	-	-	Level meter Used for calculation of η refurbished.	<input checked="" type="checkbox"/>
Down-stream level	-	-	Level meter Used for calculation of η refurbished.	<input checked="" type="checkbox"/>
External Data				
P_r	-	-	The hourly electricity is read by electricity meters at 110 kV HV line and is recorded at the SCADA data base	<input checked="" type="checkbox"/>
P_{27}	-	-	From baseline data base.	<input checked="" type="checkbox"/>
η	-	-	The turbine efficiency of the refurbished and old units are read from the head-power chart using the EPFL model data base.	<input checked="" type="checkbox"/>
EF_{grid}	-	-	The EF are gathered from ANRE reports, they are indicated in the determination report as well.	<input checked="" type="checkbox"/>
Head	Head	Head	The net head is calculated as the difference between the water level upstream and water level downstream.	<input checked="" type="checkbox"/>
Others				
<i>Not appli-</i>				<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

ID-PDD	ID-Meth.	ID-Internal	Description	Conclusion
<i>cable</i>				

3.2. Monitoring Instrumentation

3.2.1. Instrument (QWG002685387 ELSTER)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	Main meter at the turbine HG4	<input checked="" type="checkbox"/>
ID-Internal:	Electricity at the medium voltage (6.3 kV) substation before transformation station (to 110 kV)	<input checked="" type="checkbox"/>
Data to be Measured:	Total Electricity at the turbine HG4	<input checked="" type="checkbox"/>
Data Logging:	Online monitoring, hourly reading, monthly recording	<input checked="" type="checkbox"/>
Archiving of Raw Data:	Connected via modem to the server onsite and further transferred to HQ Hidroelectrica	<input checked="" type="checkbox"/>
Measurement Principle:	3 phase quadrant, pulse measurement	<input checked="" type="checkbox"/>
Period of Operating Time:	from 28.09.2010 onwards in operation	<input checked="" type="checkbox"/>
Instrument Type:	Not specified	<input checked="" type="checkbox"/>
Serial Number:	QWG 002 685 387	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	ELSTER	<input checked="" type="checkbox"/>
Specific Location:	The meter is located at the turbine G4 6.3 kV line	<input checked="" type="checkbox"/>
Measurement Range:	Voltage : (L) 57/100 V ac (M) 63.5/110 V ac	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

	Current : I n 5 A 1 A I max 10 A 2 A	
Measurement Unit:	MWh	<input checked="" type="checkbox"/>
Calibration:	10.09.2010 (IRL 16)	<input checked="" type="checkbox"/>
Required Calibration Frequency:	8 years	<input checked="" type="checkbox"/>
Uncertainty Level:	0.2 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	hourly	<input checked="" type="checkbox"/>
Recording Frequency:	monthly	<input checked="" type="checkbox"/>
Trouble Shooting:	n/a	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

Inspection Results During Verification			
Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	3 phase quadrant digital meter, puls	The installed electricity meter operates as 3 phase, quadrant digital meter.	<input checked="" type="checkbox"/>
Installation:	Installed by the supplier ELSTER	3 phase, quadrant digital meter was installed onsite.	<input checked="" type="checkbox"/>
Functionality:	The installed electricity meter operates as 3 phase, quadrant digital meter.	The meter is installed at the turbine unit at 6.3 kV medium high voltage line and was operational.	<input checked="" type="checkbox"/>
Quality assurance:	3 phase, quadrant digital meter was installed onsite.	The calibration certificates have been provided (IRL 16).	<input checked="" type="checkbox"/>
Maintenance:	The meter is installed at the turbine unit at 15.6 kV medium high voltage line and was operational.	No maintenance records were presented so far.	<input checked="" type="checkbox"/>
Further Remarks: The meter replaced the old one, QYG002688032, presented below			<input checked="" type="checkbox"/>

3.2.2. Instrument (QYG002688032 ELSTER)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	Main meter at the turbine HG4	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

ID-Internal:	Electricity at the medium voltage (6.3 kV) substation before transformation station (to 110 kV)	<input checked="" type="checkbox"/>
Data to be Measured:	Total Electricity at the turbine HG4	<input checked="" type="checkbox"/>
Data Logging:	Online monitoring, hourly reading, monthly recording	<input checked="" type="checkbox"/>
Archiving of Raw Data:	Connected via modem to the server onsite and further transferred to HQ Hidroelectrica	<input checked="" type="checkbox"/>
Measurement Principle:	3 phase quadrant, pulse measurement	<input checked="" type="checkbox"/>
Period of Operating Time:	from 08.11.2005 until 10.09.2010 when has been replaced with QWG002685387	<input checked="" type="checkbox"/>
Instrument Type:	Not specified	<input checked="" type="checkbox"/>
Serial Number:	QYG 002 688 032	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	ELSTER	<input checked="" type="checkbox"/>
Specific Location:	The meter is located at the turbine G4 6.3 kV line	<input checked="" type="checkbox"/>
Measurement Range:	Voltage : (L) 57/100 V ac (M) 63.5/110 V ac Current : I n 5 A 1 A I max 10 A 2 A	<input checked="" type="checkbox"/>
Measurement Unit:	MWh	<input checked="" type="checkbox"/>
Calibration:	08.11.2005 (IRL 16)	<input checked="" type="checkbox"/>
Required Calibration Frequency:	5 years	<input checked="" type="checkbox"/>
Uncertainty Level:	0.2 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	hourly	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Recording Frequency:	monthly	<input checked="" type="checkbox"/>
Trouble Shooting:	n/a	<input checked="" type="checkbox"/>

Inspection Results During Verification			
Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	3 phase quadrant digital meter, puls	The installed electricity meter operated as 3 phase, quadrant digital meter.	<input checked="" type="checkbox"/>
Installation:	Installed by the supplier ELSTER	3 phase, quadrant digital meter was installed onsite.	<input checked="" type="checkbox"/>
Functionality:	The installed electricity meter operates as 3 phase, quadrant digital meter.	The meter was installed at the turbine unit HG4 at 6.3 kV medium high voltage line and was operational.	<input checked="" type="checkbox"/>
Quality assurance:	3 phase, quadrant digital meter was installed onsite.	The calibration certificates have been provided (IRL 16).	<input checked="" type="checkbox"/>
Maintenance:	The meter is installed at the turbine unit at 15.6 kV medium high voltage line and was operational.	N/A	<input checked="" type="checkbox"/>
Further Remarks: N/A			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

3.2.3. Instrument (QYG002 698 070, ELSTER)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	Main meter at the turbine HG3	<input checked="" type="checkbox"/>
ID-Internal:	Electricity at the medium voltage (6.3 kV) substation before transformation station (to 110 kV)	<input checked="" type="checkbox"/>
Data to be Measured:	Total Electricity at the turbine HG3	<input checked="" type="checkbox"/>
Data Logging:	Online monitoring, hourly reading, monthly recording	<input checked="" type="checkbox"/>
Archiving of Raw Data:	Connected via modem to the server onsite and further transferred to HQ Hidroelectrica	<input checked="" type="checkbox"/>
Measurement Principle:	3 phase quadrant, pulse measurement	<input checked="" type="checkbox"/>
Period of Operating Time:	From 19.12.2006 onwards in operation	<input checked="" type="checkbox"/>
Instrument Type:	ELSTER	<input checked="" type="checkbox"/>
Serial Number:	QYG 002 698 070	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	ELSTER	<input checked="" type="checkbox"/>
Specific Location:	The meter is located at the turbine HG3 6.3 kV line	<input checked="" type="checkbox"/>
Measurement Range:	Voltage : (L) 57/100 V ac (M) 63.5/110 V ac Current : I n 5 A 1 A I max 10 A 2 A	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Measurement Unit:	MWh	<input checked="" type="checkbox"/>
Calibration:	23.11.2006	<input checked="" type="checkbox"/>
Required Calibration Frequency:	8 years	<input checked="" type="checkbox"/>
Uncertainty Level:	0.2 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	Online	<input checked="" type="checkbox"/>
Recording Frequency:	Hourly	<input checked="" type="checkbox"/>
Trouble Shooting:	n/a	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Inspection Results During Verification			
Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	3 phase quadrant digital meter, puls	The installed electricity meter operates as 3 phase, quadrant digital meter.	<input checked="" type="checkbox"/>
Installation: Manner of execution	Installed by the supplier ELSTER	3 phase, quadrant digital meter was installed onsite.	<input checked="" type="checkbox"/>
Functionality:	It is referred to the specifications of the supplier.	The meter is installed at the turbine unit at 6.3 kV medium high voltage line.	<input checked="" type="checkbox"/>
Quality assurance:	It is referred to the specifications of the supplier.	The calibration certificates were provided (IRL 16).	<input checked="" type="checkbox"/>
Maintenance:	It is referred to the specifications of the supplier and the requirements of the grid operator.	N/A	<input checked="" type="checkbox"/>
Further Remarks: N/A			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

3.2.4. Instrument (QWG002 709 048, ABB)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	Main meter at the turbine HG 5	<input checked="" type="checkbox"/>
ID-Internal:	Electricity at the medium voltage (6.3 kV) substation before the 110 kV high-voltage TM station	<input checked="" type="checkbox"/>
Data to be Measured:	Total electricity generation at turbine HG5	<input checked="" type="checkbox"/>
Data Logging:	Online monitoring, hourly reading, monthly recording	<input checked="" type="checkbox"/>
Archiving of Raw Data:	Connected via modem to the server onsite and further transferred to HQ Hidroelectrica	<input checked="" type="checkbox"/>
Measurement Principle:	3 phase quadrant, pulse measurement	<input checked="" type="checkbox"/>
Period of Operating Time:	From 10.01.2008 onwards in operation (the unit HG 5 operated since 24.01.2008)	<input checked="" type="checkbox"/>
Instrument Type:	ELSTER	<input checked="" type="checkbox"/>
Serial Number:	QWG 002 709 048	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	ELSTER	<input checked="" type="checkbox"/>
Specific Location:	The meter is located at the turbine HG5 6.3 kV line	<input checked="" type="checkbox"/>
Measurement Range:	Voltage : (L) 57/100 V ac (M) 63.5/110 V ac Current : I n 5 A 1 A I max 10 A 2 A	<input checked="" type="checkbox"/>
Measurement Unit:	MWh	<input checked="" type="checkbox"/>
Calibration:	26.09.2007	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Required Calibration Frequency:	8 years	<input checked="" type="checkbox"/>
Uncertainty Level:	0.2 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	hourly	<input checked="" type="checkbox"/>
Recording Frequency:	monthly	<input checked="" type="checkbox"/>
Trouble Shooting:	n/a	<input checked="" type="checkbox"/>

Inspection Results During Verification			
Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	3 phase quadrant digital meter, puls	The installed electricity meter operates as 3 phase, quadrant digital meter.	<input checked="" type="checkbox"/>
Installation:	Installed by the supplier ELSTER	3 phase, quadrant digital meter was installed onsite.	<input checked="" type="checkbox"/>
Functionality:	It is referred to the specifications of the supplier.	The meter is installed at the turbine unit at 6.3 kV medium high voltage line.	<input checked="" type="checkbox"/>
Quality assurance:	It is referred to the specifications of the supplier.	The calibration certificates were provided (IRL 16)	<input checked="" type="checkbox"/>
Maintenance:	It is referred to the specifications of the supplier and the requirements of the grid operator.	N/A	<input checked="" type="checkbox"/>
Further Remarks: N/A			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

3.2.5. Instrument (QWG002 720 905, ABB)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	Main meter at the turbine HG 7	<input checked="" type="checkbox"/>
ID-Internal:	Electricity at the medium voltage (6.3 kV) substation before the 110 kV high-voltage TM station	<input checked="" type="checkbox"/>
Data to be Measured:	Total electricity generation at turbine HG 7	<input checked="" type="checkbox"/>
Data Logging:	Online monitoring, hourly reading, monthly recording	<input checked="" type="checkbox"/>
Archiving of Raw Data:	Connected via modem to the server onsite and further transferred to HQ Hidroelectrica	<input checked="" type="checkbox"/>
Measurement Principle:	3 phase quadrant, pulse measurement	<input checked="" type="checkbox"/>
Period of Operating Time:	From 20.01.2009 onwards in operation (the unit HG 7 started to operate on 06.03.2009)	<input checked="" type="checkbox"/>
Instrument Type:	ELSTER	<input checked="" type="checkbox"/>
Serial Number:	QWG 002 720 905	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	ELSTER	<input checked="" type="checkbox"/>
Specific Location:	The meter is located at the turbine HG7 6.3 kV line	<input checked="" type="checkbox"/>
Measurement Range:	Voltage : (L) 57/100 V ac (M) 63.5/110 V ac Current : I n 5 A 1 A I max 10 A 2 A	<input checked="" type="checkbox"/>
Measurement Unit:	MWh	<input checked="" type="checkbox"/>
Calibration:	15.01.2009	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Required Calibration Frequency:	8 years	<input checked="" type="checkbox"/>
Uncertainty Level:	0.2 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	hourly	<input checked="" type="checkbox"/>
Recording Frequency:	monthly	<input checked="" type="checkbox"/>
Trouble Shooting:	n/a	<input checked="" type="checkbox"/>

Inspection Results During Verification			
Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	3 phase quadrant digital meter, puls	The installed electricity meter operates as 3 phase, quadrant digital meter.	<input checked="" type="checkbox"/>
Installation:	Installed by the supplier ELSTER	3 phase, quadrant digital meter was installed onsite.	<input checked="" type="checkbox"/>
Functionality:	It is referred to the specifications of the supplier.	The meter is installed at the turbine unit at 6.3 kV medium high voltage line.	<input checked="" type="checkbox"/>
Quality assurance:	It is referred to the specifications of the supplier.	The calibration certificates were provided (IRL 16)	<input checked="" type="checkbox"/>
Maintenance:	It is referred to the specifications of the supplier and the requirements of the grid operator.	N/A	<input checked="" type="checkbox"/>
Further Remarks: N/A			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

3.2.6. Instrument (QYG 5019956, ABB)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	Main meter at the turbine HG 6 (not part of the Project, but used as back-up for HG 5 together with the meter of TB III)	<input checked="" type="checkbox"/>
ID-Internal:	Electricity at the medium voltage (6.3 kV) substation before the 110 kV high-voltage TM station	<input checked="" type="checkbox"/>
Data to be Measured:	Total electricity generation at turbine HG 6	<input checked="" type="checkbox"/>
Data Logging:	Online monitoring, hourly reading, monthly recording	<input checked="" type="checkbox"/>
Archiving of Raw Data:	Connected via modem to the server onsite and further transferred to HQ Hidroelectrica	<input checked="" type="checkbox"/>
Measurement Principle:	3 phase quadrant, pulse measurement	<input checked="" type="checkbox"/>
Period of Operating Time:	From 29.09.2007 – 22.06.2011	<input checked="" type="checkbox"/>
Instrument Type:	ELSTER	<input checked="" type="checkbox"/>
Serial Number:	QYG 5019956	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	ELSTER	<input checked="" type="checkbox"/>
Specific Location:	The meter is located at the turbine HG6 6.3 kV line	<input checked="" type="checkbox"/>
Measurement Range:	Voltage : (L) 57/100 V ac (M) 63.5/110 V ac Current : I n 5 A 1 A I max 10 A 2 A	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Measurement Unit:	MWh	<input checked="" type="checkbox"/>
Calibration:	23.08.2005	<input checked="" type="checkbox"/>
Required Calibration Frequency:	<p>5 years</p> <p>Starting with 23.08.2010, the meter has been used without calibration. Taking into account that the back-up procedure for HG 5 has never been used during this monitoring period 2008 – 2011 (see IRL 16, 17), it is considered that the use of this not calibrated meter had no impact on the JI Project.</p> <p>However,</p> <p><u>Clarification Request No.1</u></p> <p>According to the document “evidenta contori PFI si PFII.docx” (IRL 16), on 22.06.2011, the meter QYG5019956 has been replaced, but there is no information regarding the new meter installed.</p> <p>Evidence regarding the new meter installed at HG 6 on 22.06.2011 shall be provided to the TUV SUD verification team.</p>	CL 1
Uncertainty Level:	0.2 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	hourly	<input checked="" type="checkbox"/>
Recording Frequency:	monthly	<input checked="" type="checkbox"/>
Trouble Shooting:	n/a	<input checked="" type="checkbox"/>

Inspection Results During Verification

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	3 phase quadrant digital meter, puls	The installed electricity meter operates as 3 phase, quadrant digital meter.	<input checked="" type="checkbox"/>
Installation:	Installed by the supplier ELSTER	3 phase, quadrant digital meter was installed onsite.	<input checked="" type="checkbox"/>
Functionality:	It is referred to the specifications of the supplier.	The meter is installed at the turbine unit at 6.3 kV medium high voltage line.	<input checked="" type="checkbox"/>
Quality assurance:	It is referred to the specifications of the supplier.	The calibration certificates were provided (IRL 21)	<input checked="" type="checkbox"/>
Maintenance:	It is referred to the specifications of the supplier and the requirements of the grid operator.	N/A	<input checked="" type="checkbox"/>
Further Remarks: The meter is used as back-up for HG 5 (together with the meter from TB III). See also CL #1			CL 1

3.2.7. Instrument (QWG002698069, ABB)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	Main meter at the turbine HG 8 (not part of the Project, but used as back-up for HG 7 together with the meter of TB IV)	<input checked="" type="checkbox"/>
ID-Internal:	Electricity at the medium voltage (6.3 kV) substation before the 110 kV high-voltage TM station	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Data to be Measured:	Total electricity generation at turbine HG 7	<input checked="" type="checkbox"/>
Data Logging:	Online monitoring, hourly reading, monthly recording	<input checked="" type="checkbox"/>
Archiving of Raw Data:	Connected via modem to the server onsite and further transferred to HQ Hidroelectrica	<input checked="" type="checkbox"/>
Measurement Principle:	3 phase quadrant, pulse measurement	<input checked="" type="checkbox"/>
Period of Operating Time:	From 16.04.2010 onwards in operation <u>Note:</u> Up to the date of 16.04.2010, at HG 8 has been used the meter QYG005019949 , calibrated on 18.09.03 with a validity of 10 years for the calibration (IRL 16). The meter QYG005019949 has the same technical parameters as QWG002698069 and hasn't been presented in a separate table.	<input checked="" type="checkbox"/>
Instrument Type:	ELSTER	<input checked="" type="checkbox"/>
Serial Number:	QWG002698069	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	ELSTER	<input checked="" type="checkbox"/>
Specific Location:	The meter is located at the turbine HG8 6.3 kV line	<input checked="" type="checkbox"/>
Measurement Range:	Voltage : (L) 57/100 V ac (M) 63.5/110 V ac Current : I n 5 A 1 A I max 10 A 2 A	<input checked="" type="checkbox"/>
Measurement Unit:	MWh	<input checked="" type="checkbox"/>
Calibration:	23.11.2006	<input checked="" type="checkbox"/>
Required Calibration Frequency:	8 years	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Uncertainty Level:	0.2 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	hourly	<input checked="" type="checkbox"/>
Recording Frequency:	monthly	<input checked="" type="checkbox"/>
Trouble Shooting:	n/a	<input checked="" type="checkbox"/>

Inspection Results During Verification			
Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	3 phase quadrant digital meter, puls	The installed electricity meter operates as 3 phase, quadrant digital meter.	<input checked="" type="checkbox"/>
Installation:	Installed by the supplier ELSTER	3 phase, quadrant digital meter was installed onsite.	<input checked="" type="checkbox"/>
Functionality:	It is referred to the specifications of the supplier.	The meter is installed at the turbine unit at 6.3 kV medium high voltage line.	<input checked="" type="checkbox"/>
Quality assurance:	It is referred to the specifications of the supplier.	The calibration certificates were provided (IRL 16)	<input checked="" type="checkbox"/>
Maintenance:	It is referred to the specifications of the supplier and the requirements of the grid operator.	N/A	<input checked="" type="checkbox"/>
Further Remarks: N/A			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

3.2.8. Instrument (YWG 005 013 693, ABB)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	Main meter at CEZ substation (110 kV) for G4 + G3 (TB II)	<input checked="" type="checkbox"/>
ID-Internal:	Total electricity at the HV TM station (to 110 kV) for turbines HG 3 and HG 4 (sum)	<input checked="" type="checkbox"/>
Data to be Measured:	Total electricity at the turbines HG 3 and HG 4 (sum)	<input checked="" type="checkbox"/>
Data Logging:	Online monitoring, hourly reading, monthly recording	<input checked="" type="checkbox"/>
Archiving of Raw Data:	Connected via modem to the server onsite and further transferred to HQ Hidroelectrica	<input checked="" type="checkbox"/>
Measurement Principle:	3 phase quadrant, pulse measurement	<input checked="" type="checkbox"/>
Period of Operating Time:	From 13.11.2002 onwards in operation	<input checked="" type="checkbox"/>
Instrument Type:	ABB	<input checked="" type="checkbox"/>
Serial Number:	YWG 005 013 693	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	ABB	<input checked="" type="checkbox"/>
Specific Location:	The meter is located at the neighbouring CEZ high-voltage TM station station in a housing.	<input checked="" type="checkbox"/>
Measurement Range:	Voltage : (L) 57/200 V ac (M) 63.5/110 V ac	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

	Current : I n 5 A 1 A I max 10 A 2 A	
Measurement Unit:	MWh	<input checked="" type="checkbox"/>
Calibration:	07.11.2002	<input checked="" type="checkbox"/>
Required Calibration Frequency:	10 years	<input checked="" type="checkbox"/>
Uncertainty Level:	0.2 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	hourly	<input checked="" type="checkbox"/>
Recording Frequency:	monthly	<input checked="" type="checkbox"/>
Trouble Shooting:	n/a	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Inspection Results During Verification			
Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	3 phase quadrant digital meter, puls	The installed electricity meter operates as 3 phase, quadrant digital meter.	<input checked="" type="checkbox"/>
Installation:	Installed by the supplier ABB	3 phase, quadrant digital meter was installed onsite.	<input checked="" type="checkbox"/>
Functionality:	It is referred to the specifications of the supplier.	The meter is installed in the substation at 110 kV high voltage line.	<input checked="" type="checkbox"/>
Quality assurance:	It is referred to the specifications of the supplier.	The calibration certificates were provided (IRL 21).	<input checked="" type="checkbox"/>
Maintenance:	It is referred to the specifications of the supplier and the requirements of the grid operator.	No maintenance records were presented so far.	<input checked="" type="checkbox"/>
Further Remarks: N/A			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

3.2.9. Instrument (YWG005 013 695, ABB)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	Main meter at CEZ HV TM station (110 kV) for G5 + G6 (TB III)	
ID-Internal:	Total electricity at the HV TM station (to 110 kV) for turbines HG 5 and HG 6 (sum)	☑
Data to be Measured:	Total electricity at the turbines HG 5 and HG 6 (sum)	☑
Data Logging:	Online monitoring, hourly reading, monthly recording	☑
Archiving of Raw Data:	Connected via modem to the server onsite and further transferred to HQ Hidroelectrica	☑
Measurement Principle:	3 phase quadrant, pulse measurement	☑
Period of Operating Time:	07.03.2003 up to the present	☑
Instrument Type:	ABB, not specified	☑
Serial Number:	YWG 005 013 695	☑
Manufacturer Model Nr.:	ABB	☑
Specific Location:	The meter is located at the neighbouring 110 kV CEZ TM station in a housing	☑
Measurement Range:	Voltage : (L) 57/200 V ac (M) 63.5/110 V ac Current : I n 5 A 1 A	☑

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

	I max 10 A 2 A	
Measurement Unit:	MWh	<input checked="" type="checkbox"/>
Calibration:	14.02.2003	<input checked="" type="checkbox"/>
Required Calibration Frequency:	10 years	<input checked="" type="checkbox"/>
Uncertainty Level:	0.2 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	Online	<input checked="" type="checkbox"/>
Recording Frequency:	Hourly	<input checked="" type="checkbox"/>
Trouble Shooting:	n/a	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Inspection Results During Verification			
Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	3 phase quadrant digital meter, puls	The installed electricity meter operates as 3 phase, quadrant digital meter.	<input checked="" type="checkbox"/>
Installation:	Installed by the supplier ABB	3 phase, quadrant digital meter was installed onsite.	<input checked="" type="checkbox"/>
Functionality:	It is referred to the specifications of the supplier.	The meter is installed in the substation at 110 kV high voltage line.	<input checked="" type="checkbox"/>
Quality assurance:	It is referred to the specifications of the supplier.	The calibration certificates were provided (IRL 16).	<input checked="" type="checkbox"/>
Maintenance:	It is referred to the specifications of the supplier and the requirements of the grid operator.	No maintenance records were reported so far.	<input checked="" type="checkbox"/>
Further Remarks: N/A			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

3.2.10. Instrument (YWG005013692, ELSTER)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	Main meter at CEZ HV TM station (110 kV) for G7 + G8 (TB IV)	<input checked="" type="checkbox"/>
ID-Internal:	Total electricity at the HV TM station (to 110 kV) for turbines HG 7 and HG 8 (sum)	<input checked="" type="checkbox"/>
Data to be Measured:	Total electricity at the turbines HG 7 and HG 8 (sum)	<input checked="" type="checkbox"/>
Data Logging:	Online monitoring, hourly reading, monthly recording	<input checked="" type="checkbox"/>
Archiving of Raw Data:	Connected via modem to the server onsite and further transferred to HQ Hidroelectrica	<input checked="" type="checkbox"/>
Measurement Principle:	3 phase quadrant, pulse measurement	<input checked="" type="checkbox"/>
Period of Operating Time:	From 10.04.2009 up to the present <u>Note:</u> At this station from, from 2004 up to 10.04.2009, has been used the meter YWG005013694 , calibrated on 31.04.2004 (IRL 16) and with the validity for calibration of 5 years. The previous meter, YWG005013694 , has identical technical specifications as the current installed meter YWG005013692 , and was not presented in a separate table.	<input checked="" type="checkbox"/>
Instrument Type:	ELSTER, not specified	<input checked="" type="checkbox"/>
Serial Number:	YWG005013692	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	ELSTER	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Specific Location:	Description The meter is located at the turbines HG7 and HG8, 400V line	<input checked="" type="checkbox"/>
Measurement Range:	Voltage : (L) 57/100 V ac (M) 63.5/110 V ac Current : I n 5 A 1 A I max 10 A 2 A	<input checked="" type="checkbox"/>
Measurement Unit:	MWh	<input checked="" type="checkbox"/>
Calibration:	23.11.2006	<input checked="" type="checkbox"/>
Required Calibration Frequency:	10 years	<input checked="" type="checkbox"/>
Uncertainty Level:	0.2 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	hourly	<input checked="" type="checkbox"/>
Recording Frequency:	monthly	<input checked="" type="checkbox"/>
Trouble Shooting:	n/a	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Inspection Results During Verification			
Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	3 phase quadrant digital meter, puls	The installed electricity meter operates as 3 phase, quadrant digital meter.	<input checked="" type="checkbox"/>
Installation:	Installed by the supplier ELSTER	3 phase, quadrant digital meter was installed onsite.	<input checked="" type="checkbox"/>
Functionality:	It is referred to the specifications of the supplier.	The meter is installed at the turbine unit at 0.4 kV low-voltage line.	<input checked="" type="checkbox"/>
Quality assurance:	It is referred to the specifications of the supplier.	The calibration certificates were provided (IRL 16).	<input checked="" type="checkbox"/>
Maintenance:	It is referred to the specifications of the supplier and the requirements of the grid operator.	No maintenance records were presented so far.	<input checked="" type="checkbox"/>
Further Remarks: N/A			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

3.2.11 Instrument (Level meters, TLN)

PDD	Verified Situation	Conclusion
Instrumentation Information		
ID-PDD:	TLN	<input checked="" type="checkbox"/>
ID-Internal:	Not specified	<input checked="" type="checkbox"/>
Data to be Measured:	Level of the river Danube, upstream and downstream the turbines	<input checked="" type="checkbox"/>
Data Logging:	Continuously	<input checked="" type="checkbox"/>
Archiving of Raw Data:	Transfer via modem to the server at the plant and at Hidroelectrica HQ Turnu Severin	<input checked="" type="checkbox"/>
Measurement Principle:	Floating device	<input checked="" type="checkbox"/>
Period of Operating Time:	From 2003 onwards in operation	<input checked="" type="checkbox"/>
Instrument Type:	Teleimnimeter	<input checked="" type="checkbox"/>
Serial Number:	N/A	<input checked="" type="checkbox"/>
Manufacturer Model Nr.:	Not specified	<input checked="" type="checkbox"/>
Specific Location:	Upstream and downstream of the dam	<input checked="" type="checkbox"/>
Measurement Range:	N/A	<input checked="" type="checkbox"/>
Measurement Unit:	m	<input checked="" type="checkbox"/>
Calibration:	The reliability of the level meters is checked every 6 month by the common Serbian Romanian technical committee and the results are included in to the bi-annual commis-	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

	sion report (IRL 18).	
Required Calibration Frequency:	Every 6 month	<input checked="" type="checkbox"/>
Uncertainty Level:	0.15 %	<input checked="" type="checkbox"/>
Monitoring & Calculation		
Reading Frequency:	hourly	<input checked="" type="checkbox"/>
Recording Frequency:	hourly	<input checked="" type="checkbox"/>
Trouble Shooting:	not reported for this monitoring period.	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Inspection Results During Verification			
Operation of Instrumentation	Method of Verification	Verification Results	Conclusion
Measuring Principle:	In compliance with meth./PDD	See	<input checked="" type="checkbox"/>
Installation:	Not specified		<input checked="" type="checkbox"/>
Functionality:	It is referred to the bi-annual reports and annual check of the devices.	The position could be verified onsite	<input checked="" type="checkbox"/>
Quality assurance:	It is referred to the bi-annual reports and annual check of the devices.	The functionality could be verified onsite	<input checked="" type="checkbox"/>
Maintenance:	It is referred to the bi-annual reports and annual check of the devices.		<input checked="" type="checkbox"/>
Further Remarks: N/A			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

3.3. Sampling Information (not relevant)

3.4. Accounting information (not applicable)

PDD	Verified Situation	Conclusion
Accounting Information		
ID-PDD:	na	<input checked="" type="checkbox"/>
ID-Internal:	na	<input checked="" type="checkbox"/>
Description of Accounted Component:	na	<input checked="" type="checkbox"/>
Accounting Unit:	na	<input checked="" type="checkbox"/>
Quality Assurance Measures / System:	na	<input checked="" type="checkbox"/>
Account Archived:	na	<input checked="" type="checkbox"/>
Account Credible / in Line with PDD:	na	<input checked="" type="checkbox"/>
Further Remarks: N/A		<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

3.5. External Data

PDD	Verified Situation	Conclusion
External Data		
ID-PDD:	Level, head	<input checked="" type="checkbox"/>
ID-Internal:		<input checked="" type="checkbox"/>
Description of Data / Data Refers to:	The upstream and downstream levels of the Danube river at the PdF II are measured for the calculation of net head.	<input checked="" type="checkbox"/>
Unit of Data (if appropriate):	m	<input checked="" type="checkbox"/>
Date of Data Income:	continuous	<input checked="" type="checkbox"/>
Source of Data:	TLN measurements	<input checked="" type="checkbox"/>
Reliability of Data Source:	Calibration (IRL 18)	<input checked="" type="checkbox"/>
Is the Data up-to-date?	Yes	<input checked="" type="checkbox"/>
Uncertainty Level:	0.15 %	<input checked="" type="checkbox"/>
Further Remarks: N/A		<input checked="" type="checkbox"/>

PDD	Verified Situation	Conclusion
External Data		
ID-PDD:	η Turbine efficiency factor	<input checked="" type="checkbox"/>
ID-Internal:	Turbine efficiency	<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Description of Data / Data Refers to:		<input checked="" type="checkbox"/>
Unit of Data (if appropriate):	%	<input checked="" type="checkbox"/>
Date of Data Income:	EPFL report	<input checked="" type="checkbox"/>
Source of Data:	EPFL report	<input checked="" type="checkbox"/>
Reliability of Data Source:		<input checked="" type="checkbox"/>
Is the Data up-to-date?		<input checked="" type="checkbox"/>
Uncertainty Level:	n.a.	<input checked="" type="checkbox"/>
Further Remarks: N/A		<input checked="" type="checkbox"/>

PDD	Verified Situation	Conclusion
External Data		
ID-PDD:	P	<input checked="" type="checkbox"/>
ID-Internal:	Generated Electricity	<input checked="" type="checkbox"/>
Description of Data / Data Refers to:	The generated total electricity is recorded and cross-checked by various meters (see chapter 3.2). These data cannot be used, because it does not record the additional energy increase separately. Only the hourly recorded Energy (Pr) is relevant for further calculations.	<input checked="" type="checkbox"/>
Unit of Data (if appropriate):	MWh	<input checked="" type="checkbox"/>
Date of Data Income:	see chapter 3.1 and 3.2	<input checked="" type="checkbox"/>
Source of Data:	Various meters onsite, at the substation and the 110 kV CEZ HV TM station	<input checked="" type="checkbox"/>
Reliability of Data Source:		<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

Is the Data up-to-date?		<input checked="" type="checkbox"/>
Uncertainty Level:	0.2%	<input checked="" type="checkbox"/>
Further Remarks: N/A		<input checked="" type="checkbox"/>

3.6. Others (not applicable)

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

4 Data Verification

4.1 Internal Review

Description and performance of internal review			
	Description	Comments	Concl.
Procedure	According to Annex 5 of the MP. The data recorded at the Control room in PdF 1 are checked and validated in the headquarter of Hidroelectrica from Turnu Severin, by the Dispatcher.	Internal review procedures (OP) as part of the existing QM systems are implemented on the data management system (IRL 23).	<input checked="" type="checkbox"/>
Documentation	See remarks above		<input checked="" type="checkbox"/>
Responsibilities	Mr. Dragos Novac is performing the final check of the MR.	Mr. Emil Sopotă – Department for Monitoring the Hydrotechnical Construction has been named as the responsible staff for internal check of the teleimnimeters.	<input checked="" type="checkbox"/>
Further Remarks:			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



4.2 Usage of default values (not applicable)

4.3 Reproducibility

Description and performance of the assessment			
	Description	Comments and Results	Concl.
Procedure	The audit team assessed the consistency and reproducibility of the calculated results. Due to the huge collected data chain, it has been not possible to recalculate all results for cross check.	The calculation program used by the project participant (FORTRAN) is a way of handling the huge amount of data in a short calculation time. A simple program (EXCEL) is used for an easy follow-up of the results (cross-check).	<input checked="" type="checkbox"/>
Further Remarks: N/A			<input checked="" type="checkbox"/>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

4.4 Peculiarities

Description of Peculiarities and unexpected Daily Events during the verification period			
	Description	Comments and Results	Concl.
Performance	During the verification period the facility was running There were no special events during this monitoring period other than scheduled maintenance activities.	As checked with the documents provided (IRL 19) there were only minor events with no real impact on the project. The total availability of the turbines was more than 90% of time.	<input checked="" type="checkbox"/>
Documentation	Turbine logs		<input checked="" type="checkbox"/>
Measures			<input checked="" type="checkbox"/>
Further Remarks: N/A			

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

4.5 Reliability and Plausibility

Description of crosschecks and plausibility checks			
	Description	Comments and Results	Concl.
Performance	The data are plausible and no faulty founded. No discrepancies from the normal trend were found.	The procedures as included in Annex 5 to the MP are in place at the Plant.	<input checked="" type="checkbox"/>
Further Remarks: <u>Clarification Request No.2</u> An explanation regarding the low energy production during the year 2011 and high energy production in the year 2010 is requested.			CL 2

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



Industrie Service

4.6 Completeness and Correctness

Description of completeness and correctness			
	Description	Comments and Results	Concl.
Correctness	All data provided is correct. The data is collected automatically in the control room of the SH PdF 1 and simultaneously entered in the PC of the Dispatch Office from Drobeta Turnu Severin. In the same time the data is sent to the Serbian part for cross-check.	<p>The information included in the work-book has been cross-checked with monthly logbooks (IRL 15) and by random daily checks for:</p> <ul style="list-style-type: none"> • 2008: March 12, h=18, August 30, h=09, • 2009: May 10, h=17, November 01, h=24, • 2010: March 22, h=10, December 15, h=18, • 2011: January 28, h=16, July 10, h=10, <p>All data checked were found to be corrected collected, calculated and stored and further interpreted as for CO2 emission reduction purposes.</p>	<input checked="" type="checkbox"/>
Completeness	The data provided for the assessment is complete		<input checked="" type="checkbox"/>
Further Remarks:			

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



5 Additional requirements (not relevant)

6 Data Reporting

Description of the Monitoring Report		
	Comments and Results	Concl.
Compliance with UNFCCC regulations	The monitoring report for this verification audit follows the CDM MR template of UNFCCC. The verification period covers 2008 - 2011.	<input checked="" type="checkbox"/>
Completeness and Transparency	<p>The verification data consists of :</p> <ul style="list-style-type: none"> - reading protocols for power and head - calculation workbook of the turbine efficiency using power and head <p>The data analysed were complete and transparently presented.</p>	<input checked="" type="checkbox"/>
Correctness	<p><u>Corrective Action Request No.2</u></p> <ul style="list-style-type: none"> - All grammar mistakes, formal mistakes, typos, inconsistencies and non-conservative assumptions have to be revised in the MR <p><u>Corrective Action Request No.3</u></p> <p>In the documents "E_200x":</p> <ul style="list-style-type: none"> - Title is missing - The parameters Ebr and Enet are not defined - URE is used for emission reduction (English) - The data presented in Excel files are not transparent <p>Correction is requested</p>	CAR 2 CAR 3 CAR 4 CAR 5

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

	<p><u>Corrective Action Request No.4</u> There is no header with data/units in the Excel files Correction is requested</p> <p><u>Corrective Action Request No.5</u> Chapter E.6 shall be revised considering only the difference between ex-ante values estimated in the MP ver.1 dated October 2007 and Project values</p>	
Further Remarks: See CAR #1,2,3,4,5		

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania
Date of Completion: 28 November 2012
Number of Pages: 67



7 Compilation and Resolution of CARs, CRs and FARs for Pdf 2

Corrective Action Request by audit team	Summary of project owner response	Audit team conclusion
<p><u>Corrective Action Request No.1</u> On the first page of the MRs a date and a version number shall be included.</p>	<p>The new Monitoring Reports include on the first page: Version 2, July 19, 2012</p>	<p>Confirmed, IRL 33. This issue is closed.</p>
<p><u>Corrective Action Request No.2</u> - All grammar mistakes, formal mistakes, typos, inconsistencies and non-conservative assumptions have to be revised in the MR</p>	<p>The Monitoring Reports, Version 2, July 19, 2012, include the requested correction</p>	<p>Corrections have been made, as checked in the new Monitoring Reports (IRL 26):</p> <ul style="list-style-type: none"> - The “netto value” corrected in MRs 2009-2011 - The yearly ERUs values are rounded - The SI units and abbreviations are correctly used - A legend has been included at page 6 for identification of the scheme - The year 2012 has been excluded from calculations - In the table with meters calibration has been indicated the date of the last calibration performed - The discussion presented in Chapter E.6 regarding the revision of the monitoring methodology has been deleted

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



		<ul style="list-style-type: none"> - Chapter E.5 has been reviewed - In Chapter E.1 the formula for baseline calculation is now included - The monitoring parameters are now consistent with MP <p>These issues are closed.</p>
<p><u>Corrective Action Request No.3</u></p> <p>In the documents “E_200x”:</p> <ul style="list-style-type: none"> - Title is missing - The parameters Ebr and Enet are not defined - URE is used for emission reduction (English) <p>Correction is requested</p>	<p>The “E-200x” files include a title and were corrected. The parameters Ebr and Enet are defined in the new version of the Monitoring Report</p>	<p>Confirmed, IRL 33 and IRL 35.</p> <p>This issue is closed.</p>
<p><u>Corrective Action Request No.4</u></p> <p>There is no header with data/units in the Excel files</p> <p>Correction is requested.</p>	<p>The new excel files include a header with data/units. The “E-200x” files were renamed. The new file name includes “ver 02”.</p>	<p>Corrections have been made, however:</p> <p><u>Corrective Action Request No.6</u></p> <ol style="list-style-type: none"> 1. The Excel calculation files have the same name as the initial ones. A version number shall be included in the name of the files 2. The hour “1” from 01/01/yyyy

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

		<p>is missing</p> <p>3. Definition of the parameters η_{ref} and η_{next} is missing</p> <p>This issue is not closed.</p>
<p><u>Corrective Action Request No.5</u></p> <p>Chapter E.6 shall be revised considering only the difference between ex-ante values estimated in the MP ver.1 dated October 2007 and Project values.</p>	<p>The Monitoring Reports, Version 2, July 19, 2012, include the requested correction</p>	<p>The Monitoring Reports, Version 2, July 19, 2012, is corrected.</p> <p>This issue is closed.</p>
<p><u>Corrective Action Request No.6</u></p> <p>1. The Excel calculation files have the same name as the initial ones. A version number shall be included in the name of the files</p> <p>2. The hour "1" from 01/01/yyyy is missing</p> <p>3. Definition of the parameters η_{ref} and η_{next} is missing</p>	<p>The hour "1" from 01/01/yyyy were included.</p> <p>η_{ref} – is the efficiency for the refurbished turbine</p> <p>η_{next} – is the efficiency for the existing turbine before refurbishment</p>	<p>The new Excel calculation files, version 02.1, (IRL 38) have been provided and all the corrections performed.</p> <p>This issue is closed.</p>
Clarification Requests by the audit team	Summary of project owners response	Audit team conclusion
<p><u>Clarification Request No.1</u></p> <p>According to the document "evidenta contori PFI si PFII.docx" (IRL 21), on 22.06.2011, the meter QYG5019956 has been replaced, but there is no information regarding the new meter installed.</p> <p>Evidence regarding the new meter installed at HG 6 on 22.06.2012 shall be provided to the</p>	<p>A new file "evidenta contori PFI si PFII" were sent in which the new meter is mentioned.</p>	<p>The new meter, QWG 002685388 (IRL 37) has been installed on 13.06.2012 and between 30.05 2011 – 05.07.2012 the unit HG 6 has been out of operation (IRL 36) due to modernisation.</p> <p>This issue is closed.</p>

Verification Protocol

Project Title: Modernization of 4 hydro units in Portile de Fier II
hydro station, Romania

Date of Completion: 28 November 2012

Number of Pages: 67



Industrie Service

TUV SUD verification team.		
<u>Clarification Request No.2</u> An explanation regarding the low energy production during the year 2011 and high energy production in the year 2010 is requested.	During 2011 the flow on Danube was were low, respectively 4209 m ³ /s comparing with the median streamflow for Danube of 5520 m ³ /s ; 2011 was a very dry year	The explanation is clear. This issue is closed.


FIRST PERIODIC VERIFICATION

“Modernization of 4 hydro units in Portile de Fier II hydrostation”




Industrie Service


Annex 2: Information Reference List

Information Reference List	2012-11-28	Periodic Verification of the JI track 1 Project: “Modernization of 4 hydro units in Portile de Fier II Hydro Station” Information Reference List	 Industrie Service
----------------------------	------------	---	--


Ref. No.	Issuance and/or submission date (dd/mm/yyyy)	Title/Type of Document	Author / Editor / Issuer	Additional Information (Relevance in JI Context)
1	November 2008	Project Design Document PDD of JI project “Modernization of 4 hydrounits in Portile de Fier II hydro station ”	Hidroelectrica	
2	24/07/2001	Electricity Generation License issued for the refurbished new capacity in hydropower plant PdF I	ANRE	
3	2007	Procedures for using Joint Implementation (JI) mechanism under Track I (National JI Track I Procedure)	Government of Romania	
4	March 2008	Monitoring Plan of JI project “Modernization of 4 hydrounits in Portile de Fier II hydro station”	Hidroelectrica	
5	14/11/2008	Determination Report of JI project “Modernization of 4 hydrounits in Portile de Fier II hydro station”, Report No.1068445b, Revision 2	TÜV SÜD	
6	28/02/2012	Monitoring Reports of JI project “Modernization of 4 hydrounits in Portile de Fier II hydrostation” for the monitoring period 2008 to 2011	Hidroelectrica	
7	06/04/2010	Decision N.439 by Hidroelectrica regarding the implementation of the project activities PdF I with ERU 01/01 and PdF II with ERU 03/17	Hidroelectrica	
8	02/04/2009	QA_QC Operational and Management Chart. Annex 5 to MP Portile de Fier I : Flow scheme of the monitoring process with data acquisition and archiving steps OPERATIONAL AND MANAGEMENT STRUCTURE	Hidroelectrica	
9	26/06/2009	Certificates on implemented QM systems ISO 9001, ISO 14001 and ISO 18001, validity: 26/06/2012	Hidroelectrica	
10	19/08/2008	Maintenance Contract with Hidroserv	Hidroelectrica	
11	March 2008	Annex 6 to MP Portile de Fier I : Statistical adjustment procedure of the output data to operational conditions	Hidroelectrica	

Information Reference List	2012-11-28	Periodic Verification of the JI track 1 Project: “Modernization of 4 hydro units in Portile de Fier II Hydro Station” Information Reference List	 Industrie Service	
----------------------------	------------	---	--	--

12	March 2008	Annex 7 to MP Portile de Fier I : Description of the monitoring parameters of the project activity	Hidroelectrica	
13	28/02/2012	Annex 1_2_Energy_Protocols_OMEPA_P2 (grid operator) Monthly reports signed by the Grid operator and the PdF I staff in charge : - Supplied electricity to the grid for each individual turbine unit at 110 kV - Purchased electricity from the grid for each individual turbine unit at 110 kV	Hidroelectrica, Transelectrica	PdF I and PdF II
14	28/02/2012	Cross check meters (OMEPA internal meters) SCADA data output on electricity data records at the internal (ABB/PdF II) and external (OMEPA/CEZ) meters for cross check “Diferenta dintre en. el. masurata contori centrala 6KV si contori statie 110 KV PFII 2008-11.pdf»	Hidroelectrica, Transelectrica	PdF I and PdF II
15	28/02/2012	Cross check energy Romania Serbia Bi-annual report on generated electricity data cross check for the Serbian-Romanian commission (2008 – 2011) Folders “Sesiunea 077_2008” ...”Sesiunea 084_2011”	Hidroelectrica	
16	28/02/2012	Annex 1_1_Calibration (and meter scheme) P2 Single line diagramme with the positioning of the meters, “schema_contori_pf2.pdf” and calibration certificates for old and new meters	Hidroelectrica	
19	28/02/2012	Turbine History data on operation, breakdown and maintenance periods for 2008 – 2011 “ANEXA1008(turbine log).doc”...” ANEXA1011(turbine log).doc”	Hidroelectrica	
20	28/02/2012	Technical summary on the functionality of the water level-meters (“telelimnometru”) Folder: “TLN_verificare”	Hidroelectrica	Level meters calibration for the period 2008 –
21	28/02/2012	Calibration certificates for the electricity meters at PdF 1 and PdF 2 «evidenta contori PFI si PFII.docx»	OMEPA	Meters calibration
22	2012	http://www.anre.ro/documente.php?id=395	ANRE	
23	28-02-2012	Working Procedures Romania/Serbia (SCDE). Attachement to Annex 5 of MP	Hidroelectrica	JI Procedures

Information Reference List	2012-11-28	Periodic Verification of the JI track 1 Project: "Modernization of 4 hydro units in Portile de Fier II Hydro Station" Information Reference List	 Industrie Service	
----------------------------	------------	---	--	--

24	15-03-2012	bv_hg6_pf2.pdf	Hidroelectrica	Calibration certificate for HG 6
25	28-02-2012	PV PFI 2008	Hidroelectrica	Invoice Transelectrica PdF 1
26	28-02-2012	PO-HE-PF-138 Catalogare codificare achizitie echipam tehn calcul ed5 rev0	Hidroelectrica	
27	28-02-2012	PO-HE-PF-190 Gestionare materiale utilaje trimise rep la terti ed2 rev0	Hidroelectrica	
28	28-02-2012	Print screens for 28/03/2012: «date instantanee PF1 si PF2.docx»	Hidroelectrica	
29	15-03-2012	Calibration certificates for old (replaced meters) "previous meters PFI and PFII.pdf"	Hidroelectrica	
30	28-02-2012	TLN (teleimnmetru).pdf	Hidroelectrica	Details of the level meter
31	28-02-2012	Folder "Calculation"	Hidroelectrica	Calculation files for ERUs
32	11/2006	"Topogeodetic works for Level Reference, 11/2006 by Hidroelectrica (IRL 16 of the Determination Report)	Hidroelectrica	Level meters accuracy
33	19.07.2012 to 05.11.2012	Monitoring Reports ver. 2, dated 19.07.2012 Monitoring Reports ver. 3, dated 26.09.2012 Monitoring Reports ver. 4, dated 05.11.2012	Hidroelectrica	
34	19.07.2012	Excel calculation files	Hidroelectrica	
35	19.07.2012	E-200x files	Hidroelectrica	Results of excel calculation files
36	19.07.2012	Answer CL1. Meter QYG5019956	Hidroelectrica	

Information Reference List	2012-11-28	Periodic Verification of the JI track 1 Project: “Modernization of 4 hydro units in Portile de Fier II Hydro Station” Information Reference List	 Industrie Service	
----------------------------	------------	---	--	--

37	19.07.2012	Evidence for the meters PF1 and PF2	Hidroelectrica	New meter for HG 6																												
38	21.08.2012	Excel calculation files 2008 to 2011, version 02.1	Hidroelectrica																													
39	28/02/2012-01/03/2012 (Turnu Severin) and 27/02/2012, 15/03/2012 (Bucharest)	<p>On-site interviews conducted in Dr. Turnu Severin, Romania at Hidroelectrica S.A: headquarters by auditing team of TÜV SÜD</p> <p>Verification Team: Mr. Constantin Zaharia GHG auditor, TÜV SÜD</p> <p>Interviewed persons at SH Portile de Fier I and II, Romania</p> <table border="0"> <tr> <td>Mr. Dragos Novac</td> <td>Technical Director – SH Portile de Fier</td> </tr> <tr> <td>Mr. Christian Bocse</td> <td>Manager SEME– SH Portile de Fier</td> </tr> <tr> <td>Mrs. Dana Horhoianu</td> <td>Environmental Adviser– SH Hidroelectrica</td> </tr> <tr> <td>Mrs. Mereuta Dumitra</td> <td>Environmental Director– SH Hidroelectrica</td> </tr> <tr> <td>Mr Ciprian Rachitan</td> <td>Metering responsible , SH Portile de Fier</td> </tr> <tr> <td>Mr Danut Caplea</td> <td>STIC, SH Portile de Fier</td> </tr> <tr> <td>Mr. Vuc Remus</td> <td>Dispacher SH Portile de Fier II</td> </tr> <tr> <td>Mr. Paraschivoiu Mitica</td> <td>technician, SH Portile de Fier II</td> </tr> </table> <p>Abbreviations:</p> <table border="0"> <tr> <td>ANRE</td> <td>Energy Market Regulatory Authority, Romania</td> </tr> <tr> <td>ASTRÖ</td> <td>Anstalt für Strömungsmaschinen GmbH, Austria</td> </tr> <tr> <td>CEZ</td> <td>Regional grid operator in charge of PdF II</td> </tr> <tr> <td>EPFL</td> <td>Ecole Polytechnique Federal Lausanne</td> </tr> <tr> <td>OMEPA</td> <td>National Operator in charge of Electricity Metering and Accounting</td> </tr> <tr> <td>Transelectrica</td> <td>National Grid operator, Romania</td> </tr> </table>	Mr. Dragos Novac	Technical Director – SH Portile de Fier	Mr. Christian Bocse	Manager SEME– SH Portile de Fier	Mrs. Dana Horhoianu	Environmental Adviser– SH Hidroelectrica	Mrs. Mereuta Dumitra	Environmental Director– SH Hidroelectrica	Mr Ciprian Rachitan	Metering responsible , SH Portile de Fier	Mr Danut Caplea	STIC, SH Portile de Fier	Mr. Vuc Remus	Dispacher SH Portile de Fier II	Mr. Paraschivoiu Mitica	technician, SH Portile de Fier II	ANRE	Energy Market Regulatory Authority, Romania	ASTRÖ	Anstalt für Strömungsmaschinen GmbH, Austria	CEZ	Regional grid operator in charge of PdF II	EPFL	Ecole Polytechnique Federal Lausanne	OMEPA	National Operator in charge of Electricity Metering and Accounting	Transelectrica	National Grid operator, Romania	TÜV SÜD	
Mr. Dragos Novac	Technical Director – SH Portile de Fier																															
Mr. Christian Bocse	Manager SEME– SH Portile de Fier																															
Mrs. Dana Horhoianu	Environmental Adviser– SH Hidroelectrica																															
Mrs. Mereuta Dumitra	Environmental Director– SH Hidroelectrica																															
Mr Ciprian Rachitan	Metering responsible , SH Portile de Fier																															
Mr Danut Caplea	STIC, SH Portile de Fier																															
Mr. Vuc Remus	Dispacher SH Portile de Fier II																															
Mr. Paraschivoiu Mitica	technician, SH Portile de Fier II																															
ANRE	Energy Market Regulatory Authority, Romania																															
ASTRÖ	Anstalt für Strömungsmaschinen GmbH, Austria																															
CEZ	Regional grid operator in charge of PdF II																															
EPFL	Ecole Polytechnique Federal Lausanne																															
OMEPA	National Operator in charge of Electricity Metering and Accounting																															
Transelectrica	National Grid operator, Romania																															