## Projects to Reduce Emissions Rotokawa Geothermal Project (Mighty River Power Limited) 2010 Annual Report Independent Verification Report

**Project verified:** 

Rotokawa Geothermal Project Mighty River Power Limited Aaron Smith 64 (0) 9 308 6332 aaron.smith@mightyriver.co.nz

Independent verifier:

Noim Uddin DNV Australia

Date of verification:

16-17/03/2011

| PRE Project Information                                  |                               |  |  |
|--|-------------------------------|--|--|
| Name of Project: Rotokawa Geotherm                       | al Project                    |  |  |
| Project Site Address: Taupo, New Zea                     | land                          |  |  |
| Name of Project Participant:                             |                               |  |  |
| Mighty River Power Limited                               |                               |  |  |
| Name of Project contact:                                 | Telephone:                    |  |  |
| Aaron Smith  | 64 (0) 9 308 6332             |  |  |
| Postal Address:  | Email:                        |  |  |
| Level 14, ANZ Centre<br>23-29 Albert St<br>Auckland 1010 | aaron.smith@mightyriver.co.nz |  |  |
| Street Address:  | Fax:                          |  |  |
| Taupo, New Zealand                                       |                               |  |  |
| Verifier Information                                     |                               |  |  |
| Name of Company:   | Telephone:                    |  |  |
| DNV Australia  | 61 (0) 2 9922 1966            |  |  |
| Name of Lead Verifier:                                   | Fax:                          |  |  |
| Noim Uddin   | 61 (0) 2 9929 8792            |  |  |
| Email:   | Date(s) of Verification:      |  |  |
| Noim.uddin@dnv.com                                       | 16-17/03/2011                 |  |  |
| Verification Team Members:                               |                               |  |  |
| Noel Peters (DNV Sydney)                                 |                               |  |  |
| PRE Annual Report Verified                               |                               |  |  |
| Annual Report 2010                                       |                               |  |  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* Annual Report

2

### **1** Verification Statement

To:

Catherine Schofield Senior Analyst, Funds Management Ministry for the Environment PO Box 10362 Wellington New Zealand

#### 1.1 Introduction

DNV Australia has been engaged by the Ministry for the Environment on behalf of the *Crown* to undertake a verification of Mighty River Power's *Projects to Reduce Emissions (PRE Project)* Rotokawa Geothermal Project 2010 Annual Report (2010 Annual Report). The verification has been planned and performed in accordance with the Verification Plan of 01/03/2011 and our contract of 08/02/2011.

We have reviewed the nature of the 2010 Annual Report and have concluded that we are able to conduct a reasonable assurance verification of the criteria items directly related to operation of the project and limited assurance verification of the scope items which describe competence of the Project Participant and the interaction of the project with local regulatory authorities. We have indicated the relevant scope items in the Scope of Verification below.

#### 1.2 Objective

The objective of the verification engagement is to form an opinion as to whether the 2010 Annual Report is prepared in accordance with the PRE Project Agreement between the Crown and the Project Participant (Project Agreement) and is free from material discrepancy.

#### 1.3 Criteria

*DNV Australia* conducted sufficient verification procedures to enable us to express a reasonable assurance verification opinion on the following matters that, in all material respects:

- 1. The *2010* Annual Report includes the information detailed in Schedule 4 of the Project Agreement and has used correct template as per the Ministry for the Environment guidelines;
- 2. The recording and calculation of the emission reductions for the year uses the relevant emission factors and adopts the calucation of net emission reduction method as set out in Schedule 2 of the Project Agreement;
- 3. The calculation behind the Emission Units claimed for *2010*, uses the net emission reduction and the request ratio ("C") set out in clause 5.1 of the Project Agreement;
- 4. Project emissions calculation (using the emissions factors set out in Schedule 2) (a) emissions due quantities of petrol and diesel used in the project (during construction and operation), emissions due to introducing cement, iron, steel and aluminium as materials (b) emissions due to purchased electricity as auxiliary power, and (c) emissions due to non condensable gases (only CO<sub>2</sub> according to Schedule 2) in the geothermal steam.

- 5. Metering (electricity, quantity of steam discharged from the geothermal wells, pressure and temperature of the steam, non condensable gases) equipment installed has been certified by independent reputable quality assured service provider(s).
- 6. Recording of electricity supply to the grid by accredited Half Hour Data Administrator or sales revenue invoices, recording of steam discharged from the geothermal wells, recording of pressure and temperature of the steam, recording of non condensable gases.
- 7. Any other (electricity, heat, steam) generation, not part of the project, that flows through these meters has been identified, measured and subtracted;
- 8. Any significant changes to the PRE project and its baseline scenario.
- 9. Within the context of verification, any other requirement relating to the PRE project Agreement.

*DNV Australia* conducted sufficient verification procedures to enable us to express a limited assurance verification opinion on the following matter that, in all material respects:

- 10. The project participant has adequate understanding of the principles and requirements of the PRE programme and is competent to conform to those principles and requirements; and
- 11. Compliance with the regulatory requirements of local and central government agencies (including any requirement of environmental monitoring and reporting).

#### 1.4 Verification scope

The scope of verification of the 2010 Annual Report is as follows:

#### 1.4.1 GHG project and baseline scenarios relevant to the Project

The relevant project and baseline scenarios are as follows:

- 1. baseline scenario: business as usual electricity generation in New Zealand without electricity supply from Rotokawa Geothermal Project; and
- 2. project scenario: electricity generation from Rotokawa Geothermal Project as additional.

## 1.4.2 Physical infrastructure, activities, technologies and processes of the GHG project

The elements of the project subject to verification are as follows:

- 1. Physical infrastructure: rated capacity of the electricity generation unit, construction of the steam collection facility, construction of the electricity generation facility, electricity supply network to the grid;
- 2. Project activities: generation of electricity by using steam from geothermal facility;
- 3. Technologies: steam-to-electricity conversion systems (steam turbine and generator); and

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 4 Annual Report

4. Processes: quality of steam (pressure and temperature), monitoring of steam flow, monitoring of non condensable gas (fraction of CO<sub>2</sub>), supplying of electricity to the electricity grid, maintenance of metering, calibration and data archiving.

## 1.4.3 GHG sources, sinks and/or reservoirs included within the Project boundary

Project GHG sources within the Project boundary are:

- 1. CO<sub>2</sub>e emission in respect of the electricity output
- 2. CO<sub>2</sub> emission in respect of the exhaust steam
- 3. CO<sub>2</sub>e emission in respect of the quantities of construction materials, fossil fuels and electricity used in, purchased by, or introduced into the project.

#### 1.4.4 Types of GHGs included within the project boundary

The GHG species included within the Project Agreement are:

- 1. CO<sub>2</sub>
- 2.  $CH_4$ , N<sub>2</sub>O, SF<sub>6</sub> and PFCs not applicable to this project activity.

#### 1.4.5 Time period of the Annual Report

The verification is of all project activities in the period 1 January 2010 to 31 December 2010.

#### **1.5 Verification Principles**

*DNV Australia* conducted the verification in accordance with ISO 14065 and our contract with the *Crown* and the verification principles under clause 7 of the Project Agreement.

#### 1.6 Project Participant's Responsibilities

Mighty River Power Ltd is responsible for preparing the 2010 Annual Report and maintaining an effective internal control environment and data management system, including control procedures supporting the inputs into this documentation, in accordance with accepted good practice.

#### 1.7 Verifier Responsibilities

The verification has been conducted in accordance with ISO14064-3 and ISO14065 in order to provide a reasonable and limited level of assurance as described in the verification scope. As such *DNV Australia* has undertaken the following procedures that we considered appropriate to be able to provide a reasonable and limited level of assurance.

#### **1.8 Verification Procedures**

Our verification has been conducted in accordance with ISO14064-3 and ISO14065 to provide reasonable assurance that the greenhouse gas assertions and other information contained in the 2010 Annual Report are free from material misstatement. Accordingly, we have conducted such tests and procedures as we considered appropriate to be able to provide reasonable assurance including:

 On-site visit at the Rotokawa (Nga Awa Purua) Geothermal Power Plant to examine the geothermal steam collection facility, reinjection operation, PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 5 Annual Report

operation of steam turbine and generation of electricity, electricity metering, record keeping procedure, consumption of any other fossil fuels and electricity during operation, maintenance of the facility, and resource consent compliance.

- Interviews with operational, management and record keeping personnel responsible for maintenance, operation, management and reporting at the facility.
- Review of key documents, including:
  - Projects to Reduce Emissions Agreement with the Crown dated 29 March 2004.
  - Project Agreement Amendment 1 dated 10 June 2005.
  - Project Agreement Amendment 2 dated 18 February 2008.
  - 2010 Annual Report to be submitted to the Ministry for the Environment, New Zealand (revised version dated 15 February 2011).
- Random sample testing of source data, including:
  - o Electricity generation.
  - Non condensable gas CO<sub>2</sub>
  - Any other fossil fuel consumption (diesel and petrol).
  - o Introduction of any construction materials.
- Confirmation that the calculation methodology is in compliance with Schedule 2 of the Project Agreement.
- Discussions with the relevant Ministry for the Environment personnel.
- Observation and review of relevant documentations.

The results of the verification procedures undertaken are set out in the appended Attachment 1 – Verification Procedures and Findings.

Mighty River Power's personnel have overall responsibility for the project including maintenance and operational data management.

DNV Australia confirms that it is not aware of any actual or perceived conflict of interest in having completed this engagement.

#### 1.9 Independent Review

*DNV Australia* has completed an independent review, undertaken by competent personnel who did not participate in the verification, to:

- confirm that all verification activities have been undertaken; and
- conclude whether or not the assertions in the 2010 Annual Report are free from material discrepancy, and whether the verification activities provide a reasonable level of assurance and a limited level of assurance for the scope items nominated above.

In making this verification statement, we confirm that:

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 6 Annual Report

Prepared by Noim Uddin, DNV Australia on 21/03/2011

- DNV is currently accredited as a Designated Operational Entity (DOE) by the Conference of Parties as per the Ministry for the Environment requirements.
- This verification has been conducted in accordance with the requirements of ISO 14064-3.
- The findings and conclusions documented in this report are guided by professional judgment and supported by verification records held by us.

#### 1.10 Inherent Limitations

Because of the inherent limitations in any internal control environment and data management system, it is possible that fraud, error, or non-compliance with the Project Agreement may occur and may not be detected. Further, the verification was not designed to detect all weakness or errors in the internal control environment and data management system so far as they relate to the scope set out above, as the verification has not been performed continuously throughout the period and the procedures performed on the relevant internal information and data management system were on a test basis. Any extrapolation from this verification to future periods is subject to the risk that the procedures may become inadequate because of changes in conditions, or that the degree of compliance with them may deteriorate.

*DNV Australia* did not conduct any verification procedures with respect to the internal control environment and data management system of the Mighty River Power Limited as a whole. As such, no assurance is provided on any internal control environment and data management system not associated with the 2010 *Annual* Report.

The verification opinion expressed in this Report has been formed on the above basis.

#### 1.11 Verification Opinion

Our opinion, following the reasonable assurance verification undertaken at the Rotokawa (Nga Awa Purua) Geothermal Power Plant site, Taupo of the GHG assertions included in the 2010 Annual Report and the subsequent review of associated documents is that the following matters are fairly presented, in all material aspects, in accordance with the PRE requirements:

- 1. the 2010 Annual Report includes the information detailed in Schedule 4 of the Project Agreement and has used the correct template as per the Ministry for the Environment guidelines;
- 2. the recording and calculation of the emission reductions for the year using the relevant emission factors and adopting the calculation of net emission reduction method as set out in Schedule 2 of the Project Agreement;
- 3. the calculation behind the Emission Reduction Units claimed for 2010, using the net emission reduction and the request ratio ("C") set out in clause 5.1 of the Project Agreement;
- 4. project emissions calculation (using the emissions factors set out in Schedule 2) (a) emissions due to quantities of petrol and diesel used in the project (during construction and operation), emissions due to introducing cement, iron, steel and aluminium as materials (b) emissions due to purchased electricity as auxiliary power, and (c) emissions due to non condensable gases (only CO<sub>2</sub> according to Schedule 2) in the geothermal steam;

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 7 Annual Report

- metering (electricity, quantity of steam discharged from the geothermal wells, pressure and temperature of the steam, non condensable gases) equipment installed has been certified by independent reputable quality assured service provider(s);
- 6. recording of electricity supply to the grid by an accredited Half Hour Data Administrator or sales revenue invoices, recording of steam discharged from the geothermal wells, recording of pressure and temperature of the steam, recording of non condensable gases;
- 7. any other (electricity, heat steam) generation, not part of the project, that flows through these meters is identified, measured and subtracted;
- 8. any significant changes to the PRE Project and its baseline scenario; and
- 9. within the context of verification, any other requirement relating to the Project Agreement.

#### 1.12 Limited Assurance Verification Opinion

In our opinion, nothing came to our attention during the limited assurance verification undertaken at *Rotokawa (Nga Awa Purua)* Geothermal Power Plant site at Taupo of the 2010 Annual Report and subsequent review of associated documents to indicate that the assertion that the regulatory requirements of local and central government agencies have been met is not, in all material aspects, in accordance with the PRE Guidance requirements.

- 1. The Project Participant has adequate understanding of the principles and requirements of the PRE programme and is competent to perform those principles and requirements; and
- 2. Compliance with the regulatory requirements of local and central government agencies (including any requirement of environmental monitoring or reporting).

#### 1.13 Suggestions

No suggestion is made for this verification.

#### 1.14 Limitations on use

This Verification Statement has been prepared for the *Crown* solely for use in relation to the *Projects to Reduce Emissions* programme. *DNV Australia* disclaims any liability for reliance upon this Report by any other party or for any other purpose other than for which it was prepared.

| Name of Lead Verifier:               | Noim Uddin                   |
|--------------------------------------|------------------------------|
| Position:                            | Lead Climate Change Verifier |
| Company and Location:                | DNV Australia, Sydney        |
| Signature of Lead Verifier:          | Sludd                        |
| Date:                                | 13/04/2011                   |
| Name of Independent<br>Reviewer      | Noel Peters                  |
| Signature of Independent<br>Reviewer |                              |
| Date:                                | 04/04/2011                   |

Attachment 1 - Verification Procedures and Findings

# 2 Attachment 1 – verification procedures and findings

Attachment 1 is a record of the verification procedures conducted in accordance with ISO 14064-3 and ISO 14065 and of the verification findings. The checklist is not a comprehensive description of all the verification procedures performed or all verification evidence obtained during the verification process, but is a fair presentation of the procedures and findings in sufficient detail to enable all findings (both positive and negative) to be verified.

| Criteria Item 1<br>verified | The 2010 Annual Report includes the information detailed in Schedule 4 of the Project Agreement.  |   |   |  |  |
|-----------------------------|---|---|---|--|--|
| Description of requirement  | That all of the information detailed in Schedule 4 of the Project<br>Agreement for inclusion in the Annual Report has been<br>included and is fairly stated.                |   |   |  |  |
| Verification<br>procedures  | Verification item Information Comments Source/Evidence  |   |   |  |  |
|                             | Cross check of<br>Annual Report<br>information with the<br>requirements<br>documented in  | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004 | The 2010 Annual<br>Report is in<br>compliance with<br>Schedule 4 of the<br>Project Agreement. |  |  |
|                             | Schedule 4 of the<br>Project Agreement.   | Project Agreement<br>Amendment 1<br>dated 10 June<br>2005                             |   |  |  |
|                             |   | Project Agreement<br>Amendment 2<br>dated 18 February<br>2008                         |   |  |  |
|                             | 2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011                               |   |   |  |  |
| Findings                    | The 2010 Annual Report has been completed according to the Schedule 4 of the Project Agreement.   |   |   |  |  |
|                             | The 2010 Annual Report was sighted during this review and the required items checked against Schedule 4 of the Project Agreement (Contents of Annual Reports), these being: |   |   |  |  |
|                             | Total electricity supplied from the Rotokawa (Nga Awa   |   |   |  |  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 10 Annual Report

|            | <ul> <li>Purua) Geothermal: 997.60 GWh.</li> <li>Calculation of tonnes CO<sub>2</sub>-e emission reductions of 409 991 tonnes CO<sub>2</sub>-e calculated in accordance to the methodology from Schedule 2 of the Project Agreement.</li> </ul> |
|------------|---|
| Conclusion | All of the information detailed in Schedule 4 of the Project<br>Agreement has been included and is fairly stated in the 2010<br>Annual Report.  |

| Criteria Item 2<br>verified | The recording and calculation of the emission reductions for the year uses the relevant (e.g., electricity) emission factors set out in Schedule 2 (or as otherwise defined).  |   |  |  |  |
|-----------------------------|--|---|--|--|--|
| Description of requirement  | That the emission factors used in the Annual Report are the<br>same as those in Schedule 2 (or as otherwise defined) of the<br>Project Agreement, and that the mathematical calculation of<br>emission reductions using the emission factors and project<br>activity parameters are fairly stated. |   |  |  |  |
| Verification procedures     | Verification item Information Comments Source/Evidence   |   |  |  |  |
|                             | Cross check of<br>emission factors<br>used in the<br>emission reduction<br>calculation with the  | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004   | The relevant<br>emission factors<br>have been correctly<br>applied in<br>accordance with |  |  |
|                             | emission factors in<br>Schedule 2 (or as<br>otherwise defined)<br>of the Project<br>Agreement.   | Project Agreement<br>Amendment 1<br>dated 10 June<br>2005   | Schedule 2 –<br>Measurement of<br>Emission<br>Reductions.                                |  |  |
|                             |  | Project Agreement<br>Amendment 2<br>dated 18 February<br>2008   |  |  |  |
|                             |  | 2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011 |  |  |  |
|                             | not included in no emi<br>Schedule 2 are were u  |   | Not applicable as<br>no emission factors<br>were used other<br>than in Schedule 2.       |  |  |
| PRE Programme Indens        | Confirmation that<br>the measurement<br>of project activity<br>parameters hasProjects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29All project activity<br>parameters are<br>monitored and  |   |  |  |  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 12 Annual Report

| been properly | March 2004   | reported properly.  |
|---------------|--|---|
| undertaken.   |  |   |
|               | Project Agreement<br>Amendment 1<br>dated 10 June<br>2005  | The Rotokawa<br>(Nga Awa Purua)<br>Geothermal Power<br>Plant generates  |
|               | Project Agreement<br>Amendment 2<br>dated 18 February<br>2008  | electricity by using<br>geothermal steam.<br>The steam is sent<br>to the turbine after  |
|               | 2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011  | it has been<br>separated from the<br>water. As it passes<br>through the turbine<br>blades it causes the<br>turbine to spin,<br>which in turn spins<br>the generator,<br>creating electricity.   |
|               | Electricity<br>generation from<br>Rotokawa (Nga<br>Awa Purua)<br>Geothermal Power<br>Plant during 2010<br>from Mighty River<br>Power Ltd as Half<br>Hour Data<br>Administrator<br>(dated 12 January<br>2011) | A total of 997.60<br>GWh of electricity<br>delivered from<br>Rotokawa (Nga<br>Awa Purua)<br>Geothermal Power<br>Plant during the<br>period 01/01/2010<br>to 31/12/2010 has<br>been measured by<br>the Half Hour Data<br>Administrator |
|               | Electricity import by<br>Rotokawa (Nga<br>Awa Purua)   | Mighty River Power<br>Ltd.  |
|               | Geothermal Power<br>Plant during 2010<br>from Mighty River<br>Power Ltd as Half<br>Hour Data<br>Administrator<br>(dated 12 January<br>2011)  | A total of 0.88 GWh<br>of electricity is<br>imported by<br>Rotokawa<br>Geothermal Power<br>Plant during the<br>period 01/01/2010<br>to 31/12/2010 has<br>been measured by   |
|               | Screenshot of<br>RIMbase inventory<br>maintained by<br>Mighty River Power<br>Ltd (dated 1 April<br>2014)   | the Half Hour Data<br>Administrator<br>Mighty River Power<br>Ltd.   |
|               | <ul> <li>2011):</li> <li>Consumption of diesel and petrol during</li> </ul>  | A total of<br>588,417.47 litres of<br>diesel was<br>consumed during<br>the construction   |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal* 2010 13 Annual Report

| construction of<br>the Rotokawa<br>Geothermal,<br>from<br>Construction<br>Contractor as<br>inventory is<br>maintained by<br>Mighty River<br>Power Ltd  | and operation of<br>the Rotokawa<br>Geothermal Project<br>during 2010,<br>according to data<br>sourced from<br>RIMbase<br>maintained by<br>Mighty River Power<br>Ltd.   |
|--|---|
| <ul> <li>Consumption of<br/>diesel and petrol<br/>during operation<br/>of Rotokawa<br/>Geothermal<br/>Power Plant,<br/>inventory of<br/>diesel purchase<br/>is maintained by<br/>Mighty River<br/>Power Ltd</li> <li>Introduction of<br/>construction</li> </ul> | Approximately<br>36177 litres of<br>petrol consumption<br>has been recorded<br>due to the<br>operation of the<br>Rotokawa<br>Geothermal Plant<br>during 2010,<br>according to data<br>sourced from<br>Construction<br>Contractor Fuji<br>Electric Systems |
| materials (steel<br>and iron,<br>aluminium and<br>cement) from<br>Construction<br>Contractor as<br>inventory is<br>maintained by<br>Mighty River<br>Power Ltd<br>Operational control<br>documents of<br>Rotokawa (Nga<br>Awa Purua)                              | Ltd.<br>A total of 611.60<br>tonnes of steel and<br>iron was introduced<br>during construction<br>of the Rotokawa<br>Geothermal Project<br>during 2010,<br>according to data<br>sourced from<br>RIMbase<br>maintained by<br>Mighty River Power<br>Ltd.    |
| Geothermal Power<br>Plant (16 March<br>2011):<br>Quantity of CO <sub>2</sub><br>content in the<br>geothermal steam,<br>from GNS Science<br>Wairakei Analytical<br>Laboratory<br>assessment<br>Reports  | A total of 21 tonnes<br>of aluminium was<br>introduced during<br>construction of the<br>Rotokawa<br>Geothermal<br>Project, during<br>2010 according to<br>data sourced from<br>Fuji Electric<br>Systems Ltd.  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 14 Annual Report

|  | used is measured<br>by three venturi<br>meters located at<br>the inlets of High<br>Pressure (HP),<br>Intermediate<br>Pressure (IP) and<br>Low Pressure (LP)<br>turbines | tonnes of cement<br>was introduced<br>during construction<br>of the Rotokawa<br>Geothermal Project<br>during 2010,<br>according to data<br>sourced from<br>RIMbase<br>maintained by<br>Mighty River Power<br>Ltd.  |
|--|---|--|
|  |   | Records of the total<br>construction<br>materials<br>introduced and<br>fossil fuel<br>consumed during<br>operation of<br>Rotokawa (Nga<br>Awa Purua)<br>Geothermal Power<br>Plant are in the<br>opinion of the<br>verifier reasonable<br>for this type of<br>construction<br>activity.   |
|  |   | Mighty River Power<br>Ltd performs<br>checks of the<br>quantity of CO <sub>2</sub> in<br>geothermal steam<br>on monthly basis.<br>The amount of CO <sub>2</sub><br>(mmoles of CO <sub>2</sub> per<br>100 moles of H <sub>2</sub> O)<br>present in<br>geothermal steam<br>is measured by<br>GNS Science<br>Wairakei Analytical<br>Laboratory. |
|  |   | Average monthly<br>concentration of<br>CO <sub>2</sub> in steam<br>(tCO <sub>2</sub> e/tonne<br>steam) has been<br>estimated by<br>Mighty River Power  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 15 Annual Report

|  | Ltd.   |
|--|--|
|  |  |
|  | The total quantity of<br>HP, IP and LP<br>steam supplied to<br>the HP turbine, IP<br>turbine and LP<br>turbine are<br>measured by<br>venturi meters and<br>aggregated every<br>half hour.  |
|  | Steam data<br>collected during<br>January and<br>February 2010 was<br>not used to<br>calculate the<br>monthly average<br>tonne CO <sub>2</sub><br>emission per tonne<br>of steam. This is<br>because the steam<br>samples taken<br>were not under<br>normal plant<br>operating |
|  | conditions.<br>Instead, the<br>weighted average<br>tonne CO <sub>2</sub><br>emission per tonne<br>of steam was<br>calculated during  |
|  | the period March<br>2010 to December<br>2010. The weighted<br>average tonne CO <sub>2</sub><br>emission per tonne<br>of steam was<br>calculated to be<br>0.0189 tCO <sub>2</sub> e/tonne<br>steam. This<br>emission factor was   |
|  | applied for the<br>period January<br>2010 to February<br>2010 to obtain an<br>estimation of the<br>total emissions   |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 16 Annual Report

|   |  | from steam.  |
|---|--|--|
|   |  | This is, in the<br>opinion of the<br>verifier, a<br>reasonable<br>conservative<br>approach.                            |
| Confirmation that<br>the measured<br>project activity<br>parameters have<br>been accurately<br>transcribed to the<br>Annual Report. | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004<br>Project Agreement<br>Amendment 1<br>dated 10 June<br>2005<br>Project Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the | The measured<br>project activity<br>parameters have<br>been accurately<br>transcribed in the<br>2010 Annual<br>Report. |
|   | Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011   |  |
| Confirmation by<br>alternate or check<br>calculation that the<br>determination of<br>emission reductions<br>is fairly stated.       | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004  | The total emission<br>reductions<br>calculation was<br>checked and found<br>to be fairly stated.                       |
| is faily stated.  | Project Agreement<br>Amendment 1<br>dated 10 June<br>2005  |  |
|   | Project Agreement<br>Amendment 2<br>dated 18 February<br>2008  |  |
|   | 2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised  |  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 17 Annual Report

|            |   | version) d<br>April 2011 |                                      |                                 |
|------------|---|--------------------------|--------------------------------------|---------------------------------|
| Findings   | The emission factors  | used in the              | e Annual Re                          | eport are:                      |
| -          | Item  |                          | Emission                             | factor                          |
|            | Electricity   |                          | 600 tonne                            | es CO <sub>2</sub> -e /GWh      |
|            | Diesel  |                          | 0.002617                             | tonnes CO <sub>2</sub> -e/litre |
|            | Petrol  |                          | 0.002298                             | tonnes CO <sub>2</sub> -e/litre |
|            | Cement  |                          | 0.48 tonne                           | es CO <sub>2</sub> -e/tonne     |
|            | Steel and iron  |                          | 1.95 tonnes CO <sub>2</sub> -e/tonne |                                 |
|            | Aluminium   |                          | 1.74 tonnes CO <sub>2</sub> -e/tonne |                                 |
|            | The mathematical calculation of emission reductions is in accordance with Schedule 2 and fairly stated. The emission factors and project activity parameters are correctly applied. |                          |                                      |                                 |
| Conclusion | The relevant emission factors have been correctly applied in accordance with Schedule 2 – Methodology for Determining Emission Reductions.  |                          |                                      |                                 |
|            | The mathematical calculation of emission reductions using the emission factors and project activity parameters are fairly stated.   |                          |                                      |                                 |

| Criteria Item 3<br>verified | The calculation behind the Emission Units claimed for 2010 uses the net emission reduction and the request ratio ("C") set out in clause 5.1 of the Project Agreement.  |  |  |  |  |
|-----------------------------|---|--|--|--|--|
| Description of requirement  | That the calculation of Emission Units properly uses the net<br>emission reduction calculated for the year 2010 taking due<br>account of the request ratio ("C") set in Clause 5.1 of the<br>Project Agreement. |  |  |  |  |
| Verification procedures     | Verification item Information Comments Source/Evidence  |  |  |  |  |
|                             | Confirm that the calculation takes proper account of the request ratio.   | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004  | The correct request<br>ratio (C=1.0) has<br>been used to<br>estimate the 2010<br>emission unit |  |  |
|                             |   | Project Agreement<br>Amendment 1<br>dated 10 June<br>2005  | claims.  |  |  |
|                             | Project Agreement<br>Amendment 2<br>dated 18 February<br>2008   |  |  |  |  |
|                             |   | 2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011      |  |  |  |
|                             | Confirm that the<br>calculation of<br>Emission units is<br>based on net<br>emission<br>reductions.  | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004<br>Project Agreement<br>Amendment 1<br>dated 10 June<br>2005 | The calculation of<br>the emission units is<br>based on net<br>emission<br>reductions.         |  |  |
|                             |   | Project Agreement<br>Amendment 2<br>dated 18 February<br>2008  |  |  |  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 19 Annual Report

|            | 2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011                          |  |  |
|------------|--|--|--|
| Findings   | Request ratio (C=1.0) has been applied correctly.  |  |  |
|            | The calculation behind the Emission Units claimed for 2010 uses the net emission reduction.  |  |  |
| Conclusion | Request ratio (C=1.0) was used as defined in the Project Agreement. The calculation behind the Emission Units claimed for <i>2010</i> uses the net emission reduction. |  |  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 20 Annual Report

| Criteria Item 4<br>verified | If applicable: the construction emissions calculations uses (a)<br>the emission factors set out in Schedule 2 (or as defined<br>elsewhere), and (b) the records of the quantities of materials,<br>fuels, electricity purchased etc. relevant to emissions during<br>construction. |   |  |
|-----------------------------|--|---|--|
| Description of requirement  | That calculation of construction emissions uses the emission factors set out in Schedule 2 (or as defined elsewhere) and measured quantities of construction materials, accurately transcribed to the Annual Report.   |   |  |
| Verification procedures     | Verification item  | Information<br>Source/Evidence  | Comments   |
|                             | Confirm that the calculation uses the correct emission factors.  | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004   | Commissioning of<br>the project activity<br>continued during<br>2010 reporting<br>period.  |
|                             |  | Project Agreement<br>Amendment 1<br>dated 10 June<br>2005                               | Emissions due to<br>the introduction of<br>cement, aluminium<br>and iron and steel   |
|                             |  | Project Agreement<br>Amendment 2<br>dated 18 February<br>2008                           | as construction<br>materials have<br>been estimated.<br>The calculation of   |
|                             |  | 2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New | construction<br>emissions used the<br>emission factors<br>set out in Schedule<br>2.  |
|                             |  | Zealand (revised<br>version) dated 1<br>April 2011                                      | Emissions due to<br>the use of diesel<br>and petrol have<br>been estimated.<br>The calculation of<br>emissions due to<br>the use of diesel<br>used the emission<br>factors set out in<br>Schedule 2. |
|                             |  |   | Emissions due to<br>the purchase of<br>electricity have<br>been estimated.<br>The calculation of<br>emissions due to   |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 21 Annual Report

|   |  | the purchase of<br>electricity used the<br>emission factors<br>set out in Schedule<br>2.  |
|---|--|---|
| Confirmation that<br>all appropriate<br>construction<br>materials have<br>been included.  | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004<br>Project Agreement<br>Amendment 1<br>dated 10 June<br>2005<br>Project Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011 | Iron and steel,<br>aluminium and<br>cement have been<br>used as<br>construction<br>materials.<br>This is, in the<br>opinion of the<br>verifier, reasonable<br>for this type of<br>construction.   |
| Review of the<br>record keeping<br>arrangements to<br>confirm that the<br>measured<br>quantities of<br>construction<br>materials are a fair<br>presentation of<br>actual usage. | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004<br>Project Agreement<br>Amendment 1<br>dated 10 June<br>2005<br>Project Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011 | Data sourced from<br>the construction<br>contractor and<br>maintained by<br>Mighty River Power<br>Ltd's inventory<br>RIMbase were<br>used to estimate<br>the use of iron and<br>steel and<br>aluminium.<br>Data sourced from<br>the construction<br>contractor and<br>maintained by<br>Mighty River Power<br>Ltd's inventory<br>RIMbase were<br>used to estimate<br>use of cement.<br>In the opinion of<br>the verifier the |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal* 2010 22 Annual Report

|  | Screenshot of<br>RIMbase inventory<br>maintained by<br>Mighty River Power<br>Ltd dated 1 April<br>2011   | record keeping<br>arrangements and<br>estimates are<br>reasonable for this<br>type of<br>construction.  |
|--|--|---|
| The exercise of<br>professional<br>judgement in<br>relation to whether<br>the claimed<br>quantity of<br>construction<br>materials was<br>reasonable. | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004<br>Project Agreement<br>Amendment 1<br>dated 10 June<br>2005<br>Project Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011<br>Screenshot of<br>RIMbase inventory<br>maintained by<br>Mighty River Power<br>Ltd dated 1 April<br>2011 | A total of 611.60<br>tonnes of steel and<br>iron was introduced<br>during construction<br>of the Rotokawa<br>Geothermal Project<br>activity during<br>2010.<br>A total of 21.00<br>tonnes of<br>aluminium was<br>introduced during<br>construction of the<br>Rotokawa<br>Geothermal Project<br>activity during<br>2010.<br>A total of 1009.30<br>tonnes of cement<br>was introduced<br>during construction<br>of the Rotokawa<br>Geothermal Project<br>activity during<br>2010.<br>The totals of<br>construction<br>materials<br>introduced in the<br>Rotokawa<br>Geothermal Project<br>activity are in the<br>opinion of the<br>verifier reasonable<br>for this type of<br>construction<br>activity. |

|          | Alternate<br>calculations and<br>cross checks to<br>confirm that the<br>calculation of<br>construction<br>emissions is fairly<br>presented.  | Projects to<br>Emissions<br>Agreemer<br>Crown da<br>March 200<br>Project Ag<br>Amendme<br>dated 10 x<br>2005<br>Project Ag<br>Amendme<br>dated 18 x<br>2008 | s<br>nt with the<br>ted 29<br>04<br>greement<br>ent 1<br>June<br>greement<br>ent 2 | Alternate check<br>calculations were<br>performed and it<br>can be confirmed<br>that the calculation<br>of construction<br>emissions is fairly<br>presented. |
|----------|--|---|--|--|
|          |  | 2010 Ann<br>Report to<br>submitted<br>Ministry fo<br>Environm<br>Zealand (<br>version) d<br>April 2011  | be<br>to the<br>or the<br>ent, New<br>revised<br>lated 1                           |  |
| Findings | Construction and commissioning of the project activity<br>continued during 2010 reporting period. Iron and steel, and<br>aluminium and cement have been introduced as construction<br>materials. This is, in the opinion of the verifier, reasonable for<br>this type of construction.<br>The following construction emission factors were used<br>according to Schedule 2 of the Project Agreement: |   |  |  |
|          | Material   |   | Emission   | factor   |
|          | Cement   |   | 0.48 tonn  | es CO <sub>2</sub> -e/tonne  |
|          | Iron and steel   |   | 1.95 tonn  | es CO <sub>2</sub> -e/tonne  |
|          | Aluminium  |   | 1.74 tonn  | es CO <sub>2</sub> -e/tonne  |
|          | The mathematical calculation of emission reductions is in accordance with Schedule 2 and fairly stated. The emission factors and project activity parameters are correctly applied.  |   |  | ed. The emission   |
|          | Major construction works of Rotokawa (Nga Awa Purua)<br>Geothermal power plants were completed during 2008 and<br>2009. 2010 Annual Report includes construction emissions<br>from 2008 and 2009 PRE Annual Reports which were accepted<br>by MfE.   |   |  |  |
|          | Following construction emissions from 2008 and 2009 has been reported in 2010 Annual Report:   |   |  | 8 and 2009 has   |
|          | PRE Annual Report  | t   | Emissions  | s t CO <sub>2</sub> -e   |
|          |  |   |  |  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 24 Annual Report

|            | 2009<br>2008   | 30 736.0       26 018.5   |
|------------|--|---|
|            | Total construction emissions du estimated 56 754.5 t $CO_2$ -e, wh reasonable for this kind of constactors have been used to estim during 2008 and 2009 as per So Agreement. | ich is in the opinion of verifier<br>truction. Appropriate emissions<br>nate construction emissions |
| Conclusion | This is, in the opinion of the ver geothermal-based power gener  |   |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 25 Annual Report

Prepared by Noim Uddin, DNV Australia on 21/03/2011

| Criteria Item 5<br>verified | Metering and recording equipment installed has been certified by an independent reputable quality assured service provider.          |   |   |
|-----------------------------|--|---|---|
| Description of requirement  | That the metering and recording equipment installed has been certified by an independent reputable quality assured service provider. |   |   |
| Verification procedures     | Verification item  | Information<br>Source/Evidence  | Comments  |
|                             | Examination of<br>calibration and<br>maintenance<br>certificates to<br>ensure that they<br>are current.                              | On-site visit 16-17<br>March 2011<br>Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004<br>Project Agreement<br>Amendment 1<br>dated 10 June 2005<br>Project Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011<br>Following<br>calibration<br>certificates were<br>checked:<br>Rotokawa<br>Geothermal Project<br>Nga Awa Purua –<br>11kV Revenue<br>Meter, Power<br>Logic, ION 8600<br>('ION') Calibration<br>Report by AccuCal<br>(CAL-2009-255),<br>10/09/2009 (valid | Calibration<br>certificates of<br>revenue meter<br>'ION' and check<br>meter 'Nexus' were<br>examined and<br>certificates were<br>found to be valid for<br>the 2010 reporting<br>period.<br>Calibration<br>certificates of HP,<br>IP and LP steam<br>supply flow meters<br>(venturi meters)<br>were found to be<br>valid for the 2010<br>reporting period.<br>Institute of<br>Geological and<br>Nuclear Sciences<br>(GNS) Waikerakei<br>Analytical<br>Laboratory is an<br>Accredited<br>Laboratory under<br>International<br>Accreditation New<br>Zealand. |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 26 Annual Report

| till 10/09/2012).   |
|---|
| Rotokawa<br>Geothermal Project<br>Nga Awa Purua –<br>11kV Check, Nexus<br>1262 ('Nexus')<br>Calibration Report<br>by AccuCal (CAL-<br>2009-256),<br>11/09/2009 (valid<br>till 11/09/2012) |
| Rotokawa<br>Geothermal HP<br>Steam Flow Meter<br>(91J302006 910<br>XJEJA110A-426)<br>Test Certificate by<br>Fuji Electric<br>Systems Co. Ltd,<br>dated 08/01/2010                         |
| Rotokawa<br>Geothermal IP<br>Steam Flow Meter<br>(91J302007 910<br>XJEJA110A-425)<br>Test Certificate by<br>Fuji Electric<br>Systems Co. Ltd,<br>dated 08/01/2010                         |
| Rotokawa<br>Geothermal LP<br>Steam Flow Meter<br>(91J301997 910<br>XJEJA110A-425)<br>Test Certificate by<br>Fuji Electric<br>Systems Co. Ltd,<br>dated 08/01/2010                         |
| Certificate of<br>Accreditation,<br>Institute of<br>Geological and<br>Nuclear Sciences<br>(GNS), Chemical<br>Testing Laboratory,<br>dated 17 August<br>2001                               |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 27 Annual Report

|   |   | I  |
|---|---|--|
| Examination of<br>installed<br>instruments to<br>confirm that the<br>installed<br>instruments are<br>those covered by<br>the calibration<br>certificates. | On-site visit 16-17<br>March 2011<br>Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004<br>Project Agreement<br>Amendment 1<br>dated 10 June 2005<br>Project Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011<br>Following<br>calibration<br>certificates were<br>checked:<br>Rotokawa<br>Geothermal Project<br>(Nga Awa Purua –<br>11kV Revenue<br>Meter, Power<br>Logic, ION 8600)<br>Calibration Report<br>by AccuCal (CAL-<br>2009-255),<br>10/09/2009 (valid<br>till 10/09/2012)<br>Rotokawa<br>Geothermal Project<br>(Nga Awa Purua –<br>11kV Check, Nexus<br>1262) Calibration<br>Report by AccuCal<br>(CAL-2009-256),<br>11/09/2009 (valid<br>till 11/09/2012)<br>Rotokawa | The installed<br>revenue meter and<br>check meter were<br>examined during<br>the site visit and it<br>was found that the<br>installed meters are<br>covered by the<br>calibration<br>certificates.<br>HP, IP and LP<br>steam supply flow,<br>meters were<br>examined during<br>site visit and it was<br>found that the<br>installed<br>instruments are<br>covered by the<br>calibration<br>certificates. |
|   | Geothermal HP   | (a) Coothormal 2010 29   |

PRE Programme Independent Verification Report for Rotokawa (Nga Awa Purua) Geothermal 2010 28 Annual Report

|   | Steam Flow Meter<br>(91J302006 910<br>XJEJA110A-426)<br>Test Certificate by<br>Fuji Electric<br>Systems Co. Ltd,<br>dated 08/01/2010.<br>Rotokawa<br>Geothermal IP<br>Steam Flow Meter<br>(91J302007 910<br>XJEJA110A-425)<br>Test Certificate by<br>Fuji Electric<br>Systems Co. Ltd,<br>dated 08/01/2010<br>Rotokawa<br>Geothermal LP<br>Steam Flow Meter<br>(91J301997 910<br>XJEJA110A-425)<br>Test Certificate by<br>Fuji Electric<br>Systems Co. Ltd,<br>dated 08/01/2010 |  |
|---|---|--|
| Confirmation that<br>the calibration<br>agency is<br>appropriately<br>qualified and<br>accredited for the<br>instruments which<br>have been<br>calibrated | Agency<br>Accreditation scope   | AccuCal is<br>registered with the<br>Electricity<br>Commission as a<br>class A approved<br>test house.<br>The calibration test<br>is performed by<br>AccuCal according<br>to the Australian<br>National Standards<br>of Measurement.<br>Institute of<br>Geological and<br>Nuclear Sciences<br>(GNS), Chemical<br>Testing Laboratory,<br>is an Accredited<br>Laboratory under<br>International<br>Accreditation New<br>Zealand. |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 29 Annual Report

| Findings   | The metering and recording equipment was found to be<br>appropriate for its purpose and appeared to be in good<br>operating condition.<br>Calibration of the revenue meter and check meter were<br>completed by AccuCal.<br>AccuCal is an appropriately qualified and accredited agency to<br>perform calibration tests for the revenue meters installed at<br>Rotokawa (Nga Awa Purua) Geothermal Power Plant. |
|------------|---|
| Conclusion | Metering and recording equipment installed have been certified<br>by an independent reputable quality assured service provider.<br>Copies of all calibration certificates are maintained by Mighty<br>River Power Ltd.  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 30 Annual Report

| Criteria Item 6<br>verified | Any other (electricity, heat) generation, not part of the project,<br>that flows through these meters is identified, measured and<br>subtracted from the gross total.   |  |  |
|-----------------------------|---|--|--|
| Description of requirement  | That any other (electricity, heat) generation, not part of the project, that flows through these meters is indentified, measured and subtracted fro the gross total and fairly stated.  |  |  |
| Verification procedures     | Verification item   | Information<br>Source/Evidence   | Comments   |
|                             | Review of the<br>process and<br>instrumentation<br>diagram and<br>electricity metering<br>diagram of the<br>project to confirm<br>the presence or<br>absence of other<br>energy flows<br>through the project<br>metering<br>installation. | On-site visit 16-17<br>March 2011<br>Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004<br>Project Agreement<br>Amendment 1<br>dated 10 June 2005<br>Project Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual Report<br>to be submitted to<br>the Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011<br>Nga Awa Purua<br>Geothermal Power<br>Plant, Relay and<br>Instrument Diagram<br>(Generation Main<br>Circuit), NAP-FE-<br>ER-DG-1001, WA<br>48132, 27 June<br>2007, Fuji Electric<br>Systems Co. Ltd.<br>Nga Awa Purua<br>Steam-Flow<br>Measurement<br>Points, Nga Awa<br>Purua – Steam | Rotokawa (Nga<br>Awa Purua)<br>Geothermal Power<br>Plant generates<br>electricity by using<br>geothermal steam.<br>Rotokawa (Nga<br>Awa Purua)<br>Geothermal imports<br>electricity from the<br>national grid (which<br>is not part of the<br>project) which flows<br>through the<br>revenue meter.<br>There is no<br>additional energy<br>(electricity or gas)<br>flowing through the<br>project metering<br>installation other<br>than imported<br>electricity as<br>identified in the<br>project boundary.<br>The electricity<br>meter is not shared<br>with any other<br>electricity<br>generation facility.<br>No other pipeline<br>except the HP, IP,<br>LP steam supply<br>lines are connected<br>to turbine. |

PRE Programme Independent Verification Report for Rotokawa (Nga Awa Purua) Geothermal 2010 31 Annual Report

|   | Metering, Mighty   |   |
|---|--|---|
|   | River Power Ltd.   |   |
| Consideration of the nature and   | On-site visit 16-17<br>March 2011  | Rotokawa (Nga<br>Awa Purua)   |
| design of the project.  | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004  | Geothermal Power<br>Plant generates<br>electricity by using<br>geothermal steam.  |
|   | Project Agreement<br>Amendment 1<br>dated 10 June 2005   |   |
|   | Project Agreement<br>Amendment 2<br>dated 18 February<br>2008  |   |
|   | 2010 Annual Report<br>to be submitted to<br>the Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011 |   |
| Review of the record keeping  | On-site visit 16-17<br>March 2011  | Not applicable as:  |
| process to confirm<br>that the metered<br>data is accurately<br>measured and<br>recorded. | Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004  | There is no<br>additional energy<br>(electricity or gas)<br>flowing through the<br>project metering<br>installation other |
|   | Project Agreement<br>Amendment 1<br>dated 10 June 2005   | than imported<br>electricity as<br>identified in the  |
|   | Project Agreement<br>Amendment 2<br>dated 18 February<br>2008  | project boundary.<br>The electricity<br>meter is not shared<br>with any other   |
|   | 2010 Annual Report<br>to be submitted to<br>the Ministry for the   | electricity<br>generation facility.   |
|   | Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011   | No other pipeline<br>except the HP, IP,<br>LP steam supply<br>lines are connected<br>to turbine.                          |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 32 Annual Report

| Review of the<br>metering<br>arrangements to<br>confirm that the<br>measurements of<br>other energy flows<br>truly represent<br>those flows.  | On-site visit 16-17<br>March 2011<br>Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004<br>Project Agreement<br>Amendment 1<br>dated 10 June 2005<br>Project Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual Report<br>to be submitted to<br>the Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011<br>Nga Awa Purua<br>Geothermal Power<br>Plant, Relay and<br>Instrument Diagram<br>(Generation Main<br>Circuit), NAP-FE-<br>ER-DG-1001, WA<br>48132, 27 June<br>2007, Fuji Electric<br>Systems Co. Ltd<br>Nga Awa Purua<br>Steam-Flow<br>Measurement<br>Points, Nga Awa<br>Purua – Steam<br>Metering, Mighty<br>River Power Ltd | Not applicable as:<br>There is no<br>additional energy<br>(electricity or gas)<br>flow through the<br>project metering<br>installation other<br>than imported<br>electricity as<br>identified in the<br>project boundary.<br>The electricity<br>meter is not shared<br>with any other<br>electricity<br>generation facility.<br>No other pipeline<br>except the HP, IP,<br>LP steam supply<br>lines are connected<br>to turbine. |
|---|--|--|
| Review of the<br>energy calculation<br>methodology to<br>confirm that any<br>other energy flows<br>has been correctly<br>subtracted and that<br>the final result truly<br>reflects the net<br>energy flow | On-site visit 16-17<br>March 2011<br>Projects to Reduce<br>Emissions<br>Agreement with the<br>Crown dated 29<br>March 2004<br>Project Agreement<br>Amendment 1   | Not applicable as:<br>There is no<br>additional energy<br>(electricity or gas)<br>flowing through the<br>project metering<br>installation other<br>than imported<br>electricity as   |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 33 Annual Report

|            | attributable to the project.   | dated 10 June 2005<br>Project Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual Report<br>to be submitted to<br>the Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011 | identified in the<br>project boundary.<br>The electricity<br>meter is not shared<br>with any other<br>electricity<br>generation facility.<br>A total of 0.88 GWh<br>of electricity is<br>imported by<br>Rotokawa (Nga<br>Awa Purua)<br>Geothermal Power<br>Plant during<br>01/01/2010 to<br>31/12/2010. |
|------------|--|---|---|
| Findings   |  | bort amount (996.72 G<br>attributable to the proje  | , ,   |
| Conclusion | The total electricity imported by Rotokawa (Nga Awa Purua)<br>Geothermal Power Plant was measured by a revenue meter<br>which does not share any other electricity flow. |   |   |

| Criteria Item 7<br>verified | If applicable, the record of emissions as a result of the operation of the project is fairly stated |   |   |
|-----------------------------|---|---|---|
| Description of requirement  | That the record of emissions as a result of operation of the project is fairly stated.              |   |   |
| Verification procedures     | Verification item   | Information<br>Source/Evidence  | Comments  |
|                             | Confirm that the calculation uses the correct emission factors.                                     | On-site visit 16-17<br>March 2011<br>Projects to<br>Reduce<br>Emissions<br>Agreement with<br>the Crown dated<br>29 March 2004                 | All emissions<br>factors used<br>(emission due to<br>operation of the<br>Rotokawa (Nga<br>Awa Purua)<br>Geothermal Power<br>Plant) in the<br>emission reduction |
|                             |   | Project<br>Agreement<br>Amendment 1<br>dated 10 June<br>2005  | calculation are<br>sourced from<br>Schedule 2 of the<br>Project Agreement.  |
|                             |   | Project<br>Agreement<br>Amendment 2<br>dated 18 February<br>2008  |   |
|                             |   | 2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011 |   |
|                             | Confirmation that all<br>appropriate<br>operational activities<br>have been included.               | On-site visit 16-17<br>March 2011<br>Projects to<br>Reduce<br>Emissions<br>Agreement with<br>the Crown dated<br>29 March 2004                 | The following<br>operational<br>activities were<br>required to be<br>monitored<br>according to the<br>Schedule 2 of the<br>Project Agreement:                   |
|                             |   | Project<br>Agreement<br>Amendment 1   | <ul> <li>Quantities of<br/>diesel and petrol<br/>used during</li> </ul>   |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 35 Annual Report

|   | dated 10 June<br>2005<br>Project<br>Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011   | <ul> <li>operation of the project activity.</li> <li>Quantities of cement, aluminium and iron and steel as construction materials introduced or used during operation of the project activity.</li> <li>Meter and record the quantity of electricity purchased.</li> <li>Amount of CO<sub>2</sub> in geothermal steam.</li> </ul>  |
|---|--|--|
| Review of the record<br>keeping<br>arrangements to<br>confirm that the<br>measured quantities<br>of operational<br>materials are a fair<br>presentation of actual<br>usage. | On-site visit 16-17<br>March 2011<br>Projects to<br>Reduce<br>Emissions<br>Agreement with<br>the Crown dated<br>29 March 2004<br>Project<br>Agreement<br>Amendment 1<br>dated 10 June<br>2005<br>Project<br>Agreement<br>Amendment 2<br>dated 18 February<br>2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011 | Diesel and petrol<br>used during the<br>operation of the<br>Rotokawa (Nga<br>Awa Purua)<br>Geothermal Power<br>Plant was recorded<br>by contractors and<br>maintained by<br>Mighty River Power<br>Ltd.<br>Rotokawa (Nga<br>Awa Purua)<br>Geothermal imports<br>electricity from the<br>national grid. A total<br>of 0.88 GWh of<br>electricity was<br>imported from the<br>national grid. This<br>has been measured<br>by the revenue<br>meter and data has<br>been provided by<br>Half Hour Data<br>Administrator<br>Mighty River Power<br>Ltd. |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 36 Annual Report

| <br>  |   |   |
|---|---|---|
|   |   | The molecular<br>weight of CO <sub>2</sub><br>present in the<br>geothermal steam<br>was determined by<br>the Wairakei<br>Analytical<br>Laboratory. The<br>amount of CO <sub>2</sub><br>(tonnes) in steam<br>has been calculated<br>by Mighty River<br>Power Ltd.  |
| The exercise of<br>professional<br>judgement in relation<br>to whether the<br>claimed quantity of<br>operational materials<br>was reasonable. | On-site visit 16-17<br>March 2011<br>Projects to<br>Reduce<br>Emissions<br>Agreement with<br>the Crown dated<br>29 March 2004<br>Project<br>Agreement<br>Amendment 1<br>dated 10 June<br>2005<br>Project<br>Agreement<br>Amendment 2<br>dated 18 February<br>2008.<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011 | All monitoring of<br>project operational<br>data (diesel and<br>petrol use,<br>electricity purchase<br>and amount of CO <sub>2</sub><br>in geothermal<br>steam) records are<br>kept electronically.<br>In the opinion of the<br>verifier the data is a<br>fair presentation of<br>the actual<br>requirement of<br>diesel and petrol<br>use, electricity<br>purchase and<br>presence of CO <sub>2</sub> in<br>geothermal steams. |
| Alternate calculations<br>and cross checks to<br>confirm that the<br>calculation of<br>operation emissions<br>is fairly presented.            | On-site visit 16-17<br>March 2011<br>Projects to<br>Reduce<br>Emissions<br>Agreement with<br>the Crown dated<br>29 March 2004<br>Project  | Cross checking of<br>sample raw data<br>with the emission<br>reduction<br>calculation<br>methodology was<br>performed.<br>The verifier found<br>that the calculation  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 37 Annual Report

|            |   | Agreement<br>Amendment 1<br>dated 10 June<br>2005<br>Project<br>Agreement<br>Amendment 2<br>dated 18 February<br>2008.<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment, New<br>Zealand (revised<br>version) dated 1<br>April 2011 | of operation<br>emissions is fairly<br>presented. |
|------------|---|---|---|
| Findings   | All operational activities were duly included in the emission reduction calculation. The record keeping arrangement was found to be satisfactory. |   |   |
| Conclusion | The record of emissions as a result of the operation of the project is fairly stated.   |   |   |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 38 Annual Report

| Criteria Item 8<br>verified | The participant has justified and documented any significant<br>changes to the PRE project and its baseline scenario that lead<br>to material change in the project's emissions, removals and<br>emission reductions since the previous verification, and which<br>affect the projects ability to conform to the principles, and<br>requirements of the PRE project. |   |   |
|-----------------------------|--|---|---|
| Description of requirement  | Identify any additional requirements related to the PRE Project<br>Agreement which require verification and verify those<br>requirements   |   |   |
| Verification<br>procedures  | Verification item  | Information<br>Source/Evidence  | Comments  |
|                             | Rotokawa (Nga<br>Awa Purua)<br>Geothermal<br>Power Plant<br>installed capacity<br>and use of<br>geothermal<br>steam.   | On-site visit 16-17<br>March 2011<br>Projects to<br>Reduce<br>Emissions<br>Agreement with<br>the Crown dated<br>29 March 2004<br>Project<br>Agreement<br>Amendment 1<br>dated 10 June<br>2005<br>Project<br>Agreement<br>Amendment 2<br>dated 18<br>February 2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment,<br>New Zealand<br>(revised version)<br>dated 1 April 2011<br>Nameplate<br>Capacities of<br>Turbine and<br>Generator<br>Resource<br>Consent 116565<br>(File No. 60 24 | Rotokawa (Nga Awa<br>Purua) Geothermal<br>Power Plant with a<br>capacity of 130 MW<br>has been built as an<br>additional renewable<br>electricity generation<br>facility using<br>geothermal steam<br>according to the<br>Project Agreement<br>and Amendments to<br>the Project<br>Agreement. This<br>capacity was<br>confirmed from the<br>nameplate capacity of<br>the turbine and<br>generator during the<br>on-site inspection.<br>Rotokawa (Nga Awa<br>Purua) Geothermal<br>Power Plant used an<br>average of 60 879<br>tonnes of geothermal<br>steam per day during<br>2010 as evidenced<br>from Rotokawa<br>Steamfield Data 2010,<br>which is around 85%<br>of the maximum<br>consented amount (70<br>500 tonnes per day). |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 39 Annual Report

|            |  | 47RC, dated<br>23/01/2008),<br>Environment<br>Waikato<br>Rotokawa<br>Steamfield Data<br>2010 (dated 16<br>March 2011),<br>from Alex Lawson |                    |
|------------|--|--|--------------------|
| Findings   | Rotokawa (Nga Awa Purua) Geothermal Power Plant has<br>been built according to the Project Agreement.<br>Rotokawa (Nga Awa Purua) Geothermal Power Plant uses<br>geothermal steam below the consent level. |  |                    |
| Conclusion | Currently there are baseline remains s   | no changes to the P<br>ame.  | RE project and its |

| Criteria Item 9<br>verified | Within the context of verification, any other requirement relating to the PRE project Agreement.  |   |  |
|-----------------------------|---|---|--|
| Description of requirement  | Identify any additional requirements related to the PRE Project<br>Agreement which require verification and verify those<br>requirements          |   |  |
| Verification<br>procedures  | Verification item   | Information<br>Source/Evidence  | Comments   |
|                             | Rotokawa (Nga<br>Awa Purua)<br>Geothermal<br>Power Plant<br>project has been<br>built according to<br>the Project<br>Agreement and<br>Amendments. | Projects to<br>Reduce<br>Emissions<br>Agreement with<br>the Crown dated<br>29 March 2004<br>Project<br>Agreement<br>Amendment 1<br>dated 10 June<br>2005<br>Project<br>Agreement<br>Amendment 2<br>dated 18<br>February 2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment,<br>New Zealand<br>(revised version)<br>dated 1 April 2011 | Rotokawa (Nga Awa<br>Purua) Geothermal<br>Power Plant has been<br>built according to<br>Clause 6 of the<br>Project Agreement<br>Amendment 2 dated<br>18 February 2008.<br>All PRE project<br>Agreement<br>requirements have<br>been met. |
| Findings                    | All requirements under the PRE Project Agreement are met.   |   |  |
| Conclusion                  | There are no other requirements relating to the PRE Project Agreement that have not been met.   |   |  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 41 Annual Report

| Criteria Item 10<br>verified | The participant has adequate understanding of the principles<br>and requirements of the PRE programme and is competent to<br>conform to those principles and requirements.                |   |   |
|------------------------------|---|---|---|
| Description of requirement   | Identify any additional requirements related to the PRE Project<br>Agreement which require verification and verify those<br>requirements  |   |   |
| Verification<br>procedures   | Verification item   | Information<br>Source/Evidence  | Comments  |
|                              | Meeting and<br>interviewing<br>Rotokawa (Nga<br>Awa Purua)<br>Geothermal<br>Power Plant<br>project activity<br>personnel,<br>monitoring<br>personnel and<br>management<br>representative. | Projects to<br>Reduce<br>Emissions<br>Agreement with<br>the Crown dated<br>29 March 2004<br>Project<br>Agreement<br>Amendment 1<br>dated 10 June<br>2005<br>Project<br>Agreement<br>Amendment 2<br>dated 18<br>February 2008<br>2010 Annual<br>Report to be<br>submitted to the<br>Ministry for the<br>Environment,<br>New Zealand<br>(revised version)<br>dated 1 April 2011 | <ul> <li>During the on-site visit<br/>interviews were held<br/>with the following<br/>Mighty River power<br/>Ltd personnel:</li> <li>Aaron Smith,<br/>Carbon Analyst</li> <li>Alex Lawson,<br/>Geothermal<br/>Technician<br/>(Maintenance)</li> <li>Alan Ofsoski,<br/>Contract Manager</li> <li>Aaron Smith has been<br/>responsible for Mighty<br/>River Power Ltd's<br/>carbon business.<br/>Aaron has been<br/>responsible for the<br/>monitoring and<br/>reconciliation of the<br/>monitored<br/>parameters, reporting<br/>and compliance under<br/>PRE requirements.<br/>He has a good<br/>understanding of<br/>carbon credit<br/>management,<br/>geothermal power<br/>plant monitoring and<br/>controls.</li> </ul> |
|                              |   | for Rotokawa (Nga Awa   | been responsible for the operation and  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua)* Geothermal 2010 42 Annual Report

|            |  |  | monitoring of the<br>project activity since<br>its inception. He has a<br>very good<br>understanding of<br>geothermal power<br>plant operation,<br>monitoring, controls<br>and requirements for<br>conforming to<br>resource consent<br>requirements.<br>Alan Ofsoski has<br>been responsible for<br>the overall inventory<br>management of<br>Rotokawa (Nga Awa<br>Purua) Geothermal<br>Project (operation and<br>maintenance). He has<br>a comprehensive<br>understanding of PRE<br>reporting<br>requirements.<br>All project personnel<br>are competent to<br>conform to the PRE<br>requirements. |
|------------|--|--|--|
| Findings   | Project personnel and monitoring personnel have a deep<br>understanding of the PRE project and its requirement.  |  |  |
| Conclusion | It is the opinion of the verifier that the participant has an adequate understanding of the principles and requirements of the PRE programme and is competent to conform to those principles and requirements. |  |  |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* **43** Annual Report

| Criteria Item 11<br>verified | Compliance with the regulatory requirements of local and central government agencies.   |   |  |
|------------------------------|---|---|--|
| Description of requirement   | That nothing came to the notice of the verifier to indicate that<br>the project was not compliant with the regulatory requirements<br>of local and central government agencies. |   |  |
| Verification procedures      | Verification item   | Information<br>Source/Evidence  | Comments   |
|                              | Review compliance<br>conditions made<br>within the Resource<br>Consent or other<br>regulatory<br>approvals.   | The following<br>major resource<br>consent<br>certificates<br>issued by the<br>Environment<br>Waikato were<br>examined and<br>found valid:<br>Resource<br>Consent No<br>116565 dated<br>23/01/2008<br>(ground Water<br>take)<br>Resource<br>Consent No<br>116566 dated<br>23/01/2008<br>(discharge permit<br>– discharge to<br>land)<br>Resource<br>Consent No<br>116567 dated<br>23/01/2008<br>(discharge permit<br>– discharge permit<br>– discharge to<br>air) | Resource Consents<br>ground water take,<br>discharge permits –<br>discharge to land<br>and air, have been<br>granted to Rotokawa<br>Joint Venture Limited<br>(Mighty River Power<br>Ltd) to construct<br>Rotokawa (Nga Awa<br>Purua) Geothermal<br>Power Plant by the<br>Environment<br>Waikato and are<br>valid for 35 years<br>until 23 January<br>2043. |
|                              | Review<br>correspondence<br>between the local<br>authorities and the<br>project operator to<br>evaluate<br>compliance with  | The following<br>documents were<br>evidenced as<br>monitoring of<br>resource<br>consent:  | Rotokawa Annual<br>Report and<br>monitoring of air<br>discharge and<br>reservoir indicate<br>that Resource<br>Consent Nos.   |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 44 Annual Report

| requirements.   | Rotokawa Annual<br>Report July<br>2009-June 2010,<br>Mighty River<br>Power Ltd<br>Monitoring of Air<br>Discharge,<br>Mighty River<br>Power Ltd<br>Rotokawa<br>Reservoir | 116567 and 116565 are in compliance.   |
|---|---|--|
|   | Monitoring,<br>December 2010,<br>Century Drilling &<br>Energy Services<br>(NZ) Limited  |  |
| Review the<br>activities at the site<br>to confirm that the<br>project<br>arrangements are<br>generally compliant<br>with regulatory<br>requirements. | On-site visit 16-<br>17 March 2011<br>Resource<br>Consent No<br>116565 dated<br>23/01/2008<br>(ground Water<br>take)  | There were no<br>observations made<br>during the site visit to<br>indicate that the<br>project<br>arrangements were<br>not compliant with<br>regulatory<br>requirements as |
|   | Resource<br>Consent No<br>116566 dated<br>23/01/2008<br>(discharge permit<br>– discharge to<br>land)  | specified in the<br>Resource Consents.   |
|   | Resource<br>Consent No<br>116567 dated<br>23/01/2008<br>(discharge permit<br>– discharge to<br>air)   |  |
| Confirm that project<br>monitoring includes<br>relevant regulatory<br>and compliance<br>conditions.   | On-site visit 16-<br>17 March 2011<br>Resource<br>Consent No<br>116565 dated<br>23/01/2008<br>(ground Water   | Mighty River Power<br>Ltd personnel have<br>confirmed that the<br>Project meets the<br>following<br>requirements:  |
|   |   | Resource Consent<br>No 116565 – the rate   |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* 45 Annual Report

| Findings | There were no observ<br>that the project arrang<br>requirements as spec<br>Mighty River Power L | land)<br>Resource<br>Consent No<br>116567 dated<br>23/01/2008<br>(discharge permit<br>– discharge to<br>air)<br>ations made during the<br>ements are not comp<br>ified in the Resource | day<br>In the opinion of the<br>verifier that Mighty<br>River Power Ltd<br>maintains monitoring<br>relevant regulatory<br>and compliance<br>conditions.<br>The site visit to indicate<br>pliant with regulatory<br>Consents. |
|----------|---|--|--|
|          |   | Resource   | In the opinion of the  |
|          |   | take)<br>Resource<br>Consent No  | of geothermal water<br>take up to a<br>maximum 70 500<br>tonnes per day.   |

| 3 Documents Reviewed  | 4 Please include author, date prepared and date reviewed by Verifier   |  |
|---|--|--|
| 2010 Annual Report to be<br>submitted to the Ministry for<br>the Environment, New<br>Zealand (revised version)<br>dated 1 April 2011. | Aaron Smith, prepared on 1 April 2011, verified in<br>March/April 2011 |  |
| 2009 Annual Report<br>submitted to the Ministry for<br>the Environment, New<br>Zealand (6 December 2010)                              | Aaron Smith, prepared on 6 December 2010, verified in March 2011       |  |
| 2009 Annual Report<br>submitted to the Ministry for<br>the Environment, New<br>Zealand (16 April 2009)                                | John Gary, prepared on 16 April 2009, verified in<br>March 2011        |  |
| Projects to Reduce Emissions<br>Agreement with the Crown  | The Crown, dated 29 March 2004, verified in March 2011                 |  |
| Project Agreement<br>Amendment 1  | The Crown, dated 10 June 2005, verified in March 2011                  |  |
| Project Agreement<br>Amendment 2  | The Crown, dated 18 February 2010, verified in March 2011              |  |

| 5 Site Visit location                              | 6 Address, date of visit, personnel<br>interviewed  |
|--|---|
| Rotokawa (Nga Awa Purua)<br>Geothermal Power Plant | <ul> <li>Address: Taupo</li> <li>Date of visit: 16-17 March 2011</li> <li>Personnel interviewed: <ul> <li>Aaron Smith, Mighty River Power Ltd.</li> </ul> </li> <li>Alex Lawson, Mighty River Power Ltd</li> <li>Alan Ofsoski, Mighty River Power Ltd (via teleconference)</li> <li>Catherine Schofield, Senior Analyst, Funds Management, Ministry for the Environment.</li> <li>Firuza Mukhamedjanova, Analyst, Funds Management, Ministry for the Environment</li> </ul> |

PRE Programme Independent Verification Report for *Rotokawa (Nga Awa Purua) Geothermal 2010* **47** Annual Report